


BOUNDARY SURVEY


GRAPHIC SCALE



(IN FEET)
1 inch = 20 ft.



LOCATION SKETCH N.T.S.



TREE TABLE

No.	TREE NAME	DIAMETER (')	HEIGHT (')	SPREAD (')
1	FICUS	6.00	30.00	20.00
2	PALM CLUSTER	1.20	40.00	20.00
3	PALM TREE	2.00	15.00	15.00
4	PALM TREE	3.00	30.00	25.00
5	PALM TREE	3.00	30.00	25.00
6	PALM TREE	1.50	15.00	10.00
7	PALM TREE	1.50	15.00	10.00
8	PALM TREE	1.50	15.00	10.00
9	GUANAVANA	0.90	15.00	10.00
10	PALM TREE	0.90	6.00	6.00
11	PALM CLUSTER	1.40	30.00	10.00
12	PALM CLUSTER	1.20	20.00	15.00
13	PALM CLUSTER	1.20	20.00	15.00
14	PALM CLUSTER	1.20	20.00	15.00
15	PALM CLUSTER	1.20	20.00	15.00
16	PALM CLUSTER	1.20	20.00	15.00
17	PALM CLUSTER	1.20	20.00	15.00
18	PALM TREE	2.00	25.00	7.00
19	PALM TREE	2.00	25.00	7.00
20	PALM TREE	2.00	25.00	7.00
21	PALM TREE	2.00	25.00	7.00
22	UNKNOWN	0.90	30.00	10.00
23	BLACK OLIVE	0.90	15.00	30.00
24	BLACK OLIVE	0.90	15.00	30.00
25	BLACK OLIVE	0.90	15.00	30.00

LEGAL DESCRIPTION:

SURVEY OF LOT 8, BLOCK 3, OF FIRST ADDITION TO MID GOLF SUBDIVISION
ACCORDING TO THE PLAT THEREOF AS RECORDED IN THE PLAT BOOK 7,
PAGE 161, OF THE PUBLIC RECORDS OF MIAMI-DADE COUNTY, FLORIDA.

PROPERTY ADDRESS:

2840 PRAIRIE AVE
MIAMI BEACH, FL 33140

CERTIFICATIONS:

DOUGLAS F EATON & W MOLLY A OSENDORF

SURVEYOR'S NOTES:

- 1). IF SHOWN, BEARINGS ARE REFERRED TO AN ASSUMED MERIDIAN, BY SAID PLAT IN THE DESCRIPTION OF THE PROPERTY. IF NOT, THEN BEARINGS ARE REFERRED TO COUNTY, TOWNSHIP MAPS.
- 2). IF SHOWN, ELEVATIONS ARE REFERRED TO MIAMI-DADE COUNTY, BM # D-131 ELEV. 8.73 FEET OF N.G.V.D. OF 1929. LOCATOR No.3234NE,
- 3). THE CLOSURE IN THE BOUNDARY SURVEY IS ABOVE 1:7500 FT.

I HEREBY CERTIFY: THAT THIS "BOUNDARY SURVEY" OF THE PROPERTY DESCRIBED HEREON, AS RECENTLY SURVEYED AND DRAWN UNDER MY SUPERVISION, COMPLIES WITH THE MINIMUM TECHNICAL STANDARDS AS SET FORTH BY THE FLORIDA BOARD OF PROFESSIONAL LAND SURVEYORS IN CHAPTER 61G17-6, FLORIDA ADMINISTRATIVE CODE PURSUANT TO 472.027, FLORIDA STATUTES.

LEGAL NOTES TO ACCOMPANY SKETCH OF SURVEY (SURVEY):

- EXAMINATIONS OF THE ABSTRACT OF TITLE WILL HAVE TO BE MADE TO DETERMINE RECORDED INSTRUMENTS, IF ANY, AFFECTING THE PROPERTY.
- THIS SURVEY IS SUBJECT TO DEDICATIONS, LIMITATIONS, RESTRICTIONS, RESERVATIONS OR EASEMENTS OF RECORD.
- LEGAL DESCRIPTION PROVIDED BY CLIENT OR ATTESTING TITLE COMPANY.
- BOUNDARY SURVEY MEANS A DRAWING AND/ OR A GRAPHIC REPRESENTATION OF THE SURVEY WORK PERFORMED IN THE FIELD, COULD BE DRAWN AT A SHOWN SCALE AND OR NOT TO SCALE.
- EASEMENTS AS SHOWN ARE PER PLAT BOOK, UNLESS OTHERWISE NOTED.
- THE TERM "ENCROACHMENT" MEANS VISIBLE ON AND ABOVE GROUND ENCROACHMENT.
- ARCHITECTS SHALL VERIFY ZONING REGULATIONS, RESTRICTIONS AND SETBACKS AND THEY WILL BE RESPONSIBLE OF SUBMITTING PLOT PLANS WITH THE CORRECT INFORMATION FOR THEIR APPROVAL FOR AUTHORIZATION TO AUTHORITIES IN A NEW CONSTRUCTIONS, UNLESS OTHERWISE NOTED, THIS FIRM HAS NOT ATTEMPTED TO LOCATE FOOTING AND/OR FOUNDATIONS.
- FENCE OWNERSHIP NOT DETERMINED.
- THIS PLAN OF SURVEY, HAS BEEN PREPARED FOR THE EXCLUSIVE USE OF THE ENTITIES NAMED HEREON, THE CERTIFICATE DOES NOT EXTEND TO ANY UNNAMED PARTY.
- THE FNIP FLOOD MAPS HAVE DESIGNATED THE HEREIN DESCRIBED LAND TO BE SITUATED IN ZONE: "X" COMMUNITY/PANEL/SUFFIX: 120651/0184/1 DATE OF FIRM: 09/11/2009
- BASE FLOOD ELEVATION: 8 FEET.

ABBREVIATIONS AND MEANINGS

A = ARC
A/C = AIR CONDITIONER PAD.
A.E. = ANCHOR EASEMENT.
A/R = ALUMINUM ROOF.
A/S = ALUMINUM SHED.
ASPH. = ASPHALT.
B.C. = BLOCK CORNER.
BLDG. = BUILDING.
B.M. = BENCH MARK
B.O.B.s = BASIS OF BEARINGS.
C = CALCULATED
C.B. = CATCH BASIN.
C.B.S. = CONCRETE BLOCK STRUCTURE.
CBW = CONCRETE BLOCK WALL.
CH. = CHORD.
CH.B. = CHORD BEARING.
CL = CLEAR
C.L.F. = CHAIN LINK FENCE.
C.M.E. = CANAL MAINTENANCE EASEMENTS.


CONC. = CONCRETE.
C.P. = CONC. PORCH.
C.S. = CONCRETE SLAB.
D.E. = DRAINAGE EASEMENT.
D.M.E. = DRAINAGE MAINTENANCE EASEMENTS
DRIVE = DRIVEWAY
* = DEGREES.
E = EAST.
E.T.P. = ELECTRIC TRANSFORMER PAD.
ELEV. = ELEVATION.
ENCR. = ENCROACHMENT.
F.H. = FIRE HYDRANT.
F.I.P. = FOUND IRON PIPE.
F.I.R. = FOUND IRON ROD.
F.F.E. = FINISHED FLOOR ELEVATION.
F.N.D. = FOUND NAIL & DISK.
FRAME.
FT = FEET.

PROP. COR. = PROPERTY CORNER
 FNIP. = FEDERAL NATIONAL INSURANCE
 F.N. = FOUND NAIL.
 H. = HIGH (HEIGHT)
 IN. E. = INCHES AND EGRESS EASEMENT.
 L.P. = LIGHT POLE
 L.F.E. = LOWEST FLOOR ELEVATION.
 L.M.E. = LAKE MAINTENANCE EASEMENT.
 ' = MINUTES.
 H. = MEASURED DISTANCE.
 MON. = MONUMENT LINE.
 M/H = MANHOLE.
 M/L = MONUMENT LINE.
 N.A.P. = NOT A PART OF.
 NGVD = NATIONAL GEODETIC VERTICAL DATUM.
 N. = NORTH.
 N.T.S. = NOT TO SCALE.
 #-NO. = NUMBER.
 O/S = OFFSET.

O.H. = OVERHEAD
O.U.L. = OVERHEAD UTILITY LINES
OVH = OVERHANG
P.W.M.T. = PAVEMENT.
PL. = PLANTER.
P/L = PROPERTY LINE.
P.C.C. = POINT OF COMPOUND CURVE.
P.C. = POINT OF CURVE.
P.T. = POINT OF TANGENCY.
P.O.C. = POINT OF COMMENCEMENT.
P.O.B. = POINT OF BEGINNING.
P.R.C. = POINT OF REVERSE CURVE
P.B. = PLAT BOOK.
PG. = PAGE.
P.W.Y. = PARKWAY.
P.F.M. = PERMANENT REFERENCE MONUMENT
P.L.S. = PROFESSIONAL LAND SURVEYOR.
R. = RECORDED DISTANCE.

RR. = RAIL ROAD.
RES. = RESIDENCE.
R/W = RIGHT-OF-WAY.
RAD. = RADIUS OF RADIAL.
R.P. = RADIUS POINT.
RGE. = RANGE.
SEC. = SECTION.
STY. = STORY.
SWK. = SIDEWALK.
S.I.P. = SET IRON PIPE L.B. #6044.
S. = SOUTH.
" = SECONDS
T = TANGENT.
TWP = TOWNSHIP.
UTIL. = UTILITY.
U.P. = UTILITY POLE.
W.M. = WATER METER.
W.F. = WOOD FENCE.

W.S. = WOOD SHED.
W = WEST.
C = CENTER LINE.
Δ = CENTRAL ANGLE.
∠ = ANGLE.
// = WOOD FENCE.
-x-x- = CHAIN LINK FENCE.
/// = C.B.S. WALL. (C.B.W.).
x 0.00 = EXISTING ELEVATIONS.
0.00 = PROPOSED ELEVATIONS.

 = TRAFFIC FLOW
 (D) = DRAINAGE MH

E:\ADCAD\dwgfiles\Test.dwt 7/29/2005 3:36:46 PM EST

