SCOPE OF WORK

THE FOLLOWING DRAWINGS ILLUSTRATE THE PROPOSED SCOPE OF WORK FOR 2135 LAKE AVENUE TO BE APPROVED BY CITY OF MIAMI BEACH:

- REMOVAL OF EXISTING TREES & PALMS
 INSTALLATION NEW LANDSCAPE PLANTINGS
 INSTALLATION OF NEW ALTOMATIC IRRIGATION SYSTEM
 INSTALLATION OF NEW HARDSCAPE
 INSTALLATION OF NEW FRONT ENTRY DRIVEWAY
 INSTALLATION OF NEW FRONT ENTRY DRIVEWAY
 INSTALLATION OF NEW LANDSCAPE LIGHTING

08.15.2019 8.15.2019 8.15.2019

357 cypress drive, 10 tequesta, fl 33469 561.402.9414

www.nielsenlandarch.com

LOCATION MAP





$2135\,\mathrm{GARDEN}$ 235 GARDEN

SEAL (S TYLER NIELSEN - LA6667067)



VER PAGE	

DATE 08.15.2019 09.05.2019 MB DRB REVISION 01



SITEWORK GENERAL NOTES

- THE GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING ALL WORK BY THE SUBCONTRACTORS.
- CONTRACTOR SHALL VERIFY ALL CONDITIONS AT JOB SITE AND NOTIFY LANDSCAPE ARCHITECT AND GENERAL CONTRACTOR OF DIMENSIONAL ERRORS, OMISSIONS OR DISCREPANCIES BEFORE BEGINNING ANY WORK.
- CONTRACTOR TO OBTAIN ALL NECESSARY PERMITS PRIOR TO CONSTRUCTION. ALL
 CONTRACTORS MUST COMPLY WITH PERMIT REQUIREMENTS, LOCAL, STATE AND
 FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES RULES AND
 REGULATIONS AND LAND USE APPROVAL CONDITIONS AT ALL TIMES.
- 4. WORK PERFORMED WITHOUT APPROVAL OF LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES AND/OR NOT IN COMPLIANCE WITH SPECIFICATIONS AND/OR DRAWINGS IS SUBJECT TO REMOVAL AT CONTRACTOR'S EXPENSE
- 5. ALL WORK SHALL CONFORM TO THE APPROPRIATE AGENCIES. CONTRACTOR SHALL VERIEFY LOCATION OF ALL EXISTING UTILITIES, LINES AND STRUCTURES PRIOR TO EXCAVATION OR TRENCHING. DAMAGE SHALL BE REPAIRED BY THE CONTRACTOR AT NO COST TO THE OWNER. THE LANDSCAPE ARCHITECT ASSUMES NO RESPONSIBILITY FOR UTILITIES OR STRUCTURES NOT SHOWN ON THE DRAWINGS. CONTRACTOR IS TO VERIEFY THE EXACT LOCATION OF UTILITIES PRIOR TO CONSTRUCTION AND NOTIFY THE LANDSCAPE ARCHITECT OF ANY DISCREPANCIES. CONTRACTOR SHALL USE EXTREME CAUTION WHEN WORKING OVER OR NEAR EXISTING GAS AND ELECTRICAL LINES.
- 6. THE CONTRACTOR SHALL BE RESPONSIBLE FOR RESETTING ALL LAND MONUMENTS DISRUPTED BY CONSTRUCTION ACTIVITIES OR NEGLIGENCE ON THE PART OF THE CONTRACTOR. RESETS SHALL BE PERFORMED UNDER THE SUPERVISION OF A REGISTERED LAND SURVEYOR AND MONUMENT RECORDS MUST BE FILED AS REQUIRED BY STATUTE FOR ALL MONUMENTS.
- 7. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONARY MEASURES NECESSARY TO PROTECT EXISTING IMPROVEMENTS FROM DAMAGE AND ALL SUCH IMPROVEMENTS AND STRUCTURES DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR RECONSTRUCTED SATISFACTORY TO THE LANDSCAPE ARCHITECT AT THE CONTRACTOR'S EXPENSE.
- ALL BARRICADING AND TEMPORARY TRAFFIC CONTROL DEVICES OR METHODS USED DURING CONSTRUCTION SHALL BE IN ACCORDANCE WITH LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES STANDARDS. PROVIDE ADEQUATE TIME FOR REVIEW AND APPROVAL BY THE ABOVE JURISDICTIONS PRIOR TO COMMENCEMENT.
- 9. THE LANDSCAPE ARCHITECT IS NOT RESPONSIBLE FOR THE CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES UTILIZED OR FOR SAFETY PRECAUTIONS OR PROBLEMS IN CONNECTION WITH THE WORK. THE LANDSCAPE ARCHITECT WILL NOT BE RESPONSIBLE FOR THE CONTRACTOR'S FAILURE TO CARRY OUT THE WORK IN ACCORDANCE WITH THE CONTRACT DOCUMENTS. CONTRACT DOCUMENTS INCLUDE THE CONSTRUCTION DOCUMENT DRAWING SET/TECHNICAL SPECIFICATIONS MANIL (1/14):8
- CONTRACTOR TO VERIFY ALL QUANTITIES. IN CASE OF ANY DISCREPANCIES, GRAPHICALLY SHOWN MATERIAL QUANTITIES SHALL TAKE PRECEDENCE.
- A SYSTEM OF DIAGRAMMATIC SYMBOLS, HATCHES AND NOTATIONS IS USED IN THESE DRAWINGS. REVIEW NOTATIONS CAREFULLY, NOTIFY LANDSCAPE ARCHITECT AND REQUEST CLARIFICATION OF ANY UNCLEAR NOTATION OR DISCREPANCY PRIOR TO COMMENCING WORK.

SITEWORK GENERAL NOTES CONTINUED

- PROVIDE SLEEVES AS REQUIRED FOR DRAINAGE, IRRIGATION AND ELECTRICAL LINES. IRRIGATION AND ELECTRICAL SLEEVES AND SUBSURFACE DRAINAGE SYSTEMS SHALL BE CONSTRUCTED PRIOR TO PAVING AND LANDSCAPE WORK. UTILITY SLEEVES ARE REQUIRED IN ALL PLANT BEDS ISOLATED BY PAVEMENT OR ANY OTHER STRUCTURES.
- SPECIAL CONSIDERATION IS GIVEN TO THE DESIGN AND INTENDED RELATIONSHIP BETWEEN ARCHITECTURE, PLANTING AREAS AND PAVING SYSTEMS. PAVEMENT JOINTING, PAVERS, STONE, FINISHES AND GRADES HAVE BEEN STRICTLY COORDINATED IN THE CONTRACT DOCUMENTS. CONSTRUCTION OF THESE SYSTEMS SHALL BE STRICTLY COORDINATED.
- VEHICLES, EQUIPMENT, AND/OR MATERIALS SHALL NOT BE PARKED OR STORED IN AREAS OF EXISTING VEGETATION, INCLUDING WITHIN THE DRIPLINE OF EXISTING TREES TO REMAIN.
- 4. CONSTRUCTION WASTE-INCLUDING BUT NOT LIMITED TO: PLANT MATERIAL, BUILDING MATERIALS, DEMOLISHED MATERIALS, PACKAGING, LEFTOVER PAINT AND CONCRETE SLURRY-SHOULD BE PROPERLY REUSED, RECYCLED, DISPOSED OF LEGALLY OFF-SITE OR IN DESIGNATED WASH-OUT AREAS DETERMINED BY THE GENERAL CONTRACTOR.
- RECYCLING AND TRASH BINS TO BE PROVIDED ON SITE. SEPARATE BINS FOR CARDBOARD, CO-MINGLED, AND OTHER RECYCLABLE/REUSABLE MATERIALS IDENTIFIED BY THE LOCAL JURISDICTION SHALL BE MAINTAINED. ALL BINS TO BE WILDLIFE-PROOF.
- ON-SITE FUEL STORAGE FOR CONSTRUCTION EQUIPMENT IS DISCOURAGED.
 CONSTRUCTION EQUIPMENT USED ON SITE TO BE CHECKED REGULARLY TO
 ASSURE CONTAMINATION CONCERNS FROM OILS AND GREASES ARE ELIMINATED.
 NO TOXIC MATERIALS SHALL BE STORED ON-SITE.
- GENERAL CONTRACTOR TO KEEP ALL ITEMS IMPLEMENTED BY LANDSCAPE ARCHITECT IN PROPER WORKING ORDER THROUGHOUT THE DURATION OF THE PROJECT.
- 8. THE CONSTRUCTION SITE TO BE INSPECTED ON A MONTHLY BASIS BY LANDSCAPE ARCHITECT AND/OR CIVIL ENGINEER TO ASSURE THAT THE SILT FENCE AND MUD TRACKING PAD ARE PROPERLY IN PLACE AND FUNCTIONING AS DESIGNED.
- GREEN BUILDING PRACTICES SHALL BE EMPLOYED TO THE EXTENT FEASIBLE. SUCH PRACTICES INCLUDE: CARPOOLING/VANPOOLING TO JOB SITE, MINIMIZING MATERIALS PACKING BEFORE ARRIVAL TO JOB SITE, REDUCING MATERIAL/RESOURCE INFEFICIENCIES BY COORDINATING WORK.
- 10. THE PROJECT LIMIT OF CONSTRUCTION AND ALL EXISTING VEGETATION TO REMAIN IS TO BE CLEARLY DEFINED BY STURDY, WEATHERPROOF FENCING AT A MINIMUM OF FOUR (4) FEET HIGH.
- 11. WATERPROOFING OF SUBGRADE AND OTHER ARCHITECTURAL SPACES BELOW AND/OR ADJACENT TO IMPROVEMENTS DESIGNED BY THE LANDSCAPE ARCHITECT IS TO BE ADEQUATELY DESIGNED AND DETAILED BY OTHERS TO PERMANENTLY REPEL ALL WATER SOURCES INCLUDING, BUT NOT LIMITED TO: PRECIPITATION, STORM WATER RUNOFF, GROUND WATER, IRRIGATION, ROOF RUNOFF, GROUND WATER, AND PLUMBING LEAKS.
- 12. STRUCTURAL DESIGN TO SUPPORT IMPROVEMENTS DESIGNED BY THE LANDSCAPE ARCHITECT AND LOCATED ABOVE, BELOW, AND/OR ADJACENT TO SUBGRADE AND OTHER ARCHITECTURAL SPACES IS THE RESPONSIBILITY OF THE STRUCTURAL ENGINEER. THE STRUCTURAL DESIGN SHOULD BE ADEQUATELY DESIGNED TO SUPPORT ALL POSSIBLE LOADS INCLUDING, BUT NOT LIMITED TO: BACKFILL, COMPACTION, PLANTINGS, HARDSCAPES, RETAINING AND FREESTANDING SITE WALLS, AND CONSTRUCTION MATERIALS/EQUIPMENT/ACTIVITY.

SOIL EROSION CONTROL NOTES

- PRIOR TO BEGINNING ANY EARTH CHANGE, THE CONTRACTOR SHALL INSTALL AND MAINTAIN ALL SESC MEASURES AS SHOWN ON THE CONTRACT DOCUMENTS AND AS REQUIRED BY ANY GOVERNING AGENCIES.
- 2. ALL SESC MEASURES TO BE MAINTAINED DAILY.
- 3. THE CONTRACTOR TO CONDUCT ALL EXCAVATION, FILLING, GRADING, AND CLEANUP OPERATIONS IN A MANNER SUCH THAT SEDIMENT, GENERATED BY WIND OR WATER IS NOT DISCHARGED INTO ANY STORM SEWER, DRAINAGE DITCH, RIVER, LAKE, AIR, OR UNDERGROUND UTILITY SYSTEM. STAGE WORK TO MINIMIZE THE AREA OF EXPOSED SOIL, THEREBY REDUCING THE OPPORTUNITY FOR SOIL EROSION.
- WATER FROM TRENCHES AND OTHER EXCAVATION TO BE PUMPED INTO A FILTRATION BAG TO REMOVE SEDIMENTS FROM THE WATER.
- NORTH AMERICAN GREEN SC-150 OR EQUIVALENT EROSION CONTROL FABRIC IS REQUIRED ON ALL DISTURBED SLOPES GREATER THAN 3:1 UNTIL PROJECT AREA IS REVEGETATED PET THE PLANTING PLAN.
- 6. PROVIDE POSITIVE DRAINAGE AWAY FROM ALL STRUCTURES.
- CONTRACTOR TO PROVIDE ONSITE WATERING TO REDUCE FUGITIVE DUST LEAVING THE SITE DURING CONSTRUCTION.
- SOIL EROSION CONTROL MEASURES TO BE PROVIDED FOR ALL EXISTING AND PROPOSED DRAINAGE STRUCTURES WITHIN THE PROJECT LIMITS.
- CONSTRUCTION STAGING AND PHASING SHALL OCCUR, WHERE APPLICABLE, TO MINIMIZE SOIL DISTURBANCE TIME.
- 10. BEST MANAGEMENT PRACTICES (BMPs) SHALL BE ADJUSTED AS NEEDED TO MEET ANY
- 11. THE GENERAL CONTRACTOR IS RESPONSIBLE FOR INSTALLING A MUD TRACKING PAD/WASHING PAD AT THE CONSTRUCTION ENTRANCES TO MINIMIZE MUD DETACHMENT FROM TRUCK TIRES. 1-1/2 INCH SCREENED ROCK TO BE PLACED ON MIRAFI 140-N FILTER FABRIC. ADDITIONAL CLEAN GRAVEL TO BE ADDED THROUGHOUT THE DURATION OF CONSTRUCTION AS NEEDED.
- 12. CONTRACTOR SHALL ABIDE BY THE LOCAL, STATE AND FEDERAL JURISDICTIONS AND GOVERNING BODIES/AGENCIES CONSTRUCTION MANAGEMENT PLAN FEQUIREMENTS.
- 13. RESEED AS INDICATED IN SEEDING NOTES.





tequesta, fl 33469 561.402.9414

www.nielsenlandarch.com



SEAL (S TYLER NIELSEN - LA6667067)



GENERAL	SITE NOTES
DATE	ISSUE

08.15.2019 MB DRB 09.05.2019 REVISION

1.001

CONTRACTOR QUALIFICATIONS

- CONTRACTOR MUST BE A LICENSED LANDSCAPE CONTRACTOR.
- CONTRACTOR MUST HAVE A MINIMUM OF 10 YEARS OF PROVEN EXPERIENCE RELOCATING LARGE SPECIMEN TREES AND PALMS IN SOUTH FLORIDA.
- CONTRACTOR MUST HAVE PROVEN EXPERIENCE RELOCATING TREES AND PALMS OF THE SAME SPECIES AND SIZE AS THOSE TO BE RELOCATED FOR THE CURRENT PROJECT.
- 4. CONTRACTOR MUST HAVE A CERTIFIED ARBORIST ON STAFF

CONTRACTOR REQUIREMENTS

- CONTRACTOR MUST VISIT THE JOBSITE AND INSPECT ALL TREES AND PALMS TO BE RELOCATED AS WELL AS EXISTING SITE CONDITIONS AND RESTRICTIONS PRIOR TO PREPARING RID.
- CONTRACTOR MUST VERIFY AND ENSURE THAT ALL TREES AND PALMS IDENTIFIED ON THE PLANS AND THOSE TAGGED ON THE JOBSITE CORRESPOND AS TO NUMBER AND DESCRIPTION. ANY DISCREPANCIES MUST BE BROUGHT TO THE ATTENTION OF THE LANDSCAPE ARCHITECT IMMEDIATELY, PRIOR TO PREPARING BID.
- CONTRACTOR MUST CONDUCT ALL WORK ASSOCIATED WITH RELOCATION AND MAINTENANCE OF TREES AND PALMS TO BE RELOCATED. NO WORK IS TO BE SUBCONTRACTED WITHOUT PRIOR WRITTEN CONSENT OF THE OWNER AND/OR LANDSCAPE ARCHITECT
- CONTRACTOR MUST DESIGNATE A COMPETENT, ENGLISH-SPEAKING SUPERVISOR OR FOREMAN OVERSEE AND DIRECT ALL RELOCATION AND MAINTENANCE ACTIVITIES AS OUTLINED IN THESE SPECIFICATIONS.
- 5. CONTRACTOR MUST SCHEDULE ROOT PRUNING TO PROVIDE THE MAXIMUM POSSIBLE TIME FOR NEW ROOT GROWTH. EVEN TREES AND PALMS THAT TYPICALLY DO NOT REQUIRE LONG (OR ANY) ROOT PRUNING WILL BENEFIT FROM MORE ROOT PRUNING TIME; THEREFORE, ALL TREES AND PALMS TO BE RELOCATED MUST BE ROOT PRUNED. CONTRACTOR MUST PROVIDE A ROOT PRUNE SCHEDULEFOR EACH TREE OR PALM TO BE RELOCATED AS AN ATTACHMENT TO THE BID.
- 6. CONTRACTOR MUST CALL SUNSHINE 811 TO HAVE ALL UNDERGROUND UTILITIES LOCATED UNDER OR IN THE VICINITY OF THE CURRENT OF FUTURE LOCATIONS OF ALL TREES AND PALMS TO BE RELOCATED PRIOR TO WORK COMMENCING.
- CONTRACTOR MUST VERIFY WITH THE GENERAL CONTRACTOR THE ABSENCE OF ANY UNDERGROUND CONSTRUCTION OR OBSTRUCTIONS (E.G., BULKHEADS, SEPTIC SYSTEMS, ETC.) IN THE CURRENT AND PUTURE LOCATIONS OF ALL TREES AND PALMS TO BE RELOCATED.
- CONTRACTOR MUST ALERT THE LANDSCAPE ARCHITECT OF ANY TREES OR PALMS
 THAT WILL NOT SUCCESSFULLY RELOCATE DUE TO POOR HEALTH PRIOR TO BEGINNING
 ROOT PRUNING.
- CONTRACTOR MUST FLAG ALL PROPOSED TRANSPLANT LOCATION FOR THE LANDSCAPE ARCHITECT'S APPROVAL A MINIMUM OF 15 DAYS PRIOR TO RELOCATION.
- CONTRACTOR MUST ENSURE THAT ALL TREES AND PALMS TO BE RELOCATED ARE INSTALLED AT THE CORRECT GRADE OR ELEVATION, ACCORDING TO THE GRADING PLAN
- 11. CONTRACTOR MUST BE ENSURE THAT ALL ROOT FLARES ARE EXPOSED AFTER RELOCATION.
- 12. CONTRACTOR MUST REMOVE ALL RESIDUAL ROOTS, STUMPS, AND PORTIONS THEREOF AND BACKFILL PITS FROM WHICH RELOCATED TREES AND PALMS WERE REMOVED WITH CLEAN FILL FLUSH WITH THE SURROUNDING GRADE.
- 13. CONTRACTOR MUST BE REPAIR ANY DAMAGE TO OTHER PLANTS, LAWN, HARDSCAPES, OR NEW CONSTRUCTION WITHIN THE RELOCATION AREA AT CONTRACTOR'S EXPENSE. HARDSCAPES INCLUDE BUT ARE NOT LIMITED TO CURBS, WALKS, ROADS, FENCES, SITE FURNISHINGS, ETC.
- 14. CONTRACTOR MUST PHOTOGRAPHICALLY DOCUMENT NEW ROOT GROWTH FOLLOWING EACH ROOT PRUNE AND SUBMIT THIS DOCUMENTATION TO THE LANDSCAPE ARCHITECT. THE PURPOSE OF THIS REQUIREMENT IS TO ENSURE THAT SUFFICIENT ROOT GROWTH HAS OCCURRED PRIOR TO THE SECOND AND SUBSEQUENT ROOT PRUNES AND FOLLOWING THE FINAL ROOT PRUNE PRIOR TO RELOCATION.
- 15. CONTRACTOR MUST INSTALL AND MAINTAIN PROTECTION FENCING AROUND EACH TREE AND PALM TO BE RELOCATED BOTH DURING ROOT PRUNING AND AFTER RELOCATION. PROTECTION FENCING MUST CONSIST OF GALVANIZED WELDED WIRE FABRIC OR PLASTIC MESH ATTACHED TO 4" X 4" POSTS INSERTED AROUND THE PERIMETER OF THE DRIPLINE OF THE TREE OR PALM. PROTECTION FENCING MUST BE PLUMB, TAUT, AND STURDY AT ALL TIMES AND MUST REMAIN IN PLACE THROUGHOUT THE ROOT PRUNING AND WARRANTY PERIODS, OR AS DIFECTED BY THE LANDSCAPE ABCHITECT
- CONTRACTOR MUST OBTAIN ALL NECESSARY OR REQUIRED PERMITS FOR THE RELOCATION AND TRANSPORTATION OF THE TREES AND PALMS TO BE RELOCATED.
- 17. CONTRACTOR MUST GUARANTEE ALL RELOCATED TREES AND PALMS FOR ONE YEAR FROM THE DATE OF RELOCATION TO THE FINAL LOCATION, GUARANTEE MUST INCLUDE THE LEGAL THE AND SETTING.
- 18. CONTRACTOR MUST PROVIDE ALL MATERIAL NECESSARY TO PERFORM THE WORK COVERED HEREIN, INCLUDING BUT NOT LIMITED TO BACKFILL MATERIAL, PROTECTION FENCING, FLAGGING, ADDITIVES AND SUPPLEMENTS, TEMPORARY IRRIGATION, BURLAP, WIRE, SHRINK WRAP, AND ALL NECESSARY TOOLS AND EQUIPMENT.

TREE ROOT PRUNING SPECIFICATIONS

- ALL TREES AND PALMS TO BE RELOCATED MUST BE WATERED DAILY FOR AT LEAST 2-3 DAYS PRIOR TO ANY ROOTS BEING CUT TO ENSURE THAT THEY ARE FULLY HYDRATED. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH.
- EACH TREE AND PALMS MUST THEN BE WATERED EVERY OTHER DAY, NOT RELYING ON RAIN, DURING THE ENTIRE ROOT PRUNING PROCESS EITHER BY A TEMPORARY IRRIGATION SYSTEM OR BY HAND. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH.
- TREE AND PALM RELOCATION ACTIVITIES MUST BE SCHEDULED SO THAT REMOVAL AND REPLANTING TAKE PLACE IN THE SAME 24-HOUR PERIOD. NO TREES OR PALMS MAY BE "STOCKPILED" ONSITE OR OFFSITE FOR ANY PERIOD OF TIME WITHOUT PRIOR WRITTEN APPROVAL OF THE LANDSCAPE ARCHITECT. WHEN ALLOWED, APPROVAL FOR THE METHOD OF "STOCKPILING" MUST BE OBTAINED FROM THE LANDSCAPE ARCHITECT.
- ALL DIGGING IN THE ROOT ZONE DURING THE ROOT PRUNE PROCESS MUST BE DONE BY HAND; NO MACHINERY WILL BE ALLOWED. PRUNING OF ROOTS MUST BE DONE BY HAND WITH CLEAN, SHARP TOOLS. DO NOT PAINT CUT ROOTS WITH TREE PAINT OR BAY KIND OF SEALANT
- MYCORRHIZA (ROOTS® TRANSPLANT OR EQUIVALENT) MUST BE INCORPORATED INTO THE BACKFILL SOIL PRIOR TO BACKFILLING AS PER MANUFACTURER'S BECOMMENDATIONS
- 6. AFTER EACH ROOT PRUNE, EACH SECTION OF ROOTBALL THAT IS PRUNED MUST BE WRAPPED WITH BLACK PLASTIC AND THE TRENCH BACKFILLED WITH ORIGINAL EXCAVATED SOIL. A TREE RING WITH A MINIMUM HEIGHT OF 6" MUST BE CONSTRUCTED 6-12" OUTSIDE THE OUTERMOST EDGE OF THE ROOTBALL AND AROUND THE ENTIRE PERIMETER OF THE ROOTBALL TO DIRECT IRRIGATION WATER AND ANY ADDED SUPPLEMENTS DOWN INTO THE ROOTBALL DURING ROOT PECENIER ATOM.
- ONCE THE TREE RING IS CONSTRUCTED AFTER EACH ROOT PRUNE, A
 HIGH-PHOSPHORUS ROOT STIMULANT MUST BE LIBERALLY APPLIED TO THE
 SURFACE OF THE ROOTBALL AND THOROUGHLY WATERED IN TO ENCOURAGE NEW
 ROOT GROWTH.
- PRIOR TO ANY ROOTS BEING CUT, ALL MAJOR ROOTS MUST BE IDENTIFIED TO DETERMINE THE ROOTBALL DIAMETER BASED ON THE RELATIVE LOCATION AND SIZE OF THE ROOTS.
- 9. MANY TREE RELOCATION SPECIFICATIONS USE "GENEFAL RULES" TO CALCULATE MINIMUM ROOTBALL DIAMETER, SUCH AS MULTIPLYING THE DIAMETER AT BREAST HEIGHT (DBH) OF THE TREE BY A FACTOR OF 10 OR ALLOWING A MINIMUM OF 9"-12" OF ROOTBALL FOR EVERY 1" OF TREE CALIPER. OTHERS LIST UNREALISTIC MINIMUM SIZES FOR THE ROOTBALLS OF VARIOUS TREE CALIPERS OR OTHERS LIST UNREALISTIC MINIMUM SIZES FOR THE ROOTBALLS FOR THE ROOTBALLS OF VARIOUS TREE CALIPERS OR HEIGHTS. IN MANY CASES, SUCH APPROACHES RESULT IN ROOTBALLS THAT ARE EITHER TOO LARGE OR TOO SMALL FOR A GIVEN TREE. THE FOLLOWING TABLE LIST MINIMUM ROOTBALL DIAMETERS BASED ON REAL-WORLD EXPERIENCE OF TREE RELOCATION SPECIALISTS IN SOUTH FLORIDA.

.CALIPER	MIN. ROOTBALL	CALIPER	MIN. ROOTBAL
(inches)	DIA. (feet)	(inches)	DIA. (feet)
1-4	3	12-14	8
4-5	4	15-17	10
6-7	5	18-24	12-15
8-9	6	25-30	15-25
10-11	7	30+	as needed

- WHENEVER POSSIBLE, ROOTBALLS MUST BE CIRCULAR IN SHAPE WITH AN EQUAL DISTANCE FROM THE TRUNK TO THE EDGE OF ROOTBALL ALL AROUND.
- MINIMUM ROOTBALL DEPTH MUST BE 24"-36" FOR ALL TREES TO BE RELOCATED, WITH THE ACTUAL DEPTH TO BE DETERMINED ONLY AFTER A THOROUGH EXAMINATION OF ALL ROOTS DURING THE INITIAL ROOT INSPECTION AND BASED ON THE ABSENCE OF MAJOR ROOTS AT THE BOTTOM OF THE ROOTBALL. ROOTBALLS DEEPER THAN 36" MAY BE REQUIRED FOR LARGE SPECIMEN TREES, DEPENDING ON THE RELATIVE LOCATIONS AND DEPTHS OF THE MAJOR ROOTS AS OBSERVED DURING THE INITIAL ROOT INSPECTION.
- AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR TREES WITH A DBH OF LESS THAN 10" IS 12 WEEKS. THE FIRST ROOT PRUNE MUST BE ON TWO OPPOSING SIDES OF THE ROOTBALL, WITH THE SECOND ROOT PRUNE ON ONE OF THE OTHER TWO SIDES DONE A MINIMUM OF 6 WEEKS LATER, AND A THIRD ROOT PRUNE ON THE LAST SIDE DONE A MINIMUM OF 3 WEEKS AFTER THAT. THE SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW ROOT GROWTH FROM EARLIER ROOT PRUNES IS EVIDENT (SEE SECTION 2.14 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT GROWTH DURING THE ROOT PRUNE PROCESS). MORE TIME MAY BE NEEDED DURING THE COOLER MONTHS OF THE YEAR.
- AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR TREES WITH A DBH OF 10"
 OR GREATER IS 24 WEEKS, THE FIRST ROOT PRUNE MUST BE ON TWO OPPOSING
 SIDES OF THE ROOTBALL, WITH THE SECOND ROOT PRUNE ON ONE OF THE
 OTHER TWO SIDES DONE A MINIMUM OF 12 WEEKS LATER, AND A THIRD ROOT
 PRUNE ON THE LAST SIDE DONE A MINIMUM OF 6 WEEKS AFTER THAT. THE
 SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW
 ROOT GROWTH FROM EARLIER ROOT PRUNES IS EVIDENT (SEE SECTION 2.14
 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT
 GROWTH DURING THE ROOT PRUNE PROCESS). MORE TIME MAY BE NEEDED
 DURING THE COOLER MONTHS OF THE YEAR.

PALM ROOT PRUNING SPECIFICATIONS

. THE FOLLOWING TABLE LISTS MINIMUM ROOTBALL DIAMETERS FOR VARIOUS SPECIES OF PALMS BASED ON REAL-WORLD EXPERIENCE OF RELOCATION SPECIALISTS IN SOUTH FLORIDA.

SABAL/CABBAGE PALM QUEN & FOXTAIL PALMS ROYAL & COCONUT PALMS CANARY DATE PALM

3.

POOTBALL SPECIFICATIONS

12"from trunk in all directions
18-24" from trunk in all directions
24" from trunk in all directions
24" from trunk in all directions

- PALM ROOTBALL MUST BE A MINIMUM OF 24" DEEP, WHENEVER POSSIBLE, ROOTBALLS MUST BE CIRCULAR IN SHAPE WITH AN EQUAL DISTANCE FROM THE TRUNK TO THE EDGE OF THE ROOTBALL ALL AROUND.
 - AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR PALMS IS 6-8 WEEKS. THE RRST ROOT PRUNE MUST BE ON TWO OPPOSING SIDES OF THE ROOTBALL, WITH THE SECOND ROOT PRUNE ON ONE OF THE OTHER TWO SIDES DONE A MINIMUM OF 3-4 WEEKS LATER, AND A THIRD ROOT PRUNE ON THE LAST SIDE DONE A MINIMUM OF 4.5-6 WEEKS AFTER THAT. THE SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW ROOT GROWTH FROM EARLIER ROOT PRUNES IS EVIDENT (SEE SECTION 2.14 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT GROWTH DURING THE ROOT PRUNE PROCESS). MORE TIME MAY BE NEEDED DURING THE COOLER MONTHS OF THE YEAR.
- CERTAIN PALMS, IN PARTICULAR THOSE THAT ARE SLOW GROWING, REQUIRE LONGER ROOT PRUNING TIME. THESE INCLUDE, EUT ARE NOT LIMITED TO, THE FOLLOWING.
 - ALL SPECIES OF ARCHONTOPHOENIX
 - ALL SPECIES OF CORYPHA
 AMERICAN OIL PALMS (ALL SPECIES OF ATTALEA)
 - AMERICAN OIL PALMS (ALL SPECIES OF ATTALEA BISMARCK PALM (BISMARCKIA NOBILIS)
 - CUBAN & CARIBBEAN COPERNICIA
 - CUBAN BELLY PALM (GASTROCOCOS CRISPA)
 - GINGERBREAD/DOUM PALMS (ALL SPECIES OF HYPHAENE)
 PALMYRA PALMS (ALL SPECIES OF BORASSUS)
 - SATAKE PALM (SATAKENTIA LIUKIUENSIS)
 - SAW PALMETTO (SERENOA REPENS)
 - SILVER PALM (COCCOTHRINAX ARGENTATA)
 - ZOMBIE PALM (ZOMBIA ANTILLARUM)

FOR THESE PALMS, THE MINIMUM ROOT PRUNING TIME IS 4-6 MONTHS OR GREATER. ONLY WHEN SUFFICIENT NEW ROOT GROWTH HAS TAKEN PLACE FOLLOWING AN EARLIER ROOT PRUNE CAN THE NEXT ROOT PRUNE BE DONE, AND ONLY WHEN SUFFICIENT NEW ROOT GROWTH HAS TAKEN PLACE FOLLOWING THE FINAL ROOT PRUNE MAY THE TREE BE RELOCATED (SEE SECTION 2.14 ABOVE FOR SPECIFICATIONS ON PHOTOGRAPHICALLY DOCUMENTING NEW ROOT GROWTH DURING THE ROOT PRUNE PROCESS).

TREE CANOPY PRUNING SPECIFICATIONS

- PRIOR TO RELOCATION, THE CANOPY OF EACH TREE TO BE RELOCATED MUST BE SELECTIVELY PRUNED TO REMOVE CROSSING DEAD, DISEASED, BROKEN, AND LOW HANGING BRANCHES THAT MAY INTERFERE WITH CONSTRUCTION ACTIVITIES, OR THAT MAY INTERFERE OR RESTRICT STRAPPING OR LIFTING THE TREE DURING RELOCATION.
- FOR TREES BEING RELOCATED ONSITE, THE CANOPY MAY BE SELECTIVELY THINNED AND REDUCED BY NO MORE THAN 1/3 OF THE OVERALL CANOPY MASS, AT THE DIRECTION OF THE LANDSCAPE ARCHITECT; HOWEVER, THE BASIC SHAPE, FORM, AND CHARACTER OF THE TREES MUST BE PRESERVED.
- FOR TREES BEING RELOCATED OFFSITE, THE CANOPY MUST BE PRUNED, AT THE DIRECTIONS OF THE LANDSCAPE ARCHITECT, TO FIT ON THE TRAILER FOR TRANSPORT. EVERY EFFORT MUST BE MADE TO RETAIN AS MANY BRANCHES AS POSSIBLE. TO THE WIDEST LOAD WIDTH ALLOWABLE BY THE FLORIDA DEPARTMENT OF TRANSPORTATION. CONTRACTOR MUST OBTAIN ALL NECESSARY PERMITS AND ESCORTS TO TRANSPORT WIDE LOADS, PER FLORIDA LAW.
- ALL CANOPY PRUNING MUST BE CONDUCTED FOLLOWING ANSI A-300 TREE PRUNING STANDARDS AND BEST MANAGEMENT PRACTICES.
- ALL DEBRIS GENERATED DURING CANOPY PRUNING MUST BE REMOVED OFFSITE AND DISPOSED.

PALM CANOPY PRUNING SPECIFICATIONS

- 1. IT IS WELL KNOW THAT SOME PALMS SURVIVE RELOCATION BETTER WHEN ALL OF THE LEAVES ARE REMOVED (E.G., CABBAGE PALM, SABAL PALMETTO), AND THAT OTHER PALMS BENEFIT FROM HAVING THEIR LEAVES CUT IN HALF DURING RELOCATION (E.G., COCONUT PALM, COCOS NUCIFERA). BOTH OF THESE HORTICULTURAL PRACTICES, WHILE TRUE, ARE ONLY APPLICABLE WHEN PALMS ARE NOT ROOT PRUNED. LEAVES DO NOT NEED TO BE CUT IN HALF OR REMOVED FROM PALMS THAT ARE ADEQUATELY ROOT PRUNED. ON OCCASION WHEN SUFFICIENT ROOT PRUNING TIME IS NOT AVAILABLE, PALMS TO BE RELOCATED MAY HAVE THEIR LEAVES CUT IN HALF OR REMOVED ENTIRELY AT THE DIRECTION OF THE LANDSCAPE ARCHITECT.
- PALMS LEAVES MUST BE TIED UP WITH 2-PLY BIODEGRADABLE TWINE PRIOR TO RELOCATION TO PREVENT MECHANICAL DAMAGE DURING THE RELOCATION PROCESS.
- PALM TRUNKS SHALL ONLY BE 'CLEANED UP' ACCORDING TO THE LANDSCAPE ARCHITECT'S SPECIFICATIONS SPECIFIC TO EACH PALM.



357 cypress drive, 1 tequesta, fl 33469 561.402.9414

www.nielsenlandarch.com

2135 GARDEN

SEAL (S TYLER NIELSEN - LA6667067)



09.05.20

DATE ISSUE

08.15.2019 MB DRB 09.05.2019 REVISION 01

1100

© COPYRIGHT NIELSEN LANDSCAPE ARCHITECTS, LLC

TREES PROTECTION NOTES

- CONTRACTOR TO PROTECT ALL EXISTING TREES PRIOR TO THE DEMOLITION OF THE EXISTING STRUCTURE.
- UPON COMPLETION OF OF SITE DEMOLITION, CONTRACTOR TO RELOCATE ALL SPECIFIED TREES AND PALMS FOR RELOCATION. CONTRACTOR TO REINSTALL TREE PROTECTION FENCE AROUND RELOCATED AND EXISTING TREES.
- FENCING AT A MINIMUM FOUR (4) FEET HEIGHT INSTALLED NO CLOSER TO THE TREE
 TRUNK THAN ITS DRIPLINE. THIS FENCE SHALL BE MAINTAINED IN WORKING ORDER
 DURING ALL PHASES OF CONSTRUCTION. MAINTAIN TREE PROTECTION ZONES FREE OF
 WEETER AND TRACE.
- THE PROJECT LIMIT OF CONSTRUCTION AND ALL EXISTING VEGETATION TO REMAIN IS TO BE CLEARLY DEFINED BY STURDY, WEATHERPROOF FENCING AT A MINIMUM OF FOUR MATERIAL HIGH.
- STURDY TEMPORARY BARRIERS SHALL BE INSTALLED AROUND ALL TREE PROTECTION ZONES.
 BARRIERS SHALL BE A MINIMUM OF FOUR FEET HIGH, AND SHALL BE CONSTRUCTED OF
 CONTINUOUS CHAIN LINK FENCE WITH METAL POSTS AT EIGHT-FOOT SPACING, OR OF
 TWO-BY-FOUR INCH POSTS WITH THREE EQUALLY SPACED TWO-BY-FOUR RAILS. POSTS MAY
 BE SHIFTED TO AVOID ROOTS.

MAINTENANCE SPECIFICATIONS

- ALL RELOCATED TREES AND PALMS MUST BE MAINTAINED FOR ONE YEAR FROM THE DATE OF RELOCATION TO THEIR FINAL LOCATIONS.
- 2. CONTRACTOR MUST MAINTAIN ALL RELOCATED TREES AND PALMS FOR ONE FULL YEAR FROM THE DATE OF RELOCATION TO THE FINAL LOCATION.
- 3. WHENEVER POSSIBLE, EACH TREE AND PALM MUST BE WATERED BY A PERMANENT AUTOMATIC IRRIGATION SYSTEM FOLLOWING RELOCATION. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH; THIS WILL REQUIRE 25-50 GALLONS OF WATER FOR SMALL TREES AND PALMS DEPENDING ON ROOTBALL SIZE, WHILE LARGE TREES WILL REQUIRE A MINIMUM OF 10 GALLONS PER FOOT OF ROOTBALL DIAMETER (I.E., A 10' DIAMETER ROOTBALL WILL REQUIRE A MINIMUM OF 100 GALLONS PER WATERING EVENT).WATERING FREQUENCY MUST BE EVERY DAY FOR THE RIST TWO WEEKS, EVERY OTHER DAY FOR THE NEXT THREE WEEKS, AND EVERY THIRD DAY FOR THE NEXT 6-8 WEEKS.
- WHEN AN AUTOMATIC IRRIGATION SYSTEM IS NOT POSSIBLE, CONTRACTOR IS
 RESPONSIBLE FOR HAND WATERING RELOCATED TREES AND PALMS THROUGHOUT THE
 MAINTENANCE PERIOD AND UNTIL FINAL ACCEPTANCE BY THE LANDSCAPE ARCHITECT
 AND/OR CLIENT.
- IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION. A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE APPLIED TO THE SURFACE OF THE ROOTBALLAT THE RECOMMENDED LABEL RATE AND WATERED IN WITH A DRENCH CONSISTING OF A SYSTEMIC INSECTICIDE AND A CONTACT ROOT ROT FUNGICIDE, FOLLOWING LABEL INSTRUCTIONS. AS INITIAL PREVENTATIVE MAINTENANCE.
- 6. EVERY THREE MONTHS THEREAFTER, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE APPLIED TO THE SURFACE OF THE ROOTBALL AT THE RECOMMENDED LABEL RATE AND WATERED IN WITH A DRENCH CONSISTING OF A SYSTEMIC INSECTICIDE AND A BROAD-SPECTRUM SYSTEMIC FUNGICIDE, FOLLOWING LABEL INSTRUCTIONS, AS CONTINUING PREVENTATIVE MAINTENANCE.
- IRRIGATION AND BRACING MUST BE CHECKED AND EACH TREE OR PALM THOROUGHLY INSPECTED FOR SIGNS OF STRESS, DISEASE, OR PEST PROBLEMS ON A MONTHLY BASIS.
- IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS
 THEREAFTER, A HIGH-QUALITY, SLOW-RELEASE 15-2-15 GRANULAR FERTILIZER MUST BE
 APPLIED, AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SURFACE
 OF THE ROOTBALL.
- IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS
 THEREAFTER A HIGH-QUALITY, SLOW-RELEASE 15-2-15 GRANULAR FERTILIZER MUST BE
 APPLIED, AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SURFACE
 OF THE ROOTBALL.
- 10. FOLIAR FEED FOUR TIMES PER YEAR.
- 11. STRING MUST BE REMOVED FROM THE TIED UP LEAVES IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION IF THE PALM WAS ROOT PRUNED OR WITHIN 30-45 DAYS AFTER RELOCATION ON THE OCCASION THE LANDSCAPE ARCHITECT APPROVED RELOCATION WITHOUT ROOT PRUNING DUE TO TIME CONSTRAINTS.
- 12. IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS THEREAFTER A HIGH-QUALITY, SLOW-RELEASE 8-4-12 GRANULAR PALM FERTILIZER WITH MINORS MUST BE APPLIED. AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SUBFACE OF THE ROOTRALL.
- 13. FOLIAR FEED PALMS SIX TIMES PER YEAR.

RELOCATION SPECIFICATIONS

- LANDSCAPE CONTRACTOR TO FLAG ALL PROPOSED PLANT LOCATIONS FOR LANDSCAPE ARCHITECT'S APPROVAL PRIOR TO INSTALLATION. NOTIFY LANDSCAPE ARCHITECT A MINIMUM OF 15 DAYS PRIOR TO REVIEW.
- ALL TREES AND PALMS TO BE RELOCATED MUST BE WATERED DAILY FOR AT LEAST 5 DAYS PRIOR TO ANY RELOCATION TO ENSURE THAT THEY ARE FULLY HYDRATED. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTRALL TO ITS FULL DEPTH.
- 3. ALL ROOTBALLS MUST BE WRAPPED IN BURLAP AND THE TIGHTLY WIRE-WRAPPED (USING REDLINE HORSE WIRE OR EQUIVALENT) TO KEEP THE ENTIRE ROOTBALL INTACT DURING RELOCATION. TREES AND PALMS GROWING IN LIMESTONE MUST BE DUG AND RELOCATED WITH THE ROOT ATTACHED TO A SECTION OF ROCK AS PART OF THE ROOTBALL SUCH THAT THE ROOTS REMAIN INTACT, ROOTBALLS COMING FROM SAND OR SANDY SOIL MAY ALSO NEED TO BE BOXED PRIOR TO RELOCATION, AT THE DISCRETION OF THE LANDSCAPE ARCHITECT.
- 4. TREES AND PALMS BEING RELOCATED OFFSITE MUST HAVE THER ENTIRE ROOTBALLS THOROUGHLY AND TIGHTLY WRAPPED WITH PLASTIC SHRINK WRAP ON THE OUTSIDE OF THE WIRE WRAP, AND THE ENTIRE TREE OR PALM (INCLUDING CANOPY, TRUNK, AND ROOTBALL) MUST BE COVERED WITH A BREATHABLE TARP (E.G., SHADE CLOTH) DURING TRANSPORT.
- 5. NEW PLANTING PITS FOR RELOCATED TREES AND PALMS MUST BE PREPARED PRIOR TO LIFTING THE PALM OR TREE FROM ITS CURRENT LOCATION AND MUST BE AT LEAST 3-4 FEET WIDER THAN THE ROOTBALL AND THE SAME DEPTH AS THE ROOTBALL, SUCH THAT THE FINAL ELEVATION OF THE TOP OF THE ROOTBALL IS AT OR SLIGHTLY ABOVE (NO MORE THAN 2" HIGHERO FINAL GRADE.
- 6. TREES AND PALMS TO BE RELOCATED MUST BE LIFTED BY THE ROOTBALL ONLY, USING APPROPRIATELY SIZED (LENGTH AND STRENGTH) LIFTING STRAPS OR CHAINS. DURING LIFTING, THE TREE OR PALM MUST BE BALANCED IN A MORE-OR-LESS UPRIGHT POSITION, WITH THE STRAP THE TRUNK USED ONLY FOR BALANCING AND MANEUVERING THE TREE OR PALM INTO A POSITION. NO CHAINS MAY BE USED AROUND OR AGAINST THE TRUNK AT ANYTIME. AT NO TIME SHALL 100% OF THE WEIGHT OF THE TREE OR PALM BE ON THE STRAP ATTACHED TO THE TRUNK. TRUNKS MUST BE HEAVILY PADDED WITH 30-60 LAYERS (DEPENDING ON SIZE AND WEIGHT) OF BURLAP BENEATH THE BALANCING STRAP.
- 7. TREES AND PALMS MUST BE LIFTED WITH A CRANE OR BACKHOE APPROPRIATELY SIZED FOR THE SIZE AND WEIGHT OF THE TREE OR PALM AND LIFTED OR CARRIED DIRECTLY TO THE FINAL INSTALL LOCATION OR TRANSPORT TRAILER.
- 8. ONCE LIFTING BEINGS, ANY UNCUT ROOTS UNDER OR AROUND THE ROOTBALL THAT MAY YET REMAIN MUST BE IMMEDIATELY SEVERED WITH HAND PRUNING TOOLS TO MINIMIZE TEARING AND ROOT DAMAGE
- AGRIFORM PLANTING TABLETS (OR APPROVED EQUIVALENT) MUST BE EVENLY DISTRIBUTED AROUND THE PERIMETER OF THE PLANTING PIT AT THE RATE OF 2 TABLETS PER 1" TRUNK CALIPER PRIOR TO BACKFILLING.
- MYCORRHIZA (ROOTS® TRANSPLANT OR EQUIVALENT) MUST BE INCORPORATED INTO THE BACKFILL SOIL PRIOR TO BACKFILLING.
- 11. RELOCATED TREES AND PALMS MUST BE CENTERED IN THE PLANTING PIT, AND THE PIT BACKFILLED USING A 1:1 MIXTURE OF EXISTING SOIL AND 80:20 (DOT SAND:MUCK) SOIL MIX THOROUGHLY BLENDED TOGETHER. DO NOT USE MUDDY SOIL AS BACKFILL.
- 12. SMALL TREES AND PALMS MUST BE FIRMLY BRACED USING A MINIMUM OF FOUR 4"X 4" WOODEN BRACES ATTACHED TO 2" X 4" WOODEN BATTENS HELD IN PLACE WITH TWO STEEL BANDS, LARGER TREES MAY REQUIRE 6"X 6" WOODEN POSTS OR EVEN TELEPHONE POLES TO PROVIDE SUFFICIENT BRACING STRENGTH TO PREVENT TOPPLING DURING WIND EVENTS, A SUFFICIENT NUMBER OF BATTENS MUST BE STRATEGICALLY PLACED AROUND THE TRUNK SUCH THAT THE STEEL BANDS NEVER CONTACT THE TRUNK, NO BURLAP IS TO REMAIN UNDER THE WOODEN BATTENS ON TREES DURING BRACING, BUT SEVERAL LAYERS OF BURLAP SHOULD BE LEFT UNDER THE WOODEN BATTENS WHEN BRACING PALMS, NAILS SHALL NEVER BE DRIVEN DIRECTLY INTO THE TRUNK DURING BRACING. BRACING MUST REMAIN IN PLACE FOR A MINIMUM OF ONE YEAR.
- A TREE RING WITH A MINIMUM HEIGHT OF 6" MUST BE CONSTRUCTED 6-12" OUTSIDE THE OUTERMOST EDGE OF THE ROOTBALL AND AROUND THE ENTIRE PERIMETER OF THE ROOTBALL TO DIRECT IRRIGATION WATER AND ANY SUPPLEMENTS THAT ARE ADDED DOWN INTO THE ROOTBALL DURING ROOT REGENERATION.
- 14. ONCE THE TREE RING IS CONSTRUCTED, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE LIBERALLY APPLIED TO THE SURFACE AND THOROUGHLY WATERED IN.
- 15. ROOTBALLS MUST BE A THOROUGHLY WATERED IN USING A HOSE AND JOHNSON BAR INSERTED TO THE VERY BOTTOM OF THE ROOTBALL AND SWUNG BACK AND FORTH TO PREVENT FORMATION OF AIR POCKETS. THE JOHNSON BAR TECHNIQUE MUST BE REPEATED AT LEAST ONCE MORE WITHIN 6" OF THE TRUNK. MULCH MUST NOT BE APPLIED OR ALLOWED TO ACCUMULATE DIRECTLY AGAINST THE TRUNK.
- 16. ORGANIC MULCH (MELALEUCA IS PREFERRED) MUST BE APPLIED WITHIN 48 HOURS OF RELOCATION AT A DEPTH OF 3-4" OVER THE ENTIRE TOP OF THE ROOTBALL FROM THE TREE RING TO WITHIN 6" OF THE TRUNK. MULCH MUST NOT BE APPLIED OR ALLOWED TO ACCUMULATE DIRECTLY AGAINST THE TRUNK.
- PITS FROM WHICH THE RELOCATED TREES AND PALMS WERE REMOVED MUST BE CLEANED OFF ALL RESIDUAL ROOTS, STUMPS, AND PORTIONS THEREOF AND BACKFILLED WITH CLEAN FILL FLUSH WITH THE SURROUNDING GRADE.
- 18. RESTORE THE SURFACE WITH MATERIAL TO MATCH ADJACENT AREAS, MATERIAL TO BE APPROVED BY LANDSCAPE ARCHITECT. CONTRACTOR TO PROVIDE A MINIMUM OF ONE YEAR WARRANTY ON SETTLING AND PLANT MATERIAL FROM THE SUBSTANTIAL COMPLETION.
- 19. MULTI-TRUNK TREES AND PALMS MUST BE RELOCATED AS ONE UNIT WITH A SINGLE ROOTBALL
- PLANTING PITS FOR EDIBLE DATE PALMS (PHOENIX DACTYLIFERA) MUST BE BACKFILLED WITH PURE DOT SILICA SAND.

WARRANTY NOTES

- ALL RELOCATED TREES AND PALMS MUST BE GUARANTEED FOR ONE YEAR FROM THE DATE OF RELOCATION TO THEIR FINAL LOCATIONS.
- IF A TREE OR PALM DIES WITHIN THE 1-YEAR WARRANTY PERIOD, IT MUST BE REMOVED AND REPLACED AT CONTRACTOR'S EXPENSE.
- IF A TREE OR PALM PERFORMS POORLY WITHIN THE 1-YEAR WARRANTY PERIOD, IT MUST BE REMOVED AND REPLACED AT CONTRACTOR'S EXPENSE. THE DECISION TO REPLACE BASED ON POOR HEALTH IS AT THE DISCRETION OF THE LANDSCAPE ABCHITCHT.
- IF A TREE OR PALM SETTLES TO AN UNHEALTHY DEPTH WITHIN THE 1-YEAR WARRANTY PERIOD, AS DEEMED BY THE BY THE LANDSCAPE ARCHITECT, IT MUST BE RAISED TO THE CORRECT GRADE AT CONTRACTOR'S EXPENSE.



357 cypress drive, 1 tequesta, fl 33469 561.402.9414

www.nielsenlandarch.com

2135 GARDEN

SEAL (S TYLER NIELSEN - LA6667067)



09.05.2019

DATE ISSUE

08.15.2019 MB DRB 09.05.2019 REVISIO

L101

TREE DISPOSITION SCHEDULE

חו	EE DISPOSITION SCHEL	JULE					_					
#	BOTANICAL NAME	COMMON NAME	DBH.	HT.	SPREAD	ACTION	CRZ	TPZ	CANOPY	CONDITION	NATIVE	NOTES
1	VEITCHIA MERRILLII	CHRISTMAS PALM	6"	35'	6'	REMOVE	8'	8'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
2	COCOS NUCIFERA	COCONUT PALM	6"	25'	12'	REMOVE	8'	8'	113	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
3	FICUS BENJAMINA	WEEPING FIG	12"	4'	10'	REMOVE	NA	NA	0	POOR	NO	FICUS HEDGE - NO MITIGATION REQUIRED
4	VEITCHIA MERRILLII	CHRISTMAS PALM	6"	35'	6'	REMOVE	8'	8'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
5	FICUS BENJAMINA	WEEPING FIG	12"	4'	10'	REMOVE	NA	NA	0	POOR	NO	FICUS HEDGE - NO MITIGATION REQUIRED
6	FICUS BENJAMINA	WEEPING FIG	12"	4'	10'	REMOVE	NA	NA	0	POOR	NO	FICUS HEDGE - NO MITIGATION REQUIRED
7	FICUS BENJAMINA	WEEPING FIG	12"	4'	10'	REMOVE	NA	NA	0	POOR	NO	FICUS HEDGE - NO MITIGATION REQUIRED
8	MANGIFERA INDICA	MANGO	24"	38'	15'	REMOVE	24'	24'	176	MODERATE	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
9	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
10	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
11	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
12	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
13	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
14	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
15	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
16	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
17	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
18	PTYCHOSPERMA ELEGANS	SOLITAIRE PALM	4"	35'	6'	REMOVE	6'	6'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
19	VEITCHIA MERRILUI	CHRISTMAS PALM	6"	35'	6'	REMOVE	8'	8'	28	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
20	VEITCHIA MERRILLII	CHRISTMAS PALM	6"_	35'	6'	REMOVE	8'	8'	28	GOOD	_NO _	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
2 Y	MÄNGIFERA INDICA	MANGO	Y2"	20'	14'	REMOVE	24'	24'	153	MODERATE	V NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
22	FICUS ALTISSIMA	FIG	36"	36'	48'	REMOVE	36'	36'	1,809	GOOD	NO	INVASIVE
23	LIMISTOMIA CHINENSIS	CHINESE PAN PANA	№ "	28'	8'^	AREMOVE A				GOOD		PLADIT CONFLICTS WITH THE CONSTRUCTION ENVILOPE
24	LIVISTONIA CHINENSIS	CHINESE FAN PALM	18"	22'	8'	REMOVE	6'	6'	50	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
25	LIVISTONIA CHINENSIS	CHINESE FAN PALM	18"	22'	8'	REMOVE	6'	6'	50	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
26	LIVISTONIA CHINENSIS	CHINESE FAN PALM	18"	22'	8'	REMOVE	6'	6'	50	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE
27	LIVISTONIA CHINENSIS	CHINESE FAN PALM	18"	22'	8'	REMOVE	6'	6'	50	GOOD	NO	PLANT CONFLICTS WITH THE CONSTRUCTION ENVELOPE

TOTAL CANOPY AREA REMOVED =

2,893 SQUARE FEET (2,138 TREES & 755 PALM)

MITIGATION NOTES

THE PROPERTY OWNER IS RESPONSIBLE FOR THE MITIGATION OF THE ABOVE TREES SPECIFIED FOR REMOVAL.

TREES REMOVED EQUALS 2,138 SQUARE FEET OF CANOPY. THE LANDSCAPE DRAWINGS PROPOSE TO MITIGATE FOR THE REMOVAL OF THE TREES IN THE FOLLOWING MANNER:

PLANT THE EQUIVALENT OF (05) CATEGORY 1 (4 IN. DBH / 16 FT. HEIGHT / 8 FT. SPREAD) TREES ON-SITE.

PALMS REMOVED EQUALS 755 SQUARE FEET OF CANOPY. THE
LANDSCAPE DRAWINGS PROPOSE TO MITIGATE FOR THE REMOVAL OF THE
PALMS IN THE FOLLOWING MANNER:
PLANT THE EQUIVALENT OF (12) ROYAL PALMS, CATEGORY 4.
PLANT THE EQUIVALENT OF (08) COCONUT PALMS, CATEGORY 4.
1,000 SQUARE FEET OF MITIGATION CANOPY TOTAL.


1.2.1. 1.2.2. 1.2.3.




SEAL (S TYLER NIELSEN - LA6667067)



TREE DISPOSITION PLAN			
DATE	ISSUE		
08.15.2019	MB DRB		
09.05.2019	REVISION 01		





- LAYOUT AND VERIFY DIMENSIONS PRIOR TO CONSTRUCTION. NOTIFY LANDSCAPE ARCHITECT OF ANY DISCREPANCIES. LANDSCAPE ARCHITECT TO REVIEW AND APPROVE ALL LAYOUTS CONTAINED IN THE CONSTRUCTION DOCUMENTS PRIOR
- WRITTEN DIMENSIONS SHALL TAKE PRECEDENCE OVER SCALED DIMENSIONS. DO NOT SCALE DIMENSIONS FROM REDUCED 2.
- DIMENSIONS REFERRED TO AS "EQUAL" INDICATE SPACING WHICH IS EQUIDISTANT MEASURED TO THE CENTERLINES.



357 cypress drive, tequesta, fl 33469 561.402.9414

www.nielsenlandarch.com








LAYOUT PLAN ISSUE

08.15.2019 MB DRB 09.05.2019 RE VISION 01





PLANTING NOTES

- PLANT MATERIAL IS TO BE HEALTHY SPECIMENS FREE FROM DISEASE OR DAMAGE, AND IS TO BE MAINTAINED IN EXCELLENT CONDITION WHILE ON THE JOBSITE. LANDSCAPE ARCHITECT SHALL INSPECT PLANT MATERIAL UPON ARRIVAL TO JOBSITE AND WILL REJECT PLANT MATERIAL THAT DOES NOT MEET THE STANDARDS DESCRIBED WITHIN THE CONTRACT DOCUMENTS.
- THE LANDSCAPE ARCHITECT WILL PERIODICALLY INSPECT PLANT MATERIAL STOCKPILED AND/OR PLANTED ON SITE DURING THE COURSE OF CONSTRUCTION. PLANT MATERIAL NOT MEETING THE STANDARDS CONTAINED WITHIN CONTRACT DOCUMENTS SHALL BE REPLACED AT NO COST TO THE OWNER.
- PROVIDE MATCHING SIZES AND FORMS FOR EACH PLANT OF THE SAME SPECIES
- CONTRACTOR TO VERIFY ALL QUANTITIES. IN CASE OF DISCREPANCIES, GRAPHICALLY SHOWN QUANTITIES SHALL TAKE PRECEDENCE.
- ALL MATERIALS USED SHALL CONFORM TO THE GUIDELINES ESTABLISHED BY THE CURRENT AMERICAN STANDARDS FOR NURSERY STOCK, PUBLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
- ALL PLANT MATERIAL SHALL BE INSTALLED PLUMB AND PER THE SPECIFICATIONS CONTAINED WITHIN THE CONTRACT DOCUMENTS. ANY NECESSARY STAKING AND/OR OTHER SUPPORTS MATERIALS/METHODS SHALL BE SUBMITTED TO THE LANDSCAPE ARCHITECT FOR REVIEW AND APPROVAL PRIOR TO INSTALLATION.
- 7. THE CONTRACTOR SHALL PRUNE EXISTING AND/OR NEW TREES ONLY PER LANDSCAPE ARCHITECT DIRECTION.
- THE CONTRACTOR SHALL STAKE THE LOCATIONS OF ALL TREES AND B&B SHRUBS FOR LANDSCAPE ARCHITECT REVIEW AND APPROVAL, PRIOR TO INSTALLATION.
- ALL ROOT-WRAPPING MATERIALS THAT ARE NOT BIO-DEGRADABLE SHALL BE REMOVED FROM THE ROOT BALL. ROOT BALLS SHALL BE FREE OF WEEDS.
- 10. SPECIFIED PLANT MATERIAL SIZES SHALL BE CONSIDERED MINIMUM SIZES.
- FINISH GRADE OF PLANTING BEDS SHALL BE ONE (1) INCH BELOW ADJACENT FLATWORK, UNLESS SPECIFIED OTHERWISE
- 12. MULCH OR PLANTING BED DRESSING SHALL BE PLACED IN ALL PLANTING AREAS AS SPECIFIED. MULCH OR PLANTING BED DRESSING SHALL NOT BE PLACED WITHIN SIX (6) INCHES OF TREE TRUNKS. MULCHING SHOULD BE REPEATED ANNUALLY DURING THE AUTUMN TO A THREE (3) INCH DEPTH.
- 13. ALL PLANT MATERIAL SHOULD RECEIVE AN ORGANIC FERTILIZER IN LIMITED APPLICATION FOLLOWING INSTALLATION. TYPE AND APPLICATION RATE AND METHOD OF APPLICATION TO BE SPECIFIED BY THE CONTRACTOR AND APPROVED BY THE LANDSCAPE ARCHITECT
- 14. EXCESS FERTILIZER SHALL BE DISPOSED OF PROPERLY OFF-SITE. IT SHALL NOT BE DISPOSED OF IN STORM DRAINS AND/OR DRYWELLS.
- 15. STOCKPILED PLANT MATERIAL TO BE PLACED IN THE SHADE AND PROPERLY HAND-WATERED UNTIL PLANTED.
- MINI-NUGGET TYPE DECORATIVE BARK MULCH WILL BE USED TO RETURN NUTRIENTS TO THE SOIL, REDUCE MAINTENANCE AND MINIMIZE EVAPORATION FOR AREAS APPROXIMATE TO THE RESIDENCE. LARGER SHREDDED BARK MULCH WILL BE USED FOR STEEP AREAS SO SLOUGHING IS LESS LIKELY TO OCCUR.
- 17. PRESERVE & PROTECT ALL EXISTING VEGETATION INDICATED TO REMAIN AT ALL TIMES.
- ALL VEGETATION PROPOSED FOR OUTSIDE THE BUILDING ENVELOPE TO BE NATIVE UNLESS OTHERWISE NOTED. PLANTING THAT OCCURS OUTSIDE THE BUILDING ENVELOPE IS FOR RESTORATION PURPOSES ONLY OR IS SPECIFIC TO UTILITIES
- SIX (6) INCH PLANT MIX SHALL BE PROVIDED FOR ALL LAWN, TURF, AND NATIVE PLANTING ZONES. 18 INCH PLANT MIX SHALL BE PROVIDED FOR ALL PERENNIAL PLANTING BEDS UNLESS OTHERWISE NOTED.
- ALL PLANT MATERIAL SHALL BE FLORIDA GRADE #1 OR BETTER AS OUTLINED IN GRADES AND STANDARDS FOR NURSERY PLANTS, PARTS I AND II OF THE LATEST EDITION, PUBLISHED BY THE FLORIDA DEPARTMENT OF AGRICULTRE AND CONSUMER

A PLANTING SCHEDULE

_						
ABR.	QUANTITY	BOTANICAL NAME	COMMON NAME	SPECIFICATIONS		
TREES						
THE	4	TABEBUIA HETEROPHYLLA	PINK TRUMPET TREE	FG. 16 FT. OA. 4 IN. DBH. SINGLE LEADER / STANDARD FLORIDA #1		
MFR	2	MYRCIANTHES FRAGRANS	SIMPSON STOPPER	100 GAL. MULTI-TRUNK 14 FT. OA. LANDSCAPE ARCHITECT TO TAG AT HACKBERRY FARM		
BMO	2	BUCIDA MOLINETTI	SPINY BLACK OLIVE	45 GAL GROW BAG, 6 FT. OA LANDSCAPE ARCHITECT TO TAG AT BOTANICS WHOLESALE		
CSP	1	CHORISIA SPECIOSA	FLOSS SILK TREE	FG. 8 IN. DBH. 18 FT. HT. MIN. PROVIDE IMAGES FOR LANDSCAPE ARCHITECT'S APPROVAL		
0	4	CHRYSOPHYLLUM OLIVIFORMIS	SATIN LEAF	45 GAL 12 FT. OA. 2 IN. DBH MIN.		
CER	4	CONOCARPUS ERECTUS	GREEN BUTTONWOOD	45 GAL 12 FT. OA. 2 IN. DBH MIN.		
PRA	4	PIMENTA RACEMOSA	BAY RUM	45 GAL 12 FT. OA. 2 IN. DBH MIN.		
CDI	4	COCCOLOBA DIVERSIFOLIA	PIGEON PLUM	45 GAL 12 FT. OA. 2 IN. DBH MIN.		
SGL	4	SIMAROUBA GLAUCA	PARADISE TREE	45 GAL 12 FT. OA. 2 IN. DBH MIN.		
PALI	MS					
CNO	3	COCOS NUCIFERA 'GREEN MALAYAN'	COCONUT PALM	FG. CHARACTER CURVE 9 FT. CT. PROVIDE IMAGES FOR LANDSCAPE ARCHITECT APPROVAL		
CNU2	2	COCOS NUCIFERA 'GREEN MALAYAN'	COCONUT PALM	FG. CHARACTER CURVE 12 FT. CT. PROVIDE IMAGES FOR LANDSCAPE ARCHITECT APPROVAL		
CNU3	3	COCOS NUCIFERA 'GREEN MALAYAN'	COCONUT PALM	FG. CHARACTER CURVE 15 FT. CT. PROVIDE IMAGES FOR LANDSCAPE ARCHITECT APPROVAL		
PCO	11	PINANGA CORONATA	IVORY CANE PALM	45 GAL 10 FT. OA.		
REX	22	RHAPIS EXCELSA	LADY PALM	15 GAL 4 FT. OA.		
RRE	12	ROYSTONEA REGIA	ROYAL PALM	FG. 12 FT. GW.		
SLI	2	SATAKENTIA LIUKIUENSIS	SATAKENTIA PALM	FG. 9 FT. GW.		
LAR	GE SHRUBS					
CZ	30	CALYPTRANTHES ZUZYGIUM	MYRTLE OF THE RIVER	25 GAL 6 FT. OA. BUSH FORM FULL		
SHR	UBS					
CZ	90	CALYPTRANTHES ZUZYGIUM	MYRTLE OF THE RIVER	15 GAL 4 FT. OA. BUSH FORM FULL		
S	55	PSYCHOTRIA NERVOSA	WILD COFFEE	7 GAL. 24 IN. X 24 IN.		
5	20	AMPHITECNA LATIFOLIA	BLACK CALABASH	15 GAL 4 FT. HT.		
PP	68	POGONATHERUM PANICEUM	DWARF BAMBOO GRASS	7 GAL. 36 IN. X 36 IN.		
PG	4	PHILODENDRON GIGANTEUM	SAME	15 GAL 36 IN. X 36 IN.		
XX	86	PHILODENDRON XANADU	SAME	7 GAL. 24 IN. X 24 IN.		
٧	64	STRELITZIS PARVIFOLIA JUNCEA	LEAFLESS BIRD OF PARADISE	7 GAL. 36 IN. HT.		
GROUNDCOVERS						
LM	792	LIRIOPE MUSCARI	SAME	3 GAL. 18" O.C.		
AR	204	AJUGA REPTANS 'CHOCOLATE CHIP'	AJUGA	1 GAL. 12" O.C.		
EL	500	ERNODEA LITTORALIS	GOLDEN CREEPER	3 GAL. 18" O.C.		
MISC).					
ALL SOD AREAS TO BE REPLACED WITH ZOYSIA 'ZEON'						
LANDSCAPE ARCHITECT TO HAVE \$2000 WHOLESALE ACCENT PLANT ALLOWANCE						

CITY OF MIAMI BEACH LANDSCAPE LEGEND

	LANDSCAPE LEGEND INFORMATION REQUIRED TO BE PERMANENTLY AFFIXED TO PLANS		
	Zuming District RS-3 tot Area 23,361 Acre		-
	OPEN SPACE	REQUIRED/ ALLOWED	PROVIDED
٠.	Square feet of required Open Space as indicated on site plan: Lot Area = $23,361$ s.f.x 09 %= $2,102$ s.f.	2,102	3,973
R	Square feet of parking lot open space required as indicated on site plan:		
	Number of parking spaces NA x 10 s.f. parking space =	NA	NA
5.5	Total square feet of landscaped open space required: A+B=	2,102	3,973
	LAWN AREA CALCULATION		
١.	Square feet of landscaped open space required	2,102	3,973
B.	Maximum lawn area (sod) permitted= 50 % x 3,973f.	1,986	1,900
	TREES		
ί,	Number of trees required per lot or net lot acre, less existing number of		
		23	27
R	Number of trees required per lot or net lot acre, less existing number of trees meeting minimum requirementses 23 trees _ NA _ net lot acres - number of existing trees— 14 Natives required: Number of trees provided x 30% =	23 7	27
R	Number of trees required per lot or net lot acre, less existing number of trees meeting minimum requirements= 23 trees x NA net lot acres - number of existing trees-	23 7 12	27 20 20
R.	Number of trees required per lot or net lot acre, less existing number of trees meeting minimum requirements. 23. trees . NA net lot acres - number of existing trees- W. Halves required: Number of trees provided a 30% = 15. town minimumer, drought and and liberant required: Number of trees provided s. 50%: 55 receive (receive minimum werearse specing of 20" o.c.)		20 20
R	Number of trees required per lot or net lot acre, less existing number of trees meeting nitrium requirements. 23 trees x MA , net lot acres -number of existing trees- 18 town existence when ber of trees provided a 20% = 18 town maintenance / drought and all tolerant required. Number of trees provided a 50% - Street Trees (maximum average specing of 20" o.c.) MA , man fret atling street chidded by 20"-	23 7 12 NA	27 20 20 NA
R	Number of trees required per lot or net lot acre, less existing number of trees meeting minimum requirements. 23. trees . NA net lot acres - number of existing trees- W. Halves required: Number of trees provided a 30% = 15. town minimumer, drought and and liberant required: Number of trees provided s. 50%: 55 receive (receive minimum werearse specing of 20" o.c.)		20 20
R	Number of trees required per lot or net lot acre, less existing number of trees meeting infirmm requirements: 23 trees x NA net lot acres - number of existing trees* % Hadvox required: Number of loves provided 3 20% = % 18 tow ministractors; drought and salt tolerant required: Number of trees provided a 50%: Street frees (namum average sporting of 20" o.c.) NA innar first along street chiddle by 20"= Street trees sported a loved directly beneath power lines:		20 20
R C D.	Number of trees required per lot or net lot acre, less existing number of trees meeting minimum requirements— 23. trees: NA net bit acres - number of existing trees* 16. Halves required: Number of trees provided 8.3% = 16. How minimum records of trees provided 8.3% = 16. How minimum records of trees provided 8.3% = 16. Number of trees provided 8.3% = 1	7 12 NA	20 20 NA

PLANTING REFERENCE IMAGERY



PINK TABEBUIA



SIMPSON STOPPER













DWARF BAMBOO GRASS WILD COFFEE

COCONUT PALM







FLOSS SILK













150 160

15 30





IVORY CANE PALM





LADY PALM

GREEN BUTTONWOOD WEST INDIAN HOLLY



GIGANTEUM







ROYAL PALM

L700


SEAL (S TYLER NIELSEN - LA6667067)


09.05.2019


08.15.2019 09.05.2019


tequesta, fl 33469 561.402.9414

www.nielsenlandarch.com










www.nielsenlandarch.com



5 GARDEN 3 N E










09.05.2019 REVISION 01

SCALE AS NOTED:






SCALE: 3/32" = 1'- 0"



LOOSEN & SCORE

SHRUB PLANTING DETAIL

SCALE: 3/32" = 1'- 0"



5 LAYERS OF BURLAP

5 P.T. WOOD BATTENS

@ 2" x 4" x 16"

SECURE BATTENS WITH 2-3/4"

HI CARBON STEEL BANDS TO HOLD BATTENS IN PLACE

DURING PLANTING PROCESS.

HEIGHT OF THE TREE FOR

LANDSCAPE ARCHITECT).

EXPOSED WOOD SURFACES, (COLOR TO BE APPROVED BY

DO NOT NAIL BATTENS TO TREE.

THE HEIGHT OF BATTENS SHALL

ADEQUATE BRACING. PAINT ALL

3 PAINTED BRACES @ 4" x4" FOR TREES AND CHARACTER TREES.

3 PAINTED BRACES @ 2" x 4" FOR SMALL TREES, (COLOR TO BE

- 3 STAKES @ 2" x 4" x 24" -TOP OF STAKE 6" ABOVE GRADE


APPROVED BY LANDSCAFE ARCHITECT).


MOUND AND COMPACT SOIL

NO LESS THAN 12", ADJUST

HEIGHT TO PLACE TOP OF POOT BALL EVEN WITH GRADE

2" x 4" STAKES PAD BURIED 3" BELOW GRADE





PLANT & SHRUB SPACING DETAIL SCALE: 3/32" = 1'- 0"

TREE PLANTING AND STAKING DETAIL

3" PINE NEEDLE MULCH-


4" CONTINUOUS -

SOIL SAUCER RIM

SPECIFIED PLANTING

EXISTING SOIL OR

SCALE: 3/32" = 1'- 0"




www.nielsenlandarch.com




09.05.2019

SECOND LEVEL IRRIGATION PLAN
DATE ISSUE

08.15.2019 MB DRB 09.05.2019 REVISION 01





www.nielsenlandarch.com









09.05.2019

ROOF	LEVEL	IRRIGATION
DATE		ISSUE

08.15.2019 MB DRB 09.05.2019 REVISION 01






HSL16-R TELLURIDE

LMG1-AF MAGLIO

: AVENUE

357 cypress drive, tequesta, fl 33469 561.402.9414

www.nielsenlandarch.com



LAMP

LED

LED

NA

AMPS

.05 AMPS

.041 AMPS

LUMENS

300

CONFIRM LOCATION IN THE FIELD WITH L.A.

AMPS TOTAL

.35 AMPS TOTAL

0.697 AMPS TOTAL

ARDEN 35 C71381

SEAL (S TYLER NIELSEN - LA6667067)



ISSUE MB DRB

REVISION 01

