

1  
49

## EAST-WEST SITE SECTION FACING NORTH

SCALE: 1/16" = 1'-0"



2  
49

## 3D WEST ELEVATION


SCALE: 1/16" = 1'-0"



3  
49

## 3D EAST ELEVATION

SCALE: 1/16" = 1'-0"



4  
49

## 3D NORTH ELEVATION

SCALE: 1/16" = 1'-0"



5  
49

## 3D SOUTH ELEVATION

SCALE: 1/16" = 1'-0"

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"


(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139

HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

EAST-WEST SITE SECTION

12/9/2019



NOTE:  
 -LANDSCAPE IRRIGATION BY OTHERS  
 -SEE TREE DISPOSITION PLAN FOR EXISTING VEGETATION SPECIES AND SPECS.

1  
50

# LANDSCAPE PLAN

SCALE: 1/16" = 1'-0"

Casto Miguel Juncal, RLA 1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
 LA6667184 (1225 & 1235 UNDER UNIFICATION)  
 President/ Landscape Architect 1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
 Juncal Design Studio, LLC. HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019  
 786.877.2034 LANDSCAPE PLAN  
 juncaldesignstudio@gmail.com 12/9/2019

LANDSCAPE CANOPY SCHEDULE							
ABBREV.	QTY	NATIVE	COMMON NAME	SCIENTIFIC NAME	PLAN SYMBOL	IMAGE	SPECIFICATIONS
BU SI	4	X	Gumbo Limbo Tree	Bursera simaruba			14' HT OA., 16' SPR. 6" CAL FG CHARACTER
CH CA	6		Cat Palm	Chamaedorea cataractarum			6' HTm 25G, FULL
CO ER	3	X	Green Buttonwood	Conocarpus Erectus			16' Ht., 16' Spr., 4" CAL FG, CHARACTER
CO NU	10		Coconut Palm	Cocus nuifera			6' Ht. 25G FULL
CO UV	3	X	Sea Grape	Coccoloba uvifera			17' OA HT., 16' SPR, 5" Cal, SINGLE TRUNK, 5' CT, FG, CHARACTER
FI BE	1		Weeping Fig Tree	Ficus Benjamina			18' HT, 18' SPR. 24" Cal FG, CHARACTER
PA UT	3	X	Screw Pine	Pandanus Utilis			12' OA HT, FULL 5' CT, FG SINGLE TRUNK

LANDSCAPE UNDERSTORY SCHEDULE								
ABBREV.	QTY	LARGE SHRUB OR TREE	NATIVE	SCIENTIFIC NAME	COMMON NAME	PLAN SYMBOL	SPACING	SPECIFICATIONS
AL CA	71			Alocasia 'California'	Elephant Ear		2' O.C.	3G, 2' HT., 2' SPR., FULL
AL PU	24			Alpinia 'Purpurata'	Red Ginger		2'-6" O.C.	7G, 2.5" HT, 2.5' SPR., FULL
AL ZE	35		X	Serenoa repens 'Cinerea'	Shell Ginger		2'-6" O.C.	7G, 5' HT, 2.5' SPR., FULL
CL GU	39	X	X	Clusia 'Guttifera'	Small Leaf Clusia		4' O.C.	7G, 6' HT, 4' SPR., FULL
CO ER	72		X	Conocarpus 'Erectus'	Silver Buttonwood		2'-6" O.C.	15G, 5' HT, 2.5' SPR., FULL
CO UV	66		X	Coccoloba 'Uvifera'	Sea Grape		2'-6" O.C.	3' HT, 20" SPR, 7G, FULL.
ER LI	29		X	Enodea 'Littoralis'	Beach Creeper		1'-6" O.C.	1.5' HT, 1.5' SPR, 3G, FULL
ZO JA	1,529 SF			Zoysia japonica 'Empire'	Empire Zoysia		---	SOD, UNDER 6" MATURE HT. (UNMAINTAINED), NON-NATIVE

Casto Miguel Juncal, RLA 1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
 LA6667184  
 President/ Landscape Architect  
 Juncal Design Studio, LLC.  
 786.877.2034  
 juncaldesignstudio@gmail.com


(1225 & 1235 UNDER UNIFICATION)  
 1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
 HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019  
 LANDSCAPE SCHEDULES  
 12/9/2019

GENERAL NOTES:

1. PLANT MATERIAL: ALL PLANT MATERIAL SHALL BE FLORIDA #1 OR BETTER AS ESTABLISHED BY "GRADES AND STANDARDS FOR NURSERY PLANTS" OF THE STATE OF FLORIDA, DEPARTMENT OF AGRICULTURE.
2. ALL TREES, SHRUBS AND GROUNDCOVERS SHALL BE OF THE SIZES AS SPECIFIED IN THE PLANT LIST.
3. QUANTITIES LISTED ON THE THE PLANT LIST ARE FOR ESTIMATING PURPOSES. CONTRACTOR SHALL VERIFY ALL QUANTITIES. MULCH, TOPSOIL, FERTILIZER, ETC. SHALL BE INCLUDED IN THE UNIT COST OF THE PLANTS.
4. WHERE THERE IS A DISCREPANCY EITHER IN QUANTITIES, PLANT NAMES, SIZES OR SPECIFICATIONS BETWEEN THE PLAN OR PLANT LIST, THE PLAN TAKES PRECEDENCE.
5. ALL PLANTING BEDS AND WATER BASINS FOR TREES SHALL BE COVERED WITH A 3" MINIMUM DEPTH OF SHREDDED EUCALYPTUS OR FLORIMULCH GRADE 'B' OR BETTER.
6. THE PLANTING PLAN SHALL BE INSTALLED IN COMPLIANCE WITH ALL EXISTING CODES AND APPLICABLE DEED RESTRICTIONS.
7. SOD: ALL AREAS NOT USED FOR BUILDINGS, VEHICULAR USE AREAS, WALKS OR PLANTING BEDS SHALL BE GRASSED. GRASSING SHALL EXTEND TO ANY ABUTTING STREET PAVEMENT EDGE AND TO THE MEAN WATERLINE OF ANY ABUTTING CANAL, LAKE OR WATERWAY.
8. PLANTING SOIL: ALL TREES AND SHRUBS SHALL BE PLANTED WITH A MINIMUM OF 12" TOPSOIL AROUND AND BENEATH THE ROOTBALL. MINIMUM TOPSOIL SHALL BE 6" FOR GROUNDCOVER AREAS AND 2" FOR SODDED GRASS AREAS.
9. PLANTING SOIL TO BE A WEED-FREE MIXTURE OF 50% SAND, 40% MUCK, AND 10% CANADIAN PEAT. ALL PLANT MATERIAL TO RECEIVE PLANTING SOIL AS PER DETAILS.
10. CONTRACTOR IS RESPONSIBLE FOR DETERMINING ALL UTILITY LOCATIONS AND INSTALLING FACILITIES SO AS TO NOT CONFLICT. ALL DAMAGE TO EXISTING UTILITIES OR IMPROVEMENTS CAUSED BY CONTRACTOR SHALL BE REPAIRED AT NO ADDITIONAL COST TO THE OWNER.
11. CONTRACTOR TO NOTIFY "SUNSHINE" AT 1-800-638-4097 TWO FULL BUSINESS DAYS PRIOR TO DIGGING FOR UNDERGROUND UTILITY LOCATIONS.
12. CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING FINAL GRADING OF ALL ASSOCIATED PLANTING AREAS.
13. AFTER FINAL GRADE, AREA TO BE RAKED TO 6" DEPTH AND ALL ROCK AND FOREIGN INORGANIC MATERIALS REMOVED AND DISPOSED OF PROPERLY OFF-SITE.
14. ALL PLANTING HOLES TO BE HAND DUG EXCEPT WHERE MACHINE DUG HOLES WILL NOT ADVERSELY AFFECT OR DAMAGE UTILITIES OR IMPROVEMENTS (SEE NOTE 8).
15. NO PLUNGING OF ANY TREE OR PALM WILL BE ACCEPTED. ALL PLANTS TO BE PLANTED AT THE NURSERY GRADE OR SLIGHTLY HIGHER.
16. CONTRACTOR SHALL STAKE & GUY ALL TREES AND PALMS AT TIME OF PLANTING AS PER THE APPROPRIATE DETAIL. CONTRACTOR IS RESPONSIBLE FOR THE MAINTENANCE AND/OR REPAIR OF ALL STAKING AND GUYING DURING WARRANTY PERIOD AND REMOVAL & DISPOSAL OF STAKING AFTER ESTABLISHMENT PERIOD.
17. FERTILIZER FOR GRASS AREAS SHALL BE NPK 16-4-8 @ 12.5 LBS/1000 S.F. OR 545 LBS/ACRE. NITROGEN 50% SLOW RELEASE FORM & FERTILIZER TO INCLUDE SECONDARY MICRONUTRIENTS.
18. SUBSTITUTIONS AND CHANGES: ALL SUBSTITUTIONS AND CHANGES SHALL BE APPROVED IN WRITING PRIOR TO INSTALLATION. ANY DISCREPANCIES BETWEEN PLANS, SITE AND SPECIFICATIONS SHALL BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE LANDSCAPE ARCHITECT, THE OWNER AND GOVERNING MUNICIPALITY.
19. WATERING: ALL PLANT MATERIAL SHALL BE WATERED IN AT TIME OF PLANTING IN ACCORDANCE WITH STANDARD NURSERY PRACTICES. IN ADDITION, CONTRACTOR WILL CONTINUE WATERING OF PLANT MATERIAL UNTIL SUBSTANTIAL COMPLETION AND AS NEEDED THEREAFTER FOR A PERIOD OF 2 MONTHS.
20. ALL NEW PLANT MATERIAL SHALL BE GUARANTEED FOR 1 YEAR FROM TIME OF FINAL ACCEPTANCE OF PROJECT. ANY PLANT MATERIAL NOT IN A HEALTHY GROWING CONDITION WILL BE REPLACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER WITHIN 10 DAYS OF NOTIFICATION. FOR ALL REPLACEMENT PLANT MATERIAL, THE WARRANTY PERIOD SHALL BE EXTENDED AN ADDITIONAL 45 DAYS BEYOND THE ORIGINAL WARRANTY PERIOD. ALL TREES THAT LEAN OR ARE BLOWN OVER, CAUSED BY WINDS LESS THAN 75 MPH, WILL BE RE-SET AND BRACED BY THE CONTRACTOR AT NO ADDITIONAL COST TO THE OWNER.
21. THE SUCCESSFUL BIDDER SHALL FURNISH TO THE OWNER A UNIT PRICE BREAKDOWN FOR ALL MATERIALS. THE OWNER MAY, AT ITS DISCRETION, ADD OR DELETE FROM THE MATERIALS UTILIZING THE UNIT PRICE BREAKDOWN SUBMITTED.
22. NO PLANT MATERIAL WILL BE ACCEPTED SHOWING EVIDENCE OF CABLE, CHAIN MARKS, EQUIPMENT SCARS, OR OTHERWISE DAMAGED.
23. PLANT MATERIAL WILL NOT BE ACCEPTED WHEN THE BALL OF EARTH SURROUNDING ITS ROOTS HAS BEEN CRACKED, BROKEN OR OTHERWISE DAMAGED.
24. ROOT-PRUNE ALL TREES A MINIMUM OF (8) WEEKS PRIOR TO PLANTING.
25. ALL LANDSCAPED AREAS WILL BE IRRIGATED BY AN UNDERGROUND, AUTOMATIC, RUST-FREE IRRIGATION SYSTEM PROVIDING 100% COVERAGE AND 100% SPRAY OVERLAP. THE SYSTEM SHALL BE MAINTAINED IN GOOD WORKING ORDER AND DESIGNED TO MINIMIZE WATER ON IMPERVIOUS SERVICES AND NOT OVERSPRAY WALKWAYS. A RAIN SENSOR DEVICE SHALL BE INSTALLED TO OVERRIDE THE IRRIGATION CYCLE OF THE SYSTEM WHEN ADEQUATE RAINFALL HAS OCCURRED.
26. ALL PLANT MATERIAL PLANTED WITHIN THE SIGHT DISTANCE TRIANGLE AREAS (SEE PLAN) SHALL PROVIDE UNOBSTRUCTED CROSS-VISIBILITY AT A HORIZONTAL LEVEL BETWEEN 30 INCHES AND 8 FEET ABOVE ADJACENT STREET GRADE.
27. NO CANOPY TREES SHALL BE PLANTED WITHIN 12 FEET OF A LIGHT POLE. NO PALM SPECIES SHALL BE PLANTED WITHIN 6 FEET OF A LIGHT POLE.
28. GROUND COVER PLANTINGS SHALL PROVIDE NOT LESS THAN 50 PERCENT COVERAGE IMMEDIATELY UPON PLANTING AND 100 PERCENT COVERAGE WITHIN 6 MONTHS AFTER PLANTING.

Casto Miguel Juncal, RLA 1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

(1225 & 1235 UNDER UNIFICATION)  
1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019  
LANDSCAPE GENERAL NOTES  
12/9/2019




TREE TABLE														
No.	TREE NAME	DISPOSITION	NATIVE	DIAMETER (")	HEIGHT (')	SPREAD (')	No.	TREE NAME	DISPOSITION	DIAMETER (")	HEIGHT (')	SPREAD (')		
1	FICUS	REMAIN		4.00	25.00	10.00	32	FISH TAIL PALM	REMAIN	0.60	24.00	10.00		
2	FICUS	REMAIN		1.00	30.00	5.00	33	FISH TAIL PALM	REMAIN	0.60	24.00	10.00		
3	TRAVELER'S PALM	REMAIN		0.90	20.00	5.00	34	FISH TAIL PALM	REMAIN	0.60	24.00	10.00		
4	FISH TAIL PALM	REMAIN		2.00	25.00	25.00	35	TRAVELER'S PALM	REMAIN	0.80	24.00	15.00		
5	TRAVELER'S PALM	REMAIN		0.80	10.00	-	36	TRAVELER'S PALM	REMAIN	0.80	24.00	15.00		
6	TRAVELER'S PALM	REMAIN		0.80	12.00	5.00	37	TRAVELER'S PALM	REMAIN	0.80	26.00	15.00		
7	FISH TAIL PALM	REMAIN		2.00	20.00	10.00	38	TRAVELER'S PALM	REMAIN	0.80	24.00	15.00		
8	TRAVELER'S PALM	REMAIN		0.90	15.00	10.00	39	TRAVELER'S PALM	REMAIN	0.80	22.00	15.00		
9	TRAVELER'S PALM	REMAIN		0.90	15.00	10.00	40	MACARTHUR PALM	REMAIN	0.80	24.00	10.00		
10	TRAVELER'S PALM	REMAIN		0.90	15.00	30.00	41	ADONIDIA PALM	REMAIN	0.67	30.00	8.00		
11	TRAVELER'S PALM	REMAIN		0.90	15.00	30.00	42	ADONIDIA PALM	REMAIN	0.67	24.00	8.00		
12	TRAVELER'S PALM	REMAIN		0.90	15.00	30.00	43	ADONIDIA PALM	REMAIN	0.67	30.00	8.00		
13	FISH TAIL PALM	REMAIN		0.50	12.00	-	44	ADONIDIA PALM	REMAIN	0.67	18.00	8.00		
14	DRACEANA MARGINATA	REMAIN		1.10	15.00	30.00	45	ADONIDIA PALM	REMAIN	0.67	24.00	8.00		
15	ARECA	REMOVE		0.40	12.00	5.00	46	ADONIDIA PALM	REMAIN	0.67	24.00	8.00		
16	HIBISCUS	REMAIN		0.30	7.00	-	47	ADONIDIA PALM	REMAIN	0.67	24.00	8.00		
17	BUSHES	REMAIN		0.30	10.00	10.00	48	ADONIDIA PALM	REMAIN	0.67	18.00	8.00		
18	FICUS	REMAIN		0.30	12.00	-	49	ADONIDIA PALM	REMAIN	0.67	22.00	8.00		
19	SML LEAF CLUSIA TREE	REMAIN	X	0.40	18.00	15.00	50	ROYAL PALM	REMAIN	1.67	50.00	22.00		
20	ORANGE GEIGER TREE	REMAIN	X	0.40	14.00	9.00	51	COCONUT PALM	REMAIN	1.15	30.00	20.00		
21	DRACEANA MARGINATA	REMAIN		0.40	12.00	10.00	52	BAMBOO	REMAIN	0.25	16.00	16.00		
22	BOUGAINVILLEA TREE	REMAIN		0.40	18.00	18.00	53	CHINESE FAN PALM	REMAIN	1.00	20.00	20.00		
23	SML LEAF CLUSIA TREE	REMAIN	X	0.40	18.00	15.00	54	ADONIDIA PALM DBL	REMAIN	0.50	22.00	13.00		
24	FISH TAIL PALM	REMAIN		0.60	22.00	10.00	55	CABADA PALM	REMAIN	0.25	18.00	8.00		
25	FISH TAIL PALM	REMAIN		0.60	22.00	10.00	56	TRAVELER'S PALM	REMAIN	0.90	15.00	15.00		
26	FISH TAIL PALM	REMAIN		0.60	22.00	10.00	57	TRAVELER'S PALM	REMAIN	0.90	15.00	15.00		
27	FISH TAIL PALM	REMAIN		0.60	22.00	10.00	58	TRAVELER'S PALM	REMAIN	0.90	15.00	15.00		
28	FISH TAIL PALM	REMAIN		0.60	22.00	10.00	59	CABADA PALM	REMAIN	0.25	18.00	8.00		
29	SEA GRAPE TREE	REMAIN	X	0.33	18.00	10.00	60	CABADA PALM	REMAIN	0.25	18.00	8.00		
30	COCONUT PALM	REMAIN		0.83	28.00	18.00	61	ADONIDIA PALM DBL	REMAIN	0.50	19.00	16.00		
31	SIMPSON STOPPER	REMAIN	X	0.40	14.00	8.00	62	ROYAL PALM	REMAIN	1.67	58.00	22.00		

NOTE: ALL EXISTING PALMS AND SHRUBS IN GOOD CONDITION

1  
53  
**TREE DISPOSITION PLAN**  
NOT TO SCALE


Casto Miguel Juncal, RLA  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
(1225 & 1235 UNDER UNIFICATION)  
1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019  
TREE DISPOSITION PLAN  
12/9/2019



(2" cal. and under)  
**SMALL TREE PLANTING DETAIL**

N.T.S.




**CIGARED SABAL  
PALM PLANTING DETAIL**

N.T.S.


Casto Miguel Juncal, RLA  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
(1225 & 1235 UNDER UNIFICATION)  
1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019  
LANDSCAPE DETAILS  
12/9/2019



(2" cal. and over)  
**LARGE TREE PLANTING DETAIL**

N.T.S.




**LARGE PALM PLANTING DETAIL**

N.T.S.


Casto Miguel Juncal, RLA  
 LA6667184  
 President/ Landscape Architect  
 Juncal Design Studio, LLC.  
 786.877.2034  
 juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
 (1225 & 1235 UNDER UNIFICATION)  
 1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
 HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019  
 LANDSCAPE DETAILS  
 12/9/2019



## MULTI- TRUNK AND SMALL TREE (2" cal. and under) PLANTING DETAIL

N.T.S.




## TREE PRESERVATION BARRICADE FENCING DETAIL

N.T.S.


SPACE PLANTS

N.T.S.



## SHRUB PLANTING DETAIL

N.T.S.



## SHRUB / GROUNDCOVER SPACING / PLANTING DETAIL

N.T.S.

Casto Miguel Juncal, RLA  
 LA6667184  
 President/ Landscape Architect  
 Juncal Design Studio, LLC.  
 786.877.2034  
 juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"

(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139


HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

LANDSCAPE DETAILS

12/9/2019




SIGN ENLARGEMENT



NOTES:

1. TREE PROTECTION FENCE (TPF) SHALL BE INSTALLED PRIOR TO ANY SITE WORK, CLEARING OR DEMOLITION.
2. TPF SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
3. REMOVE TPF ONLY WITH WRITTEN APPROVAL FROM CITY URBAN FORESTER AFTER ALL SITE WORK HAS BEEN COMPLETED.
4. NO CONSTRUCTION ACTIVITIES PERMITTED WITHIN TPF WITHOUT URBAN FORESTER APPROVAL



4' CHAIN LINK TREE PROTECTION FENCE

ELEVATION

Casto Miguel Juncal, RLA  
 LA6667184  
 President/ Landscape Architect  
 Juncal Design Studio, LLC.  
 786.877.2034  
 juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"


(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139

HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

LANDSCAPE DETAILS


12/9/2019



1  
59

# SITE LIGHTING PLAN

SCALE: 1/16" = 1'-0"



Casto Miguel Juncal, RLA  
 LA6667184  
 President/ Landscape Architect  
 Juncal Design Studio, LLC.  
 786.877.2034  
 juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
 (1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
 HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

SITE LIGHTING PLAN  
 12/9/2019



1  
60

VIEW AT POOL TERRACE


Casto Miguel Juncal, RLA  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

VIEW AT POOL TERRACE

12/9/2019



1  
61

## VIEW FROM REAR GARDEN

Casto Miguel Juncal, RLA  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139

HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

VIEW FROM REAR GARDEN

12/9/2019



1  
62

## FRONT VIEW FROM STREET NW

Recommendations from Staff at the City of Miami Beach Planning Department were considered regarding the dense landscape in the front yard. Landscaping was re-designed from First Submittal.

Casto Miguel Juncal, RLA  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139

HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

FRONT VIEW FROM STREET NW

12/9/2019



1  
63

## FRONT VIEW FROM STREET SW

Recommendations from Staff at the City of Miami Beach Planning Department were considered regarding the dense landscape in the front yard. Landscaping was re-designed from First Submittal. The view here shows the "corridor" available between the 2 structures. A view to the rear yard can be seen from the street, while still maintain privacies.

Casto Miguel Juncal, RLA  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"  
(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139  
HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

FRONT VIEW AT STREET SW

# 1235 LENOX AVENUE

## Tree Mitigation Requirements

### REPLACING THE TREE CANOPY

THE REPLACEMENT TREES ARE BASED ON THE TOTAL SQUARE FOOTAGE OF THE NON-SPECIMEN TREES TO BE REMOVED.

CANOPY MEASUREMENT SHALL BE ROUNDED UP TO THE NEAREST FOOT.

### PLANTING REQUIREMENTS

IF YOU PLANT A:	WITH THIS MINIMUM SIZE:	YOU WILL GET THIS CREDIT (IN SQ. FT.)
CATEGORY 1	12' OVERALL HEIGHT	300
CATEGORY 2	10' OVERALL HEIGHT	150

### PROJECT REMOVAL DATA

CANOPY REMOVED (SQ. FT.) TAKEN FROM TREE DISPOSITION PLAN	19.63	
REQUIRED CANOPY REPLACEMENT	20	

### PROJECT MIGRATION DATA

PROVIDED TREE	QUANTITY PROVIDED	TOTAL CANOPY CREDIT
CATEGORY 1 - 12' O.A.	14	4,200
CATEGORY 2 - 10' O.A.		
TOTAL CANOPY CREDIT REPLACEMENT		4,200

## LANDSCAPE LEGEND

INFORMATION REQUIRED TO BE PERMANENTLY AFFIXED TO PLANS

Zoning District RS-4 Lot Area 18,750 SF Acres 0.43

### OPEN SPACE

	REQUIRED/ ALLOWED	PROVIDED
A. Square feet of required Open Space as indicated on site plan: Lot Area = <u>18,750</u> s.f. x <u>22.85</u> % = <u>4,283.60</u> s.f.	<u>3,218.75 SF</u>	<u>4,283.60 SF</u>
B. Square feet of parking lot open space required as indicated on site plan: Number of parking spaces <u>0</u> x 10 s.f. parking space =	<u>0 SF</u>	<u>NA</u>
C. Total square feet of landscaped open space required: A+B=	<u>3,218.75 SF</u>	<u>4,283.60 SF</u>

### LAWN AREA CALCULATION

A. Square feet of landscaped open space required	<u>3,218.75 SF</u>	<u>4,283.60 SF</u>
B. Maximum lawn area (sod) permitted= <u>50</u> % x <u>3,218.75</u> s.f.	<u>1,609.38 SF</u>	<u>1,529.10 SF</u>

### TREES

A. Number of trees required per lot or net lot acre, less existing number of trees meeting minimum requirements=		
$5 \text{ (2 FRONT, 3 REAR)} \text{ trees} \times 1 \text{ net lot acres} - \text{number of existing trees} = 8$ <small>+13 (1 FOR EVERY 1000SF ABOVE 6000 SF)</small>	<small>(5 EXISTING AT REAR) (3 EXISTING IN THE GARDEN)</small>	
B. % Natives required: Number of trees provided x 30% =	<u>4</u>	<u>4</u>
C. % Low maintenance / drought and salt tolerant required: Number of trees provided x 50%=	<u>5</u>	<u>6</u>
D. Street Trees (maximum average spacing of 20' o.c.) <u>124'</u> linear feet along street divided by 20'= <u>6</u>	<u>6</u>	<u>5</u>
E. Street tree species allowed directly beneath power lines: (maximum average spacing of 20' o.c.): <u>NA</u> linear feet along street divided by 20'= <u>NA</u>	<u>NA</u>	<u>NA</u>

### SHRUBS

A. Number of shrubs required: Sum of lot and street trees required x 12=	<u>288</u>	<u>297</u>
B. % Native shrubs required: Number of shrubs provided x 50%=	<u>144</u>	<u>202</u>

### LARGE SHRUBS OR SMALL TREES

A. Number of large shrubs or small trees required: Number of required shrubs x 10%=	<u>29</u>	<u>39</u>
B. % Native large shrubs or small trees required: Number of large shrubs or small trees provided x 50%=	<u>16</u>	<u>39</u>

Casto Miguel Juncal, RLA  
LA6667184  
President/ Landscape Architect  
Juncal Design Studio, LLC.  
786.877.2034  
juncaldesignstudio@gmail.com

1225 LENOX RESIDENCE - GUEST COTTAGE "FORMER 1235 RESIDENCE"

(1225 & 1235 UNDER UNIFICATION)

1235 LENOX AVENUE, MIAMI BEACH, FL, 33139

HPB REVIEW - CSS FINAL SUBMITTAL - DEC. 9, 2019

LANDSCAPE WORKSHEET

12/9/2019