

TRRE MITIGATION CALCULATIONS

TOTAL PALMS REMOVED: __0 TOTAL DBH INCHES REMOVED: 35.5

Required Mitigation Per Sec. 46-61

(12) Trees - 12' Ht, 2" DBH, 6' Spread

(6) Trees - 16' Ht, 4" DBH, 8' Spread

Tree Species Diversity

(2) Required minimum number of species

Provided Mitigation:

(3) Trees - 12' Ht ,2" DBH, 6' Spread

(5) Trees - 16' Ht ,4" DBH, 8' Spread

Mitigation shortfall of (0) (2") DBH, trees = (0) __ to be paid into the

City of Miami Beach Tree Preservation Trust Fund.

SYMBOL LEGEND

TREE TO REMAIN


SEE LANDSCAPE PLANS FOR EXACT SPECIES AND LOCATIONS

TREE TO REMOVE

TREE CANOPY - DIA.

TREE DISPOSITION LEGEND 129.5 Trees relocated: Palms removed: Total DBH on-site: Trees removed (total): Root pruning: Total removed DBH: 76.5 Prohibited trees removed: Tree Trimming Total calculated removed DBH: 35.5 Ref. # Common Name Scientific Name **Condition Status** Avocado Persea americana 4.5 18 15 Fair 38 40 70 Good \$28,000 Swistania mahagoni Mahogany Tree Remain Schinus terabinthifolius 25 28 Brazillan Pappar Fair Ramova 30 25 Good Royal Poinciana Delonix regia Remain Strangler Fig. Ficus aurea 28 33 30 Fair Ramova Royal Poinciana Delonix regia 15 10 Fair Remove Ptychosperma elegana 12 Solitaira Palm B Good Remove

1. TREE DISPOSITION PLAN SCALE 1/16"= 1'-0"



GAIA/S DESIGN

GAIA/S DESIGN INC. 86.777.8716 gaia@gaiasdesign.c

OWNER Jorge M Campodonico

703.963.4438 jc@citylendinginc.co LANDSCAPE ARCHITECT

Diego Vanderbiest 6200 SW 80 ST MIAMI, FLORIDA 33143 (305) 528-4001

Diego Digitally signed by Diego Vanderbiest Date: rbiest 14:14:42 -04'00'

RCTEK ARCHITECTURE LLC

1395 BRICKELL AVE SUITE 900 MIAMI FL 33131 PH: 305.967.635



JOHN SACCO AR0004952


New Single Family Home 4354 N MICHIGÁN AVE MIAMI BEACH, FL 33140

FINAL SUBMITTAL DATE: 08/10/2020

THESE PLANS ARE FOR DRB REVIEW ONLY, THI ARE NOT TO BE CONSTRUED AS CONSTRUCTIO OCUMENTS UNTIL ALL BUILDING DEPARTMEN APPROVAL ARE OBTAINED

TREE **DISPOSITION PLAN**

DRB L.1



LANDSCAPE SCHEDULE

		TREES			
SYMBOL	QUAN.	PROPOSED MATERIAL	DESCRIPTION	NATIVE	WATER NEE
G SEZ	3	*Conocarpus erectus STREET TREE	12' HT, X 6' SPR, 2.5" DBH,	Y	LOW
		GREEN BUTTONWOOD	F.G.		
۵.,	5	Coccoloba diversiflora	16' HT, X 6' SPR, 4" DBH,	Y	LOW
		PIGEON PLUM	F.G.		
Me.	2	Phoenix canarlensis	10' C.T.	N	LOW
PC PC		CANARY ISLAND DATE PALM	F.G.		
	3	"Conocarpus erectus 'sericeus'	12' HT, X 6' SPR, 2.5" DBH,	Y	
SE		SILVER BUTTONWOOD	F.G.	<u>'</u>	
\bigcirc	1	*Bursera simaruba	18' HT, X 6' SPR, 4" DBH,	Y	LOW
Ų _{BS}		GUMBO LIMBO	F.G.		
(3)	1	Ligustrum japonicum	12' HT. X 8' SPR., MULTI TRUNK	N	MEDIUM
		JAPANESE PRIVET	F.G.	- "	
		SHRUBS			
SYMBOL	QUAN.	PROPOSED MATERIAL	DESCRIPTION	NATIVE	WATER NEE
051		*Conocarpus erectus	36" HT, X 24" SPR, / 36" O.C.		LOW
CE1	34	GREEN BUTTONWOOD	7 GAL.	Y	
	87	*Clusia guttifera	36" HT, X 24" SPR, / 36" O.C.		MEDIUM
CG		SMALL LEAF CLUSIA	7 GAL.	Y	
DT		Pittosporum tobira	18" HT, X 18" SPR, / 24" O.C.		MEDIUM
PT	43	CHINESE CHEESEWOOD	3 GAL.	N	
	3	Sabal minor	24" HT, X 18" SPR	Υ	LOW
SM		DWARF BLUE-STEM PALMETTO	7 GAL.		
	1	Cyrtostachys renda	7" HT OA HEIGHT	-	MEDIUM
LP		LIPSTICK PALM	15 GAL:	N	
		GROUND COVERS			
SYMBOL	QUAN.	PROPOSED MATERIAL	DESCRIPTION	NATIVE	WATER NEE
STWIDOL	458 29 104			NATIVE	LOW MEDIUM
FM		Ficus microcarpa 'Green Island' GREEN ISLAND FICUS	15" HT. X 15" SPR. / 15" O.C. 3 GAL.	N	
			24" HT. X 18" SPR. / 24" O.C.		
NB		Nephrolepis bisserata		Υ	
		MACHO FERN	3 GAL, FULL 12" HT, X 15" SPR, / 18" O.C.		
PO		Peperomia obtusifolia		N	
		BABY RUBBER PLANT	1 GAL. FULL	-	
JP CH	145 45 3	Lirlope muscarl 'Evergreen Glant'	12" HT. X 12" SPR. / 15" O.C.	N Y	LOW
		EVERGREEN GIANT LIRIOPE	1 GAL.		
		Juniperus chinensis 'Blue Rug'	18" HT. X 18" SPR. / 18" O.C.		
		JUNIPER GROUNDCOVER			
		Chamearops humilis	3' O.A. HT.		
PB1	15	EUROPEAN FAN PALM	7 GAL., FULL	N	MEDIUM
		Philodendron 'Burle Marx'	24" HT. X 24" SPR. / 36" O.C.		
MS	78	BURLE MARX PHILODENDRON	3 GAL.		LOW
		Microsorum scolopendrium	12" HT. X 12" SPR. / 15" O.C.	N	
		WART FERN	1 GAL.		
HL	48	*Hymenocallis latifolia	15" HT. X 12" SPR. / 18" O.C.	Y	LOW
HL			3 GAL, FULL		
HL	10	SPIDER LILLY	O GAL. I OLL		
	423 SF	SHIDER LILLY Stenotaphrum secundatum 'Floratam' ST. AUGUSTINE GRASS	SOLID EVEN SOD		LOW

LANDSCAPE LEGEND

LO	T AREA: 9,720 sf OPEN SPACE: 4,	860 sf	
		REQ.	PRO
A)	Minimum Number Of Required Trees Per Lot, 2 Front Lot - 3 Back Yard	5	5
B)	Minimum Number Of Required Street Trees, Maximum average spacing of 20 feet on center	4	4
C)	Additional Lot Trees Sec. 126-6 -(4) (1)additional Tree For Each 1,000 sf Above 6,000 sf	4	4
D)	Number of Existing Trees Existing trees required by law to be preserved on site and that meet the requirements of minimum tree size may be counted toward fulfilling the minimum tree requirements.	3	3
TO	TAL NUMBER OF TREES	10	10
E)	Shrubs Required The Minimum Number Shall Be 12 Shrubs Per The Number Of Required Lot And Street Trees	120	17:
F)	Large Shrubs Required Large shrubs shall be 10% of the required number of shrubs for the specific project	12	73
G)	Maximum permitted lawn grass/sod areas = 50%	2,430 sf	620



TREE TO REMOVE



FINAL SUBMITTAL DATE: 08/10/2020

 $G\Lambda I\Lambda /S$ DESIGN

GAIA/S DESIGN INC. 86.777.8716 gaia@gaiasdesign.c

Jorge M Campodonico 703.963.4438 jc@citylendinginc.co

Diego Vanderbies

Diego Digitally signed by Diego Vande Vande Date:

rbiest 2020.08.09 14:15:25 -04'00'

DIEGO J. VANDERBIEST RLA #6667355 RCTEK ARCHITECTURE LLC 1395 BRICKELL AVE SUITE 900 MIAMI FL 33131 PH: 305.967.6355

JOHN SACCO AR0004952

New Single Family Home 4354 N MICHIGAN AVE MIAMI BEACH, FL 33140

6200 SW 80 ST MIAMI, FLORIDA 33143 (305) 528-4001 SEAL

THESE PLANS ARE FOR DRB REVIEW ONLY, THI ARE NOT TO BE CONSTRUED AS CONSTRUCTIC DOCUMENTS UNTIL ALL BUILDING DEPARTMEN APPROVAL ARE OBTAINED

PROPOSED LANDSCAPE PLAN

DRB L.2

SYMBOL LEGEND

TREE TO REMAIN




TREE CANOPY - DIA.

1. PROPOSED LANDSCAPE PLAN SCALE 1/16"= 1'-0"






Conocarpus erectus 'Sericeus' Silver Buttonwood






Phoenix canariensis
Canary Island Date Palm




Ligustrum japonicum Japanese Privet








Cyrtostachys renda Lipstick Palm



Pittosporum tobira Japanese Cheesewood



Sabal minor Dwarf Blue-stem Palmetto



Clusia guttifera Small Leaf Clusia



Nephrolepis biserrata 'Macho' Macho Fern



Juniperus chinensis 'Blue Rug' Chinese Juniper




Hymenocallis latifolia Spider Lyli



Liriope muscari Lyliturf



Ficus microcarpa ' Ficus 'Green Island'



Philodendron 'Burle Marx'
Burle Marx Philodendron

GNIA/S DESIGN

GAIA/S DESIGN INC. 86.777.8716 gaia@gaiasdesign.co

OWNER Jorge M Campodonico 703.963.4438 jc@citylendinginc.co

LANDSCAPE ARCHITECT Diego Vanderbiest

6200 SW 80 ST MIAMI, FLORIDA 33143 (305) 528-4001 SEAL

Diego Digitally signed by Diego Vanderbiest Date: 2020.08.09 rbiest 14:15:03 -04'00'

DIEGO J. VANDERBIEST RLA #6667355 RCTEK ARCHITECTURE LLC 1395 BRICKELL AVE SUITE 900 MIAMI FL 33131 PH: 305.967.6355



JOHN SACCO AR0004952


New Single Family Home 4354 N MICHIGAN AVE MIAMI BEACH, FL 33140


FINAL SUBMITTAL DATE: 08/10/2020

THESE PLANS ARE FOR DRB REVIEW ONLY, THI ARE NOT TO BE CONSTRUED AS CONSTRUCTIO OCCUMENTS UNTIL ALL BUILDING DEPARTMEN APPROVAL ARE OBTAINED

PLANT BOARD

DRB L.3





SHRUB/GROUND COVER DETAIL


BACKFILL PLANTING HOLE W/ PREPARED SOIL MIX.

NOTE: WHEN PLANTING BEDS ARE ADJACENT TO CONCRETE SLABS, TOP OF MULCH TO BE A MINIMUM OF 1" BELOW TOP OF CONCRETE SLAB.

- EXISTING SUBGRADE

PLANT NOTES

- ALL PLANT MATERIAL TO BE FLORIDA NO. 1 OR BETTER FLORIDA DEPARTMENT OF AGRICULTURE GRADES AND STANDARDS; PARTS I AND II. 2ND EDITION: FEBRUARY 1998. RESPECTIVELY.
- ALL PLANTING BEDS TO BE TOPPED WITH 3" MULCH EXCLUDING TOP OF ROOT BALL (SEE PALM / TREE PLANTING DETAIL).
- 3. ALLTrees TO BE STAKED IN A GOOD WORKMANLIKE MANNER, NO NAIL STAKING IN TRUNKS PERMITTED.
- LANDSCAPE PLAN SHALL BE INSTALLED IN COMPLIANCE WITH ALL LOCAL CODES.
- ALL SOD SHALL BE ZOYSIA JAPONICA SOLID SOD, (UNLESS OTHERWISE NOTED) AND LAID WITH ALTERNATING AND ABUTTING JOINTS.
- 6. ALL PLANTING BEDS TO BE WEED AND GRASS FREE.
- 7. LANDSCAPE CONTRACTOR SHALL REVIEW ALL DRAWINGS AND PREPARE ONES OWN QUANTITY COUNTS(PRIOR TO BID COST AND COMPARE TO ARCHITECT'S PLANT LIST). LANDSCAPE CONTRACTOR IS RESPONSIBLE FOR ATTAINING ACCURATE COUNT OF PLANT MATERIALS SPECIFIED. IN THE EVENT OF DISCREPANCIES, LANDSCAPE CONTRACTORS SHALL BRING TO THE ATTENTION OF LANDSCAPE ARCHITECT. PLAN SHALL TAKE PRECEDENCE OVER PLANT LIST.
- 8. LANDSCAPE CONTRACTOR SHALL LOCATE AND VERIFY ALL UNDER-GROUND UTILITIES PRIOR TO DIGGING.
- 9. NO CHANGES SHALL BE MADE WITHOUT THE PRIOR CONSENT OF THE
- 10. ALL PLANTED AREAS TO RECEIVE 100% COVERAGE BY AN AUTOMATIC IRRIGATION SYSTEM, WITH A MINIMUM OF 50% OVERLAP. RAIN SELECT TO BE REPORTED.



NOTE:

-A BARRIER SHALL BE INSTALLED AROUND THE TREES IN ORDER TO PROTECT THEM DURING CONSTRUCTION.

-TREE BARRIER DIMENSIONS TO COMPLY WITH ANSI A300 STANDARDS. BARRIER DIMENSIONS SHALL BE 1' PER 1" OF DBH.

-BARRIER SHALL BE LOCATED A MINIMUM OF 10' FROM THE FACE OF TRUNK IN ALL DIRECTIONS.

Y BARRIER Range ex 2050

N.T.S.

ROOT PRUNING SPECIFICATIONS

ALL TREES AND PALMS TO BE RELOCATED MUST BE WATERED DAILY FOR AT LEAST 2-3 DAYS PRIOR TO ANY ROOTS BEING CUT TO ENSURE THAT THEY ARE FULLY HYDRATED. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH.

EACH TREE AND PALM MUST THEN BE WATERED EVERY OTHER DAY, NOT RELYING ON RAIN, DURING THE ENTIRE ROOT PRUNING PROCESS EITHER BY A TEMPORARY IRRIGATION SYSTEM OR BY HAND. EACH WATERING MUST THOROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH.

TREE AND PALM RELOCATION ACTIVITIES MUST BE SCHEDULED SO THAT REMOVAL AND REPLANTING TAKE PLACE IN THE SAME 24 HOUR PERIOD.

ALL DIGGING IN THE ROOT ZONE DURING THE ROOT PRUNE PROCESS MUST BE DONE BY HAND. PRUNING OF ROOTS MUST BE DONE BY HAND WITH CLEAN, SHARP TOOLS. MACHINERY COULD BE USED ON LARGER TREES AS LONG AS ROOTS ARE FINALIZED BY HAND PRUNING. DO NOT PAINT ROOTS WITH PAINT OR ANY KIND OF SEALANT.

MYCORRHIZA (ROOTS TRANSPLANT OR EQUIVALENT) MUST BE INCORPORATED INTO THE BACKFILL SOIL PRIOR TO BACKFILLING AS PER MANUFACTURERS RECOMMENDATIONS.

AFTER EACH ROOT PRUNE, EACH SECTION OF ROOTBALL THAT IS PRUNED MUST BE WRAPPED WITH A BLACK PLASTIC AND THE TRENCH BACKFILLED WITH ORIGINAL EXCAVATED SOIL. A TREE RING WITH A MINIMUM HEIGHT OF 6" MUST BE CONSTRUCTED 6-12" OUTSIDE THE OUTERMOST EDGE OF THE ROOTBALL AND AROUND THE ENTRE PERIMETER OF THE ROOTBALL DURING ROOT IRRIGATION WATER AND ANY ADDED SUPPLEMENTS DOWN INTO THE ROOTBALL DURING ROOT PRESENTED AT ON.

ONCE THE TREE RING IS CONSTRUCTED AFTER EACH ROOT PRUNE, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE LIBERALLY APPLIED TO THE SURFACE OF THE ROOTBALL AND THROUGHLY WATERED IN TO ENCOURAGE NEW ROOT GROWTH.

PRIOR TO ANY ROOTS BEING CUT, ALL MAJOR ROOTS MUST BE IDENTIFIED TO DETERMINE THE ROOTBALL DIAMETER BASED ON THE RELATIVE LOCATION AND SIZE OF THE ROOTS.

MINIMUM ROOTBALL DIAMETER CALCULATION BASED ON A FACTOR OF 10 OR ALLOWING A MINIMUM OF 9"-12" OF ROOTBALL FOR EVERY 1" OF CALIPER. WHENEVER POSSIBLE, ROOTBALLS MUST BE CIRCULAR IN SHAPE WITH AN EQUAL DISTANCE FROM THE TRUNK TO THE EDGE OF THE ROOTBALL ALL AROUND.

MINIMUM ROOTBALL DEPTH MUST BE 24"—36" FOR ALL TREES TO BE RELOCATED, WITH THE ACTUAL DEPTH TO BE DETERMINED ONLY AFTER A THOROUGH EXAMINATION OF ALL ROOTS DURING THE INITIAL ROOT INSPECTION AND BASED ON THE ABSENCE OF MAJOR ROOTS AT THE BOTTOM OF THE ROOTBALL. ROOTBALLS DEEPER THAN 36" MAY BE REQUIRED FOR LARGE SPECIMEN TREES, DEPENDING ON THE RELATIVE LOCATIONS AND DEPTHS OF THE MAJOR ROOTS AS OBSERVED DURING THE INITIAL ROOT INSPECTION.

AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR TREES WITH A DBH OF LESS THAN 10" IS 12 WEEKS. THE FIRST ROOT PRUNE MUST BE ON TWO OPPOSING SIDES OF THE ROOTBALL, WITH THE SECOND ROOT PRUNE ON ONE OF THE OTHER 2 SIDES DONE A MINIMUM OF 6 WEEKS LATER, AND THIRD ROOT PRUNE ON THE LAST SIDE A MINIMUM OF 3 WEEKS AFTER THAT. THE SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW ROOT GROWTH FROM EARLIER ROOT PRUNED IS EVIDENT.

AS A GENERAL RULE, MINIMUM ROOT PRUNE TIME FOR TREES WITH A DBH OF 10" OR GREATER IS 24 WEEKS. THE FIRST ROOT PRUNE MUST BE ON TWO OPPOSING SIDES OF THE ROOTBALD WITH THE SECOND ROOT PRUNE ON ONE OF THE OTHER 2 SIDES DONE A MINIMUM OF 12 WEEKS LATER, AND THIRD ROOT PRUNE ON THE LAST SIDE A MINIMUM OF 6 WEEKS AFTER THAT. THE SECOND AND THIRD ROOT PRUNES MAY ONLY BE DONE WHEN HEALTHY NEW ROOT GROWTH FROM EARLIER ROOT PRUNED IS EVIDENT.

MAINTENANCE SPECIFICATIONS

ALL NEW AND RELOCATED TREES AND PALMS MUST BE MAINTAINED FOR ONE YEAR FROM THE DATE OF RELOCATION TO THEIR FINAL LOCATIONS.

WHENEVER POSSIBLE, EACH TREE AND PALM MUST BE WATERED BY A PERMANENT AUTOMATIC IRRIGATION SYSTEM FOLLOWING RELOCATION. EACH WATERING MUST THROUGHLY SATURATE THE ROOTBALL TO ITS FULL DEPTH; THIS WILL REQUIRE 25-50 GALLONG FWATER FOR SMALL TREES AND PALMS, DEPENDING ON ROOTBALL SIZE, WHILE LANGE TREES WILL REQUIRE A MINIMUM OF 10 GALLONS PER FOOT OF ROOTBALL DIAMETER. WATERING FREQUENCY MUST BE EVERYDAY FOR THE FIRST TWO WEEKS, EVERY OTHER DAY FOR THE NEXT TREE WEEKS, AND EVERY THIRD DAY FOR THE NEXT 6-8 WEEKS.

WHEN AN AUTOMATIC IRRIGATION SYSTEM IS NOT POSSIBLE, CONTRACTOR IS RESPONSIBLE FOR HAND WATERING RELOCATED TREES AND PALMS THROUGHLY THE MAINTENANCE PERIOD AND UNTIL FINAL ACCEPTANCE BY THE LANDSCAPE ARCHITECT AND/OR CLIENT.

IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE APPLIED TO THE SURFACE OF THE ROOTBALL AT THE RECOMMENDED LABEL RATE AND WATERED IN WITH A DRENCH CONSISTING OF A SYSTEMIC INSECTICIDE AND A CONTACT ROOT ROT FUNGICIDE, FOLLOWING LABEL INSTRUCTIONS, AS INITIAL PREVENTATIVE MAINTENANCE.

EVERY THREE MONTHS THEREAFTER, A HIGH-PHOSPHORUS ROOT STIMULANT MUST BE APPLIED TO THE SURFACE OF THE ROOTBALL AT THE RECOMMENDED LABEL RATE AND WATERED IN WITH A DRENCH CONSISTING OF A SYSTEMIC INSECTICIDE AND A BROAD-SPECTRUM SYSTEMIC FUNGICIDE, FOLLOWING LABEL INSTRUCTIONS, AS CONTINUING PREVENTATIVE MAINTENANCE.

IRRIGATION AND BRACING MUST BE CHECKED AND EACH TREE OR PALM THROUGHLY INSPECTED FOR SIGNES OF STRESS, DISEASE, OR PEST PROBLEMS ON A MONTHLY BASIS.

SHADE TREES

IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS THEREAFTER, A HIGH-QUALITY, SLOW-RELEASE 15-2-15 GRANULAR FERTILIZER MUST BE APPLIED, AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS TEH SURFACE OF THE ROOTBALL.

FOLIAR FEED FOUR TIMES PER YEAR.

FLOWERING TREES

IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS THEREAFTER, A HIGH-QUALITY, SLOW RELEASE 5-10-15 GRANULAR FERTILIZER MUST BE APPLIED, AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SURFACE OF THE ROOTBALL.

FOLIAR FEED FOUR TIMES PER YEAR.

PALMS

STRING MUST BE REMOVED FROM THE TIED UP LEAVES IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION IF THE PALM WAS ROOT PRUNED OR WITHIN 30-45 DAYS AFTER RELOCATION ON THE OCCASION THE LANDSCAPE ARCHITECT APPROVED RELOCATION WITHOUT ROOT PRUNING DUE TO TIME CONSTRAINTS.

IMMEDIATELY AFTER RELOCATION TO THE FINAL LOCATION AND EVERY THREE MONTHS THEREAFTER, A HIGH-QUALITY, SLOW RELEASE 8-14-12 GRANULAR FERTILIZER MUST BE APPLIED, AT THE RECOMMENDED LABEL RATE, SPREAD EVENLY ACROSS THE SURFACE OF THE ROOTBALL.

FOLIAR FEED SIX TIMES PER YEAR.

GAIA/S DESIGN

GAIA/S DESIGN INC. 786.777.8716 gaia@gaiasdesign.coi

OWNER
Jorge M Campodonico
703.963.4438 ic@citylendinginc.co

LANDSCAPE ARCHITECT

Diego Vanderbiest

6200 SW 80 ST MIAMI, FLORIDA 33143 (305) 528-4001 SEAL

Diego Digitally signed by Diego Vande Vanderbiest Date:

rbiest 14:14:20 -04'00'

DIEGO J. VANDERBIEST RLA #6667355

RCTEK ARCHITECTURE LLC 1395 BRICKELL AVE SUITE 900 WIAMI FL 33131 PH: 305.967.6355



JOHN SACCO AR0004952


New Single Family Home 4354 N MICHIGAN AVE MIAMI BEACH, FL 33140

FINAL SUBMITTAL DATE: 08/10/2020

THESE PLANS ARE FOR DRB REVIEW ONLY, TH ARE NOT TO BE CONSTRUED AS CONSTRUCTI DOCUMENTS UNTIL ALL BUILDING DEPARTME

PLANTING DETAILS

DRB L.4



MATERIALS SCHEDULE



GAIA/S DESIGN

GAIA/S DESIGN INC. 786.777.8716 gaia@gaiasdesign.co

OWNER Jorge M Campodonico 703.963.4438 jc@citylendinginc.co

LANDSCAPE ARCHITECT

Diego Vanderbiest
6200 SW 80 ST
MIAMI, FLORIDA 33143
(305) 528-4001
SEAL

0305) 528–4001 SEAL Diego Digitally signed by Diego

Vande Vanderbiest Date:

rbiest 14:13:33 -04'00'

DIEGO J. VANDERBIEST RLA #6667355

RCTEK ARCHITECTURE LLC 1395 BRICKELL AVE SUITE 900 MIAMI FL 33131 PH: 305.967.6355



SEAL

JOHN SACCO AR0004952

New Single Family Home 4354 N MICHIGAN AVE MIAMI BEACH, FL 33140

FINAL SUBMITTAL DATE: 08/10/2020


THESE PLANS ARE FOR DRB REVIEW ONLY, THI ARE NOT TO BE CONSTRUED AS CONSTRUCTIC DOCUMENTS UNTIL ALL BUILDING DEPARTMEN APPROVAL ARE OBTAINED

> PROPOSED HARDSCAPE PLAN

DRB L.5

1. PROPOSED HARDSCAPE PLAN
SCALE 1/16"= 1'-0"





LANDSCAPE LIGHTING FIXTURE SCHEDULE

TYPE	SYMBOL	MANUFACTURER	DESCRIPTION	QTY
A	8	HK USA Lighting Group	ZXL16i-A-CGSA-120V-6W-LED-3K-BK	11
В		BEGA	84671- 12.3W LED	5

 $G\Lambda I\Lambda /S$ DESIGN

GAIA/S DESIGN INC. 86.777.8716 gaia@gaiasdesign.c

OWNER Jorge M Campodonico 703.963.4438 jc@citylendinginc.co

LANDSCAPE ARCHITECT Diego Vanderbies 6200 SW 80 ST MIAMI, FLORIDA 33143 (305) 528-4001 SEAL

Diego Digitally signed by Diego Vande Vanderbiest

rbiest 14:12:39 -04'00'

DIEGO J. VANDERBIEST RLA #6667355 RCTEK ARCHITECTURE LLC 1395 BRICKELL AVE SUITE 900 MIAMI FL 33131 PH: 305.967.6355



JOHN SACCO AR0004952

New Single Family Home 4354 N MICHIGAN AVE MIAMI BEACH, FL 33140

FINAL SUBMITTAL DATE: 08/10/2020

THESE PLANS ARE FOR DRB REVIEW ONLY, TH ARE NOT TO BE CONSTRUED AS CONSTRUCTION OCUMENTS UNTIL ALL BUILDING DEPARTMENT APPROVAL ARE OBTAINED

LANDSCAPE LIGHTING PLAN

DRB L.6

1. PROPOSED LIGHTING PLAN SCALE 1/16"= 1'-0"