Vertical Transportation Analysis

General Description

Soundscape is an exclusive office space developed by SHVO in Miami Beach. It contains about 38,000 gross square feet of office space on five levels with the second and third floors divided between parking and office space. Outdoor spaces are planned throughout the building including on the roof. It is planned as a creative-Tech office with an open flexible floorplan that integrates indoor and outdoor spaces.

The current plans show 3 elevators in-line serving all landings with a wall at the ground floor lobby separating the 2nd and 3rd elevators working west to east. As a result, there will be two groups of elevators – a two-car duplex passenger elevator group and a single dedicated service elevator.

Current planning indicates relatively large passenger-shaped elevators for the passenger and service cars, which translates to a 4,000 pound-capacity in lieu of the standard 3,500-pound capacity commercial office building elevator. Information presented in this report will be based on 4,000 pound-capacity passenger elevators. If space planning constraints dictate reducing the elevator shaft sizes, as a rule-of-thumb, 3,500-pound capacity elevators require 1' 0" less width of the hoistway than 4,000 pound-capacity elevators.

All three elevators share a common corridor above the ground floor. The current architectural drawings show all three elevators with matching center-parting doors. FS2's preference for service elevators is that they be "Service-Shaped" meaning they are deeper than they are wide rather than the "passenger-shaped" elevator – wider than it is deep- currently shown for the service elevator. Our primary recommendation is that the core be reconsidered to fit a service-shaped service elevator that is separated from the passenger elevators.

If the current core arrangement is maintained and a passenger-shaped elevator is used as the service elevator, we recommend that its door be made side-opening for improved functionality. For example, a sheetrock dolly with 8' 0" boards on it will not fit in a 4,000-pound capacity elevator with center-opening doors, but it will fit in the same sized elevator with side-opening doors. The implication of changing the door arrangement for the service elevator is that the differences in the door types would be evident on levels above the ground floor, as the center-opening doors are important for the efficiency of the passenger elevators. The different door arrangements could help differentiate the function of the two elevator groups for tenants and encourage them to use the passenger elevators for normal circulation, as intended.

Since the building is a high-rise, the passenger & service elevators will require hoistway opening protection per FBC 3006.2, complying with 3006.3, which requires an enclosed elevator lobby or hoistway pressurization.

The parking levels are accessed by two automobile lifts, which will be 8,000-pound capacity roped holeless hydraulic class B autolifts. To maintain the required overrun below the 4th floor slab, the cab and door opening height will be 7' 6". This will accommodate luxury SUVs and even relatively tall non-commercial truck vehicles such as a Mercedes Sprinter Van with the tall roof option at 79". It is unclear from current plans whether the intent is for the parking levels to be exclusively valet-operated - or whether there will be self-parking with tenants using the autolifts – an item to be clarified by Ownership. In either case we recommend that a remote-



control call and landing signals system be integrated with the elevator controls to manage queuing in the relatively tight vehicle maneuvering spaces in the parking levels. Refer to Appendix E for more details.

Executive Summary – Passenger Elevator Vertical Transportation

The passenger and service elevators will be the machine-room-less (MRL) type. Because of relatively small commercial office floorplates which is inefficient for elevator service, the Soundscape elevators are required to be 350 FPM – refer to Appendix A for a performance comparison of 350 versus 200 FPM. Excellent service will be provided by two 350 FPM machine-room-less traction elevators during morning up-peak with Good service levels provided during peak lunchtime traffic.

A central question influencing the shaft space planning and basis-of-design for the elevators is the degree to which the elevator finishes will be customized in the design scheme. The primary OEM elevator manufacturers (Otis, Schindler etc.) have engineering limitations as to the degree their MRLs can be customized. Independent MRL manufacturers follow a process that allows a greater degree of customization, but their MRLs require more space than the OEMs. These details are discussed in detail below under *Basis of Design* and specific planning dimension options and trade-offs are found in Appendix D. To further develop the elevator spatial planning, Ownership will have to provide direction as to which basis of design path to follow for Soundscape – OEM vs. Independent?

Design Criteria

The primary factor in determining the number of passenger elevators is the estimated population that will require vertical transport during peak traffic periods. For Soundscape using an occupant density of 125 ft²/person net usable area produced a theoretical occupancy of 261 persons based on a total of 33,175 NUSF as provided in gross area calculations by Kobi Karp Architects with an 85% assumed efficiency of gross to usable. To calculate requirements for elevator usage a "diversity" or absentee factor of 10% is subtracted from the theoretical population to account for the fact that every workstation is not occupied every day due to absence resulting from telecommuting, illness, business travel or vacation. This results in a net population requiring elevator service for 234 persons. The calculations are summarized below:

SOUNDSCAPE - VT POPULATION CALCULATION									
FLOOR	F/F'	ELEVATION NGVD'	GROSS SF OFFICE	USABLE SF OFFICE (85%)	125 SF/P	DIVERSITY FACTOR (10%)	NET VT POPULATION		
R		93.00							
6	13.67	79.33	9,174	7,798	62	6	56		
5	13.58	65.75	9,334	7,934	63	6	57		
4	13.58	52.17	9,334	7,934	63	6	57		
3	13.58	38.58	5,177	4,400	35	4	32		
2	13.58	25.00	5,294	4,500	36	4	32		
G	19.5	5.50							
		87.50	38,313	32,566	261	26	234		

The Vertical Transportation Analysis calculations used a criterion of 12% for the peak 5-Minute Handling Capacity for one-way morning up-peak and a 11% Handling Capacity for two-way lunchtime peak based on a diverse-tenant occupancy, which encompasses full-floor and multi-tenant floor occupancy. The design criterion for good elevator service is an Average Interval of 30 seconds resulting in an Average Waiting Time of 25 seconds or less. Thus, the requirements are the passenger elevators to serve 28 people during the busiest 5minute period during the morning up-peak and to serve 26 people during the busiest 5-minutes during lunchtime.

Prevailing elevator codes for the project include:

- Florida Building Code, 2020 Edition
- IBC 2018, Florida Edition
- Florida Elevator Safety Code
- Safety Code for Elevators and Escalators, A17.1 2016
- Americans with Disability Act / A117.1-2017

Analysis Results

Based on the developed populations and Design Standards, FS2 completed Vertical Transportation analysis calculations for the passenger elevators for morning up-peak and two-way lunchtime peak. The results are summarized below.

Elevator Application	Average Waiting Time	Service Quality	
2 x 4,000 lb. @ 350 FPM Morning Up-peak	18.7 Sec.	Excellent	
2 x 4,000 lb. @ 350 FPM Lunchtime-peak	22.4 Sec.	Good	

Detailed Vertical Transportation Analysis calculation results are in Appendix A. Industry-standard vertical transportation design and performance criteria are in Appendix B and vertical transportation analysis term definitions are in Appendix C.

Basis of Design

Passenger & Service Elevators

Based on the vertical travel distance, required size and speed of the elevators required to achieve the performance results outlined above, MRL elevators are the logical choice based on today's elevator product offerings. MRL elevators can be broadly classified into two categories, each having pros and cons for Soundscape.



The major OEM elevator manufacturer's MRL equipment have the following general characteristics:

- Compact core envelope (hoistway, pit, overhead).
- Custom cab interior finishes possible within strict weight limits for walls and suspended ceiling.
- Limited options for cab flooring recess typically 1-1/4" maximum floor material depth. Weight of flooring material considered within overall limit combined with cab finishes.
- Standard stainless steel metal finishes for elevator fixture panels & pushbuttons.
- Standard stainless steel or paint grade finishes and standard frame profile for elevator entrances.
- Competitive installation cost.
- Proprietary control systems.

The OEM manufacturers and products that can be considered as the MRL basis of design for the Soundscape are as follows:

- ✓ Kone Monospace 500
- ✓ Otis Gen3 Edge
- ✓ Schindler 5500
- ✓ Thyssenkrupp Evolution 200

Alternatively, independent elevator installers using equipment manufactured by Hollister-Whitney and other specialized suppliers of cabs, fixtures and controls can be used as the basis of design. This equipment has the following characteristics:

- Larger core envelope (hoistway, pit, overhead).
- Customizable cab interiors with greater weight limits.
- Customizable flooring, metal finishes, entrance details.
- Premium installation cost.
- Non-proprietary control systems.

Appendix D shows core planning dimensions for two Schemes. Passenger-and Service-shaped elevators are included. If a passenger-shaped elevator shaft is selected for the service elevator, the passenger elevator dimensions can be used for the service elevator, and the 4,500-pound capacity service elevator dimensions ignored.

- Scheme 1 shows core planning that represents a combined worst-case that can accommodate 4 OEM manufacturer's equipment.
- Scheme 2 shows the alternative arrangements from Hollister-Whitney that meet the design criteria. All the arrangements shown are available as planning options. If the Ownership/Design Team prefers a non-proprietary control system with more custom finish options available than an OEM solution, space planning trade-offs between hoistway, pit and overhead dimensions should be considered by the Design Team to select the Plan arrangement most suitable.

Autolifts

Acceptable hydraulic equipment manufacturers are Minnesota Elevator Inc. (MEI), Canton Elevator or Mongrain Vertical Transport (MVT). The acceptable freight door and cab manufacturer is The Peelle Company. It is optional to add the remote-control call and signal features in Appendix E, which can be utilized by valets or self-parkers, depending on how that is handled operationally. The hoistway size outlined below is standard for automobile lifts. A reduction in the overall length of the hoistway could be considered based on the type of vehicles to be served in Soundscape's parking levels. Standard characteristics are outlined below:

- ✓ 8,000# capacity @ 125 FPM.
- ✓ Clear hoistway 12' 0" wide x 22' 6" deep.
- ✓ Door opening: 9' 0" wide x 7' 6" high.
- ✓ Pit: 4' 6" Deep.
- Clear overhead: 12' 3" (as given) the equipment needs 12' 0" minimum clear based on the 7' 6" cab/door height and a 2-speed gate on the cab. A 9,000# capacity hoistbeam is required at the top of the hoistway which will be removable after the cab is installed to yield the net 12' 0" + clear overhead.
- ✓ Each elevator will have two 75hp pump motors. The machine room will require about 200SF to accommodate the two 10' long x 3' 6" deep x 6' 0" power units, elevator controllers, freight door controllers and associated electrical disconnect switches. The room should be roughly square approximately 16' x 12'.
- ✓ Heat load will be approximately 40,000 BTU/h per elevator to be maintained at <=95F @ 90% max noncondensing.

Elevator Products to address Covid 19

In the time since Covid 19 impacted life in the US, the elevator industry has responded with products to mitigate the spread of airborne viruses in in elevators. Each is briefly outlined below, with greater detail found in Appendix E. The inclusion of any of these products in the elevator design is at the Owner's option.

The focus is on cab ventilation systems. There are three products currently on the market. Efficacy test results are available for each the cab ventilation systems described below.

- Ionization is offered by Otis and others. Otis' literature in Appendix E is representative. This product distributes ionized particles into the cab. Aerosols are attracted to the charged ion particles. When the ions attach to the aerosols, the viruses in the aerosols are neutralized by the ions. It is available in new installations with a cost of under \$2,500 per elevator. Similar products are available from Schindler and independent 3rd party industry suppliers.
- Man-D-tec, well known in the industry as manufacturer of elevator cab fans, has adapted dual HEPA filters and a UVC germicidal light to one of their workhouse elevator cab fans. This arrangement takes in air from the hoistway, passes it through the filters and UVC light, and blows purified air down into the cab. It's worth noting that in the US cab fans typically exhaust air from inside the cab to the hoistway. Elevator cabs are required to have natural ventilation but not required by code to have a fan (other than glass observation cars), so the Man-D-tec arrangement is not contrary to code. The cost of



incorporating this system into a new installation is around \$4,000 each.

• CEC Elevator Cabs located in the Bronx has developed its Sterilyft product. This system exhausts air from within the cab, passes it through a MERV 13 filter, into a UV-C germicidal light plenum, through another MERV 13 filter and then ducts the purified air down the side of the cab and returns it to the cab at the base. The cost of installing this system in a new installation is around \$8,000 per cab.

The UV light/filter systems require periodic maintenance to replace filters – twice/year and UV bulbs every 3-5 years.

End of Report



APPENDIX A – VT ANALYSIS RESULTS

MORNING UP-PEAK

ELEVATOR ANALYSIS SUMMARY

NUMBER OF ELEVATORS	DUTY	LEVELS SERVED	PROJECTED VT <u>POPULATION</u> (PERSONS)	INDIVIDUAL <u>CAR LOAD</u> (PERSONS) (UP/DOWN)	5-MINUTE,A.M., <u>AVERAGE</u> <u>INTERVAL</u> (SECONDS)	1-WAY PEAK ELEVATORING GROUP HANDLING CAPACITY (PERSONS/PERCENTAGE)	MEETS THE DESIGN CRITERIA?
2	4,000LBS @ 200 FPM	C 2 6 P	224	3.6 / 0	38.2	28 / 12.0 %	NO
2	4,000LBS @ 350 FPM	G, 2 – 0, K	234	2.5 / 0	26.7	28 / 12.0%	YES

SUGGESTED DESIGN

CRITERIA	OFFICE PASSENGER ELEVATORS – DIVERSE TENANCY
AVERAGE INTERVAL:	≤ 25-30 SECONDS
AVERAGE WAITING TIME:	≤25 SECONDS
GROUP HANDLING	
CAPACITY:	≥ 12%
MEASUREMENT PERIOD:	ONE-WAY AM UP PEAK

NOMINAL ELEVATOR CAR LOADS (MAXIMUM 80%ANALYSIS LOADS)

CAPACITY 3500LBS 4000LBS

PERSONS 18-19 PERSONS 22-24 PERSONS

ACCELERATION/DECELERATION AND JERK RATES UTILIZED:

ACV³F MRL 2.3FT/SEC² & 4.8.FT/SEC³

ELEVATOR WAITING TIME ANALYSIS

	DUTY		AVERAGE	AVERAGE TIME TO	PERCENTAG	SERVICE		
ELEVATORS		SERVED	WAITING TIME (SECONDS)	DESTINATION (SECONDS)	<u><</u> 30 SEC.	<u><</u> 60 SEC.	<u><90</u> SEC <u>.</u>	QUALITY
2	4,000LBS @ 200 FPM	G 2 6 P	26.7	46	67%	89%	97%	FAIR
2	4,000LBS @ 350 FPM	G, 2 – 0, K	18.7	32	80%	96%	100%	EXCELLENT



TWO-WAY LUNCH PEAK

ELEVATOR ANALYSIS SUMMARY

NUMBER OF ELEVATORS	ARRANGEMENT	LEVELS SERVED	PROJECTED VT <u>POPULATION</u> (PERSONS)	INDIVIDUAL <u>CAR LOAD</u> (PERSONS) (UP/DOWN)	5-MINUTE,A.M., AVERAGE INTERVAL (SECONDS)	1-WAY PEAK ELEVATORING GROUP HANDLING CAPACITY (PERSONS/PERCENTAGE)	MEETS THE DESIGN CRITERIA?
2	4,000LBS @ 200 FPM		224	1.9 / 1.9	43.1	26 / 12%	NO
2	4,000LBS @ 350 FPM	G, 2 – 0, K	234	1.3 / 1.3	29.9	26 / 12%	YES

SUGGESTED DESIGN

CRITERIA	OFFICE PASSENGER ELEVATORS – DIVERSE TENANCY
AVERAGE INTERVAL:	≤ 25-30 SECONDS
AVERAGE WAITING TIME:	≤28 SECONDS
GROUP HANDLING	
CAPACITY:	≥ 11%
MEASUREMENT PERIOD:	TWO-WAY LUNCH PEAK

NOMINAL ELEVATOR CAR LOADS (MAXIMUM 80%ANALYSIS LOADS)

<u>UTILIZED:</u> ACV³F MRL ☑ 2.3FT/SEC² & 4.8.FT/SEC³

ACCELERATION/DECELERATION AND JERK RATES

 CAPACITY
 PERSONS

 3500LBS
 18-19 PERSONS

 4000LBS
 22-24 PERSONS

ELEVATOR WAITING TIME ANALYSIS

	ARRANGEMENT		AVERAGE	AVERAGE TIME TO	PERCENTAGE OF HALL CALLS ANSWERED WITHIN:			SERVICE
ELEVATORS		SERVED	WAITING TIME (SECONDS)	DESTINATION (SECONDS)	<u><</u> 30 SEC.	<u><</u> 60 SEC.	<u><90</u> SEC <u>.</u>	QUALITY
2	4,000LBS @ 200 FPM	G 2 6 P	32.3	54	60%	84%	95%	POOR
2	4,000LBS @ 350 FPM	G, 2 – 0, K	22.4	37	74%	93%	99%	GOOD



APPENDIX B - VT DESIGN CRITERIA

Average Interval	≤ 25 – 30 Seconds		
Handling Capacity – Minimums			
Office Building			
Diversified Tenancy	≥ 12% of Zone Population Moved		
Mixed Tenancy	≥ 13% of Zone Population Moved		
Single Tenancy	≥ 14% of Zone Population Moved		
Floor Densities	10 – 15m²/Person N.U.A International 125 - 150 Sq. Ft / Person, N.U.A.		
Diversity Factor	10% - 20%		
Average Time to Destination	≤60 Seconds of Less		
Peak Period	A.M. Up Peak		

Office Building Single Deck & Double Deck Design Criteria

	AVERAGE WAITING	PERCENTAGE OF HALL CALLS UNDER						
RATING	TIME (SECONDS)	30 SECONDS	60 SECONDS	90 SECONDS				
Excellent	≤20	≥75%	≥98%	100%				
Good	≤25	≥70%	≥95%	≥98%				
Fair	≤30	≥65%	≥95%	≥96%				
Poor ≥30 ≤65% ≤92% ≤94%								
Times indicated are for the all-day period, the peak hour (other than the morning up-peak period) and the peak 15 minutes may drop one category.								

Office Building Average Waiting Time Design Criteria—Office Building



APPENDIX C - VT DESIGN DEFINITIONS

Handling Capacity – The number of persons or percentage of population that can be transported by the vertical transportation system over a peak period; the peak period is the same period used to measure Average Interval.

Demand Interval – The time interval during which the peak demand vertical transportation will occur.

Average Interval – The average time between elevator departures from the main terminal loading floor, in seconds, during the peak period; calculated by dividing the round-trip time of a single elevator by the number of elevators proposed for the group.

Round-Trip Time - The theoretical average time for an elevator, based on the calculated individual car load, to leave the main lobby, transit through the local stops, discharge passengers and return to the lobby ready to pick up another load.

Individual Car Load – The number of persons carried on the elevator during the round-trip time calculation. Elevator Engineers rate the most-commonly used passenger elevator sizes as follows:

Elevator	Maximum	Nominal Car
<u>Size</u>	<u>Net Area</u>	<u>Capacity</u>
(lbs.)	(Ft ²)	(Persons)
2500	29.1	12-14
3000	33.7	16-17
3500	38.0	19-20
4000	42.2	22-24
4500	46.2	24-25

The nominal carloads work out to about 1.7 - 1.94 ft² per person with an average body ellipse, including the "no touch" barrier we all project in front of us. The calculated individual carload used for elevator analysis is based upon the group Handling Capacity required and the Average Interval desired.

APPENDIX D – OEM vs. Independent Mfr. VT Core Planning

NON- SEISMC Kone Otis Schindler tkE MULTI-MF. WI MULTI-MF. WI CASE PASSENGER 4000 @ 350 MRL 9' 8" x 6' 11" 9' 6" x 7' 4" 9' 6" x 6' 11" 9' 8" x 7' 4" SHAPED Holstway Pit 9' 8" x 6' 11" 9' 4" x 6' 11" 9' 6" x 7' 4" 9' 6" x 6' 11" 9' 8" x 7' 4" Clear Overhead ¹ 14' 6" 15' 7" 16' 11" 14' 4" 16' 11" Stretcher 9' 0" CAB (MIN) 9' 8" x 9' 8" 7' 4" X 9' 7" 8' 5" X 9' 0" 7' 6" x 9' 6-1/2" 8' 5" X 9' 8" SERVICE 4500H @ 200 MRL 5' 0" 5' 1" 5' 0" 5' 1" Stretcher 9' 0" CAB (MIN) 5' 0" 5' 1" 5' 0" 5' 1" SERVICE 4500H @ 200 MRL 5' 0" 5' 1" 14' 9" 13' 8" 14' 9" Stretcher 9' 0" CAB (MIN) 5' 0" 5' 1" 13' 8" 14' 9" Yes Yes Yes Yes Yes Yes Yes Pit 5' 0" 5' 0" 13' 8" 14' 9" <				SCHEM	E 1 - OEM			
PASSENCER Product Passencer Stor Evolution 200 Cove SHAPED Hoistway 9' 8'' x 6' 11'' 9' 6'' x 7' 4'' 9' 6'' x 6' 11'' 9' 6'' x 7' 4'' 9' 6'' x 6' 11'' 9' 8'' x 7' 4'' SHAPED Hoistway 9' 8'' x 6' 11'' 9' 6'' x 7' 4'' 9' 6'' x 6' 11'' 9' 6'' x 6' 11'' 9' 6'' x 6' 11'' 9' 8'' x 7' 4'' Pit 5' 6'' 5' 6'' 5' 6'' 5' 6'' 5' 6'' 5' 6'' 5' 6'' Stretcher 9' 0'' CAB 200 MRL 14' 6''' 15' 7'' 16' 11'' 14' 4''' 16' 11'' SHAPED Hoistway 7' 8'' x 9' 8''' 7' 4'' X 9' 7''' 8' 5'' X 9' 6'' 7' 6'' x 9' 6-1/2''' 8' 5'' X 9' 8''' SERVICE 4500H @ 200 MRL 5' 0'' 5' 1''' 5' 0''' 5' 1'''' 14' 9''' Stretcher 9' 0'' CAB 5' 0''' 5' 0'''' 5' 10''''' 13' 8''' 14' 9'''' Product Plan 101 Plan 121 Plan 121 Plan 201 Plan 231 PASENCER 400 @ 350 MRL 11' 3''' x 7' 2''' 10' 8'''' x 7' 0'''' 9' 4''' x 8' 2''' 7' 10''''''' </th <th>NON- SEISMIC</th> <th>Mfr:</th> <th>Kone</th> <th>Otis C2 Edge</th> <th>Schindler</th> <th>tkE Evolution 200</th> <th></th> <th>BASIS OF DESIGN MULTI-MFR WORST</th>	NON- SEISMIC	Mfr:	Kone	Otis C2 Edge	Schindler	tkE Evolution 200		BASIS OF DESIGN MULTI-MFR WORST
SHAPED Hoistway Pit Clear Overhead ¹ 9' 8" x 6' 11" 9' 6" x 7' 4" 9' 6" x 6' 11" 9' 8" x 7' 4" Site Clear Overhead ¹ 14' 6" 15' 7" 16' 11" 14' 4" 16' 11" Stretcher 9' 0" CAB (MIN) 9' 8" x 9' 8" 7' 4" x 9' 7" 8' 5" x 9' 0" 7' 6" x 9' 6-1/2" 8' 5" x 9' 8" SERVICE 4500H @ 200 MRL 5' 0" 5' 0" 5' 0" 5' 1" 16' 11" 14' 4" 16' 11" SHAPED Hoistway Pit Clear Overhead ¹ 7' 8" x 9' 8" 7' 4" x 9' 7" 8' 5" x 9' 0" 7' 6" x 9' 6-1/2" 8' 5" x 9' 8" Stretcher 9' 0" CAB (MIN) 5' 0" 5' 1" 14' 9" 13' 8" 14' 9" Stretcher 9' 0" CAB (MIN) Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" Pit Stretcher Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 SHAPED Hoistway Pit Stretcher 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" 9' 0" CAB SerWice Yes Yes	PASSENGER	2 4000 @ 350 MRI	wonospace 500	G5 Edge	5500	Evolution 200		CASE
No. Cl Pit Si 6" Si 6" Si 6" Si 6" Si 6" Clear Overhead ¹ 14' 6" 15' 7" 16' 11" 14' 4" 16' 11" Stretcher 9' 0" CAB (MIN) Yes Yes Yes Yes Yes SERVICE 4500H @ 200 MRL ShAPED Hoistway 7' 8" x 9' 8" 7' 4" x 9' 7" 8' 5" x 9' 0" 7' 6" x 9' 6-1/2" 8' 5" x 9' 8" SHAPED Hoistway 7' 8" x 9' 8" 7' 4" x 9' 7" 8' 5" x 9' 0" 7' 6" x 9' 6-1/2" 8' 5" x 9' 8" SHAPED Hoistway 7' 8" x 9' 8" 7' 4" x 9' 7" 8' 5" x 9' 0" 7' 6" x 9' 6-1/2" 8' 5" x 9' 8" Pit 5' 0" 5' 0" 5' 1" 14' 9" 13' 8" 14' 9" Stretcher 9' 0" CAB (MIN) Stretcher Yes Yes Yes 9' 0" CAB (MIN) Stretcher Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 Product Plan 101 Plan 211 Plan 231 Plan 231 Stretcher Yes Yes Yes Yes O' 0 CAB Stretcher Yes Yes Yes Yes Clear Overhead ¹ 11' 3" x 7' 2" <t< td=""><td>SHAPED</td><td>) Hoistway</td><td>9' 8" x 6' 11"</td><td>9' 4" x 6' 11"</td><td>9' 6" X 7' 4"</td><td>9' 6" x 6' 11"</td><td></td><td>9' 8" x 7' 4"</td></t<>	SHAPED) Hoistway	9' 8" x 6' 11"	9' 4" x 6' 11"	9' 6" X 7' 4"	9' 6" x 6' 11"		9' 8" x 7' 4"
Clear Overhead ¹ 14' 6" 15' 7" 16' 11" 14' 4" 16' 11" Stretcher 9' 0" CAB (MIN) Yes Yes Yes Yes Yes SERVICE 4500H @ 200 MRL SHAPED Hoistway 7' 8" x 9' 8" 7' 4" X 9' 7" 8' 5" X 9' 0" 7' 6" x 9' 6-1/2" 8' 5" X 9' 8" Pit 5' 0" 5' 0" 5' 1" 5' 0" 5' 1" Clear Overhead ¹ 14' 4" 14' 8" 14' 9" 13' 8" 14' 9" Stretcher 9' 0" CAB (MIN) Yes Yes Yes Yes Yes 9' 0" CAB (MIN) Scheme 2 - HOLLISTER-WHITNEY Yes Yes Yes Yes Yes Product Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" Ph 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" Stretcher Yes Yes Yes Yes Yes 9' 0" CAB SERVICE ShAPED 4500H @ 200 MRL Plan 111 Plan 211		Pit	5' 6"	5' 6"	5' 5"	5' 6"		5' 6"
Stretcher Yes Yes Yes Yes Yes 9' 0" CAB (MIN) SERVICE 4500H @ 200 MRL Stretcher Yes Yes Yes Yes Yes Yes SHAPED Hoistway $7'$ 8" x 9' 8" $7'$ 4" x 9' 7" 8' 5" x 9' 0" $7'$ 6" x 9' 6-1/2" 8' 5" x 9' 8" Pit 5' 0" 5' 0" 5' 1" 5' 0" 5' 1" Clear Overhead ¹ 14' 4" 14' 8" 14' 9" 13' 8" 14' 9" Stretcher 9' 0" CAB (MIN) Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL ShAPED Hoistway 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" 7' 10" 6' 2" 6' 4" 5' 8" 5'		Clear Overhead ¹	14' 6"	15' 7"	16' 11"	14' 4"		16' 11"
9' 0" CAB (MIN) SERVICE 4500H @ 200 MRL SHAPED Hoistway Pit Clear Overhead ¹ Stretcher 9' 0" CAB (MIN)		Stretcher	Yes	Yes	Yes	Yes		Yes
SERVICE 4500H @ 200 MRL SHAPED Hoistway Pit 5'0" Clear Overhead ¹ 5'0" Stretcher 9'0" CAB (MIN) SCHEME 2 - HOLLISTER-WHITNEY Product Passenger 4000 @ 350 MRL SHAPED Hoistway Pit 11'3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 11'3" x 7' 2" 10' 8" x 7'0" 9' 0" CAB 11'3" x 7' 2" 9' 0" CAB 11'1" 19' 2" 9' 0" CAB		9' 0" CAB (MIN)						
SHAPED Hoistway 7' 8" x 9' 8" 7' 4" X 9' 7" 8' 5" X 9' 0" 7' 6" x 9' 6-1/2" 8' 5" X 9' 8" Pit 5' 0" 5' 0" 5' 1" 5' 0" 5' 1" 5' 0" 5' 1" Clear Overhead ¹ 5' 0" 5' 1" 14' 9" 13' 8" 14' 9" 13' 8" 14' 9" Stretcher 9' 0" CAB (MIN) Ves Yes Yes Yes Yes Yes Product Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" Pit 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" 5' 8" Stretcher Yes Yes Yes Yes Yes 20' 10" 20' 10" Pit 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" 5' 8" Yes Yes 15' 11" 19' 2" 20' 10" 20' 10" 20' 10" 20' 10" 20' 10" 10' 10" 10' 10" 10' 10" 10' 10" 10' 10" 10' 10" 10' 10" <td< td=""><td>SERVICE</td><td>E 4500H @ 200 MRL</td><td></td><td></td><td></td><td></td><td></td><td></td></td<>	SERVICE	E 4500H @ 200 MRL						
Pit 5' 0" 5' 1" 5' 0" 5' 1" Clear Overhead ¹ 14' 4" 14' 8" 14' 9" 13' 8" 14' 9" Stretcher 9' 0" CAB (MIN) Yes Yes Yes Yes Yes SCHEME 2 - HOLLISTER-WHITNEY Product Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL SHAPED Hoistway Pit 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" Pit 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" Stretcher Yes Yes Yes Yes Yes 9' 0" CAB Stretcher Yes Yes Yes Yes 9' 0" CAB SERVICE Yes Yes Yes Yes Yes 9' 0" CAB SERVICE SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" Yes Yes Yes Stretcher 10' 1" x 9' 9" 8' 6" x 9' 9" Yes Yes Yes	SHAPED) Hoistway	7' 8" x 9' 8"	7' 4" X 9' 7"	8' 5" X 9' 0"	7' 6" x 9' 6-1/2"		8' 5" X 9' 8"
Clear Overhead ¹ Stretcher 9' 0" CAB (MIN) 14' 4" 14' 8" 14' 9" 13' 8" 14' 9" Yes Yes Yes Yes Yes Yes Yes 9' 0" CAB (MIN) SCHEME 2 - HOLLISTER-WHITNEY Yes Yes Yes Product Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" SHAPED Hoistway 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" Pit 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" Stretcher Yes Yes Yes Yes Yes g' 0" CAB SERVICE Yes Yes Yes Yes Yes SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 1' x 9' 9" 8' 6" x 9' 9" Pit 1' 0" 1' C" 1' C" 1' C" 1' C" 1' C"		Pit	5' 0"	5' 0"	5' 1"	5' 0"		5' 1"
Stretcher 9' 0" CAB (MIN) Yes Yes Yes Yes Yes SCHEME 2 - HOLLISTER-WHITNEY Product Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL SHAPED Hoistway Pit 7' 10" 6' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" Pit 7' 10" 6' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" Stretcher Yes Yes Yes Yes Clear Overhead ¹ 15' 11" 19' 2" 19' 2" 20' 10" 20' 10" 9' 0" CAB SERVICE SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" Yes Vers		Clear Overhead ¹	14' 4"	14' 8"	14' 9"	13' 8"		14' 9"
9' 0" CAB (MIN) SCHEME 2 - HOLLISTER-WHITNEY Product Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL SHAPED Hoistway Pit Stretcher Clear Overhead ¹ 11' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" 7' 10" 7' 10" 15' 11" 19' 2" 19' 2" 20' 10" 20' 10" 9' 0" CAB SERVICE SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 0" CAB		Stretcher	Yes	Yes	Yes	Yes		Yes
Product Plan 101 Plan 121 Plan 131 Plan 201 Plan 231 PASSENGER 4000 @ 350 MRL I1' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" SHAPED Hoistway I1' 3" x 7' 2" 10' 8" x 7'0" 9' 10" x 8' 2" 10' 4" x 7' 0" 9' 4" x 8' 2" Pit 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" Stretcher Yes Yes Yes Yes Yes Older Overhead ¹ 15' 11" 19' 2" 19' 2" 20' 10" 20' 10" 9' 0" CAB SERVICE SERVICE Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" Han 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" 7' 0" 9' 10" 7' 0" 10' 10" Dit 7' 0" 9' 1" x 9' 9" 8' 6" x 9' 9" 7' 0" 10' 10"			SCHEMI	E 2 - HOLLISTER-WI	HITNEY			
PASSENGER 4000 @ 350 MRL SHAPED Hoistway Pit 11' 3" x 7' 2" Stretcher 6' 2" Clear Overhead ¹ 10' 2" 9' 0" CAB SERVICE SHAPED Hoistway Pit Stretcher Clear Overhead ¹ 15' 11" 19' 2" 19' 0" CAB SERVICE SHAPED Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" Pit O''' O'''		Product	Plan 101	Plan 121	Plan 131	Plan 201	Plan 231	_
SHAPED Hoistway 11' 3" x / 2" 10' 8" x / 0" 9' 10" x 8' 2" 10' 4" x / 0" 9' 4" x 8' 2" Pit 7' 10" 6' 2" 6' 4" 5' 8" 5' 8" Stretcher Yes Yes Yes Yes Yes Clear Overhead ¹ 19' 2" 19' 2" 20' 10" 20' 10" 9' 0" CAB SERVICE SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" Plan 111 Dit 7' 0" 5' 6" 7' 0"	PASSENGER	R 4000 @ 350 MRL						
Pit 7 10 6 2 6 4 5 8 5 8 Stretcher Yes Yes Yes Yes Clear Overhead ¹ 15' 11" 19' 2" 19' 2" 20' 10" 9' 0" CAB SERVICE SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9"	SHAPED) Hoistway	11' 3" x /' 2"	10' 8" x /'0"	9' 10" x 8' 2"	10' 4" x /' 0"	9' 4" x 8' 2"	
View		Pit	7 10	6° 2°	6°4°	5.8.	5.8.	
SERVICE Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9"		Stretcher	res	tes	tes	Tes 20140	Tes	
9' 0" CAB SERVICE SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" Dita		Clear Overnead	15 11	19 2	19 2	20 10	20 10	
SERVICE Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9"		9' 0" CAB						
SHAPED 4500H @ 200 MRL Plan 111 Plan 211 Hoistway 9' 1" x 9' 9" 8' 6" x 9' 9" Dit 7' 0" 5' 6" x 9' 9"	SERVICE	Ε	_					
Hoistway 9' 1' x 9' 9'' 8' 6'' x 9' 9''	SHAPED	0 4500H @ 200 MRL	Plan 111	Plan 211				
		Hoistway	9' 1" x 9' 9"	8. 6. x 9. 9.				
				0 C				
Clear Overnead 15' 4" 20' 3"		Clear Overhead	15' 4"	20.3.	—			
			res	Tes]			

1) For top of Elevator Bulkhead, add 10" for Hoistbeam and 8" for Structure to Clear Overhead

APPENDIX E - REMOTE CONTROL SYSTEM FOR AUTOMOBILE LIFTS

VMI Elevator Remote Control System

VMI's elevator remote control system is designed to give a passenger the ability to call an elevator to a floor with a small



hand held keyfob transmitter. A system can be custom designed and built to meet your needs.. Contact VMI and our engineers will work together with you to design your own unique system.



Operation -

- User presses a button to call the elevator to the corresponding level
- The Status Indicator signals whether the elevator will be arriving loaded (RED) or empty (GREEN).
- The RED indicator begins flashing as a warning while the elevator doors are closing.
- An elevator that is loaded and has its door fully closed will automatically dispatch to the other landing.
- Doors will automatically open upon arrival and automatically close after the vehicle has exited the elevator.

*Two Stop Auto-Dispatch System shown in example

Status Indicator

None: Empty elevator is available for transport

Green Flashing: Empty elevator is opening doors after responding to a call.

Green Steady: Empty elevator is responding to a call or is ready to load for transport.

- Red Flashing: Doors are closing or about to close.
- Red Steady: Loaded elevator is in transport or about to unload. Waiting vehicles should stay clear of door to allow vehicle to exit.

Components Included

Key Fob Transmitter (1 per user), Receiver Unit located at each landing Status Indicator Units, Load Weighing Device (1) VMI Controller with Auto Dispatch Software

Toll Free: (888) 864-3683 sales@vertitron.com www.vertitron.com VERTITRON MIDWEST, INC. 19336 607th Ave Mankato, MN 56001 APPENDIX F - ELEVATOR DESIGNS TO ADDRESS COVID 19

Otis Product Information

Otis Cab Air Purifier

REDUCE THE SPREAD OF BACTERIA AND VIRUSES IN YOUR BUILDING

The new Otis Cab Air Purifier uses bipolar ionization technology, significantly reducing airborne bacteria and viruses in your elevator.

IONIC AIR PURIFICATION TECHNOLOGY

The Otis Cab Air Purifier generates millions of positive and negative ions that are circulated through the air using your existing fan.

The ions attach to bacteria, viruses and microbes in the air, causing a chemical reaction. This degrades and neutralizes the harmful pathogens, helping to reduce the spread of infection.

EASY INSTALLATION & OPERATION

Otis will modify your existing exhaust fan to an intake fan and add the Otis Cab Air Purifier. The unit continuously purifies air without having to be charged, refilled or cleaned outside of regular elevator maintenance.

AIR PURIFICATION AND COVID-19

Although not tested directly against SARS-CoV-2, the virus causing COVID-19, the Otis Cab Air Purifier has demonstrated effectiveness against viruses similar to the novel coronavirus, both in air and on hard surfaces.

This device was effective in disinfecting MS2 bacteriophage, an EPA-approved surrogate for SARS-CoV-2, in a government-approved lab.



Microorganism	Species	Facility	Year
Viruses	MS2 Bacteriophage	INTA, IT	2020
	Influenza A (H1N1)	Kitasato Research Center, JP	2011
Bacteria	S. aureus	EMSL Analytical, US	2011
	P. aeruginosa	Istanbul University, TR	2011
	S. epidermidis	ARE Labs, KS, US	2011
	E. coli	EMSL Analytical, US; Istanbul University, TR	2011

The Otis Cab Air Purifier is also effective against molds, fungi and spores.

For a full list of testing results, please contact your local sales representative.



Man-D-Tec Product Information



MVS-UVHC by Man-D-Tec FOR NEW AND EXISTING ELEVATOR CABS

Patent Pending, Ultra Performance, Dual UVC Germicidal & Dual HEPA filtration unit. Built specifically for elevators and **PROVEN to remove** 99.9% of airborne virus AND bacteria particles. This unit features a 3-speed high performance sealed ball bearing motor. The "squirrel cage" blower wheel ensures maximum air flow and quiet operation. Blows purified air down into the cab.

Proprietary, fully automatic UV performance monitoring system ensures the dual UVC Germicidal unit is performing at peak levels and has LED indicators for each UV source, along with audible notification when system needs attention.

COP remote mounted UV status indicators are available. This allows passengers to visually see that the system is operating, giving them confidence that their safety is a high priority.











1.800.944.6263



CEC Cab – Sterilyft Product Information

