

| EXISTING TREE DISPOSITION LIST | | | | | | | | | | |
|--------------------------------|----------------|----------------|-----------|------------|------------|-------------|-------|------------|------------|--|
| KEY | BOTANICAL NAME | COMMON NAME | HT. (ft.) | SFD. (ft.) | DBH. (in.) | DISPOSITION | NOTES | MITIGATION | DBH. (in.) | |
| 1 | Royal Palm | Royal Palm | 35 | 12 | 17 | Remove | | | | |
| 2 | Christmas Palm | Christmas Palm | 35 | 8 | 8 | Remove | | | | |
| 3 | Royal Palm | Royal Palm | 35 | 12 | 17 | Remove | | | | |
| 4 | Christmas Palm | Christmas Palm | 28 | 8 | 8 | Remove | | | | |
| 5 | Silver Blotch | Silver Blotch | 15 | 15 | 16 | Remove | | | | |
| 6 | Silver Blotch | Silver Blotch | 15 | 15 | 15 | Remove | | | | |
| 7 | Silver Blotch | Silver Blotch | 20 | 15 | 17 | Remove | | | | |
| 8 | Silver Blotch | Silver Blotch | 25 | 15 | 18 | Remove | | | | |
| 9 | Silver Blotch | Silver Blotch | 25 | 15 | 20 | Remove | | | | |
| 10 | Christmas Palm | Christmas Palm | 14 | 8 | 3 | Relocate | | | | |
| 11 | Christmas Palm | Christmas Palm | 14 | 8 | 3 | Relocate | | | | |
| 12 | Christmas Palm | Christmas Palm | 14 | 8 | 3 | Relocate | | | | |
| 13 | Bottle Palm | Bottle Palm | 6 | 4 | 3 | Remove | *DNMR | n/a | | |
| 14 | Sabal Palm | Sabal Palm | 15 | 8 | 12 | Remove | | | | |
| 15 | Thatch Palm | Thatch Palm | 15 | 8 | 4 | Remove | | | | |
| 16 | Thatch Palm | Thatch Palm | 8 | 4 | 4 | Remove | | | | |
| 17 | Thatch Palm | Thatch Palm | 25 | 8 | 4 | Remove | | | | |
| 18 | Thatch Palm | Thatch Palm | 15 | 6 | 4 | Remove | | | | |
| 19 | Thatch Palm | Thatch Palm | 25 | 8 | 4 | Remove | | | | |
| 20 | Thatch Palm | Thatch Palm | 22 | 6 | 4 | Remove | | | | |
| 21 | Thatch Palm | Thatch Palm | 25 | 8 | 4 | Remove | | | | |
| 22 | Thatch Palm | Thatch Palm | 28 | 8 | 5 | Remove | | | | |
| 23 | Thatch Palm | Thatch Palm | 10 | 4 | 3 | Remove | | | | |
| 24 | Thatch Palm | Thatch Palm | 20 | 4 | 3 | Remove | | | | |
| 25 | Thatch Palm | Thatch Palm | 12 | 4 | 4 | Remove | | | | |
| 26 | Sabal Palm | Sabal Palm | 22 | 8 | 9 | Remove | | | | |
| 27 | Sabal Palm | Sabal Palm | 22 | 10 | 10 | Remove | | | | |
| 28 | Sabal Palm | Sabal Palm | 22 | 10 | 10 | Remove | | | | |
| 29 | Sabal Palm | Sabal Palm | 22 | 10 | 10 | Remove | | | | |




CLIENT
801 ARTHUR GODFREY ROAD

801 ARTHUR GODFREY ROAD,
 MIAMI BEACH, FL 33140

CONSULTANTS
MEP CONSULTANT:
 H. VIDAL & ASSOCIATES INC.
 241 NW S RIVER DR.
 MIAMI, FL 33128
 P: 305.571.1860

STRUCTURAL
 YHCE
 99 NW 27TH AVE
 MIAMI, FL 33125
 P: 305.969.9423

LANDSCAPE ARCHITECTS:
 GARDNER + SEMLER
 LANDSCAPE ARCHITECTURE
 17670 NW 78TH AVE, SUITE 214
 MIAMI, FL 33015
 P: 305.392.1016



NOTES:
 BARRIERS SHALL BE PLACED AT THE EDGE OF THE DRIVEWAY OF THE TREE CANOPY OR AS FAR FROM THE TREE AS POSSIBLE WHERE THE CANOPY OVERHANGS PAVEMENT THAT IS TO REMAIN. BARRIER SHALL BE MAINTAINED IN AN UPRIGHT POSITION AT ALL TIMES.
 TREE PROTECTION FENCE (TPF) SHALL BE INSTALLED PRIOR TO ANY SITE WORK, CLEARING, OR EXCAVATION, AND MAINTAINED THROUGHOUT CONSTRUCTION.
 REMOVE TPF ONLY WITH APPROVAL FROM LIBRAIRY FORESTER AFTER ALL SITE WORK HAS BEEN COMPLETED.
 *NOTE: Should any existing trees or palms be damaged they shall be evaluated by the City Urban Forester to determine corrective actions that may include removal, canopy pruning and/or replacement. Any corrective actions required shall be performed in accordance with the City of Miami Beach Code, the most current AISC 1000 being modified and/or in local City Tree or Environmental Board. Any corrective pruning required shall be performed by an ISA Certified Arborist and the City Urban Forester shall be consulted.

TREE PROTECTION DETAIL
 NTS

TREE & PALM TRANSPLANTING NOTES:

- Prior to root pruning and before excavating holes for transplanted trees, check with all local utilities to locate existing underground utilities. If any unknown utilities or sprinkler pipes are inadvertently broken, do not cover them up. Immediately notify the utility and/or the Client, and take all necessary steps to repair the break.
- Root prune trees a minimum of 8 weeks prior to moving them. It is not necessary to root prune palms prior to transplanting unless specifically instructed to do so by the Landscape Architect. Prior to root pruning, thoroughly water the root zone with at least 2'-3" of water. Root pruning shall be accomplished by digging a trench two-thirds (2/3) of the way around the tree at a minimum of 24" deep. Root prune only with a mechanical root-pruning saw or a trencher with a maximum trench width of 8 inches. This trench shall form a rootball of the minimum following sizes:

| | |
|------------------|-----------------|
| Up to 5" caliper | 3' diameter |
| 6'-8" caliper | 4' diameter |
| 9'-12" caliper | 6' diameter |
| Over 12" caliper | 8'-10' diameter |
- The amount of general pruning and thinning of the leaf mass shall be limited to 1/3 of the tree canopy or only the fronds that are more than 50% dead, unless otherwise directed by the Landscape Architect.
- Plant holes shall be roughly cylindrical in shape with sides approximately vertical. The depth of the hole shall be equal to the rootball depth plus 12" unless further depth is required to provide adequate drainage. The diameter of the hole shall be a minimum of 24" larger than the rootball diameter.
- Plant material shall be planted at their natural and original planting level prior to their placement on this project or job. When lowered into the hole, the plants shall rest on the prepared hole bottom such that the surface roots are level or slightly above the level of the top of the hole. Create a saucer, approximately 6" deep to help hold water. The practice of plunging, burying, or planting the plant material such that the surface roots are below the level of the surrounding final grade will not be permitted unless it is noted otherwise in these plans. The plants shall be set straight or plumb or normal to the relationship of their growth prior to transplanting. The Landscape Architect reserves the right to direct the Contractor to realign any plant material after it has been set.
- Backfill the bottom two-thirds of the planting hole and firmly tamp and settle by watering as backfilling progresses. After having tamped and settled the bottom two-thirds of the hole, thoroughly puddle with water and fill the remaining one-third of the hole with soil, tamping and watering to eliminate air pockets.
- Spread 3" thick layer of shredded Melaleuca mulch over entire area of the rootball immediately after transplanting.
- Stake all transplanted trees or palms as per details enclosed, or in the case of obstacle, in another manner which will support the tree or palm.
- All waste and other objectionable material created through planting operations and landscape construction shall be removed completely on a daily basis from the job or as directed by the Landscape Architect. Any paved areas, including curbs and sidewalks which have been strewn with soil, solid waste, fertilizer or other waste shall be thoroughly swept.
- After tree or palm removal, the Contractor shall be responsible to backfill holes with clean fill. The finish grade shall be placed level with existing grade. Backfilling shall be done immediately after tree removal, or suitable barricades shall be provided to return the Contractor is responsible to return the area disturbed due to transplanting activities to its original condition. If the area was previously sodded the species of sod shall be used.
- Three weeks after transplanting, and after mulching, apply on the surface, evenly spread over the area of the entire rootball, FEC (Florida East Coast Fertilizer Co.) #5321 (12-6-6) or equal at the rate of one pound per inch of trunk diameter.

SEAL / SIGNATURE

 Digitally signed by
 Kenneth Eric Gardner
 DN: c=US, st=Florida,
 |H=Hialeah, o=GSLA
 DESIGN INC.,
 cn=Kenneth Eric
 Gardner,
 email=ken@gsldesi
 gn.com
 Date: 2023.06.13
 11:38:50 -04'00'
 KEN GARDNER
 FL LA #1569


ISSUES


| DESCRIPTION | REVISION NUMBER | DATE |
|-------------|-----------------|------|
| | | |

FILE INFORMATION
 Project 9768.00
 Drawn GS/LA
 Checked KG
 Project --
 Phase: --

SHEET NAME
EXISTING TREE DISPOSITION PLAN

LA-100





| PLANT LIST | | | |
|---------------|---|---------|---|
| SHRUBS | | | |
| KEY | PLANT NAME | QTY. | UT. SIZE |
| ERLI | Ernodea littoralis ...Golden Creeper | 25 | ea. 3 gal cans, full, install 18" o.c. |
| PHBM | Philodendron "Burle Marx" ...Burle Marx Philodendron | 5 | ea. 3 gallon cans, full |
| PSBA | Psychotria bahamensis ...Bahamas Wild Coffee | 3 | ea. 18"x18" |
| RHEX | Rhapis excelsa ...Lady Palm | 2 | ea. 5' tall OA, multi |
| SABC | Sansevieria trifasciata "Black Coral" ...Black Coral Snake Plant | 17 | ea. 18"x12" |
| GROUNDCOVERS | | | |
| MISC | Microsorium scolopendria ...Wart Fern | 31 | ea. 12" x 12", install 12" o.c. |
| NEEX | Nephrrolepis exaltata ...Boston Fern | 75 | ea. 3 gal cans, full, install 12" o.c. |
| MISCELLANEOUS | | | |
| | Planting Soil: 70% Silica Sand 20% Everglades Muck 10% Shredded Pinebark | as req. | c.y. excavate and backfill 18" depth in all planting areas. |
| | Shredded Melaleuca Mulch | as req. | c.y. 3" layer in all shrub beds |



169 E FLAGLER ST. SUITE 727 MIAMI, FL. 33131
P: 786.598.7260

CLIENT
801 ARTHUR GODFREY ROAD

801 ARTHUR GODFREY ROAD,
MIAMI BEACH, FL 33140

CONSULTANTS
MEP CONSULTANT:
H. VIDAL & ASSOCIATES INC.
241 NW S RIVER DR.
MIAMI, FL 33128
P: 305.571.1860

STRUCTURAL
YHCE
99 NW 27TH AVE
MIAMI, FL 33125
P: 305.969.9423

LANDSCAPE ARCHITECTS:
GARDNER + SEMLER
LANDSCAPE ARCHITECTURE
17670 NW 78TH AVE, SUITE 214
MIAMI, FL 33015
P: 305.392.1016

SEAL / SIGNATURE

Digitally signed by
Kenneth Eric Gardner
DN: c=US, st=Florida,
l=Hialeah, o=GSLA
DESIGN INC.,
cn=Kenneth Eric
Gardner,
email=ken@gsldesi
gn.com
Date: 2023.06.13
11:39:13 -04'00'

Printed copies of this document
are not considered signed and
sealed and the signature must be
verified on any electronic copies

KEN GARDNER
FL LA #1569

| ISSUES | DESCRIPTION | REVISION NUMBER | DATE |
|--------|-------------|-----------------|------|
| | | | |


FILE INFORMATION
Project 9768.00
Drawn GS/LA
Checked KG
Project --
Phase: --

SHEET NAME
PLANTING PLAN

LA-101

© 2020 OTJ Architects, Inc.





IRRIGATION MATERIALS LIST

| KEY | ITEM | QTY. |
|-----|---|-------------|
| --- | PVC laterals shall be Class 200 PVC (sized as shown on plans) | as required |
| --- | MAIN shall be Class 200 PVC | as required |
| --- | PVC sleeves shall be Class 200 PVC (sized double the width of the pipe running through it) | as required |
| --- | Flexible PVC or Polypipe (for swing joints) | as required |
| WM | WATER METER (See Civil Plans) | 1 |
| EC | Electric Controller RAINBIRD ESP-ME3 Series Controller | 1 |
| ▲ | Rainbird RSD Series Rain Sensor (locate in area of free rainfall) | 1 |
| ⊕ | RAINBIRD 200-PE58 2" Electromechanical Solenoid Control Valve | 1 |
| --- | Irrigation Control Wire | as required |
| ▼ | Rainbird 1" In-line Pressure Regulator (PSI-M40X-100) (drip zones not to exceed 40psi max) | as required |
| --- | RAINBIRD XFS Subsurface Drip Irrigation XFS-09-12-500/250/100 Air/Vacuum Relief Valves Kit (2/4" Air relief valve/ Easy Fit Compression Tee/ and Flush Cap) | as required |
| ⊞ | Commercial Wide-Flow Control Zone Kit (WCZ-100-P8B-LC) (0.3-20 gpm) | 3 |
| ⊞ | RAINBIRD 3-RC Quick Coupler Valve | 1 |
| --- | PVC Supply Header for drip/line Class 200 PVC | as required |
| ⊕ | RAINBIRD Dual Bubbler UHB-360-1032 (6 gpm) | 28 |

LATERAL PIPE SIZING
 The Contractor is responsible to properly size all laterals. All laterals shall be sized according to the following schedule. Total gallons per pipe section shall be calculated by adding the GPM per head for every head downstream of the pipe.

PIPE SIZING CHART

| SIZE | GPM |
|--------|------------|
| 3/4" | 6-8 GPM |
| 1" | 8-14 GPM |
| 1 1/2" | 14-24 GPM |
| 2" | 24-32 GPM |
| 2 1/2" | 32-50 GPM |
| 3" | 50-75 GPM |
| 4" | 60-110 GPM |

NOTES:
 - IRRIGATION VALVES, MAINS AND LATERALS DRAWN SCHEMATICALLY. LOCATE IN LANDSCAPE AREAS WHEREVER POSSIBLE.
 - ALL PIPING AND WIRING UNDER HARDSCAPE IS TO BE INSTALLED IN SCH. 80 PVC SLEEVES 2X THE SIZE OF THE PIPE WITHIN.
 - IRRIGATION DRIPPERLINE SHALL BE CONNECTED TO THE EXISTING IRRIGATION SYSTEM ON A SEPARATE ZONE.



169 E FLAGLER ST. SUITE 727 MIAMI, FL. 33131
 P: 786.598.7260

CLIENT
801 ARTHUR GODFREY ROAD

801 ARTHUR GODFREY ROAD,
 MIAMI BEACH, FL 33140

CONSULTANTS
MEP CONSULTANT:
 H. VIDAL & ASSOCIATES INC.
 241 NW S RIVER DR.
 MIAMI, FL 33128
 P: 305.571.1860

STRUCTURAL
 YHCE
 99 NW 27TH AVE
 MIAMI, FL 33125
 P: 305.969.9423

LANDSCAPE ARCHITECTS:
 GARDNER + SEMLER
 LANDSCAPE ARCHITECTURE
 17670 NW 78TH AVE, SUITE 214
 MIAMI, FL 33015
 P: 305.392.1016

SEAL / SIGNATURE

Digitally signed by
 Kenneth Eric Gardner
 DN: c=US, st=Florida,
 l=Hialeah, o=GSLA
 DESIGN INC.,
 cn=Kenneth Eric
 Gardner,
 email=ken@gsldesi
 gn.com
 Date: 2023.06.13
 11:40:13 -04'00'

KEN GARDNER
 FL LA #1569

ISSUES

| DESCRIPTION | REVISION NUMBER | DATE |
|-------------|-----------------|------|
| | | |

FILE INFORMATION

Project: 9768.00
 Drawn: GSLA
 Checked: KG
 Project: --
 Phase: --

SHEET NAME
IRRIGATION LAYOUT PLAN









LA-103

© 2020 OTJ Architects, Inc.




GENERAL NOTES:


- SCOPE OF WORK:** The Contractor shall furnish all labor, machinery, tools, supplies, and equipment as necessary to construct and provide an operating system, as indicated in the Plans. The work shall include, but not be limited to, furnishing materials (pipe, valves, sprinkler heads, fittings, controllers, electrical, wire and fittings, primer, glue, etc.), layout, protection to the public, excavation, assembly, installation, backfilling, compaction, repair of road or pavement surfaces, controller and low voltage feed to the valves, clean-up, maintenance and guarantee, and as-built plans.
- Contractor shall coordinate with General Contractor or other pertinent Contractors on the job to insure that sleeves are provided and installed under hard surfaces to allow access to all areas to be irrigated. All sleeves shall be constructed of Class 200 PVC. Bury all sleeves a minimum of 18" below the surface. Sleeve to be double the size if the pipe running through it. Sleeve shall extend 24" past the edge of pavement into the area to be irrigated.
- GUARANTEE:** The irrigation system shall be guaranteed for a minimum of one calendar year from the time of final acceptance.
- REPAIR UTILITIES:** The Contractor shall be responsible to verify the location of all utilities by hand excavation or other appropriate measures before performing any work that may result in damage to utilities structures, or property. The Contractor shall take immediate steps to repair, replace, or restore all services to any utilities which are disrupted due to his operations. All costs involved in disruption of service and repairs due to negligence on part of the Contractor shall be his responsibility.
- AS-BUILT DRAWINGS:** Prints of the plans will be supplied to the Contractor for recording "as-built" information. Immediately upon installation of any work which deviates from what is shown on the Plans, the Contractor shall clearly indicate such changes in red pencil on the prints. Such changes shall include, but not be limited to, changes in (1) materials; (2) sizes of material; (3) location; and (4) quantities.
- The entire installation shall fully comply with all applicable local and state codes and ordinances. The Contractor shall take all required plumbing and electrical applications and permits, arrange for all necessary inspections and shall pay all fees and expenses in connection with same as part of work under the contract.
- UNIT PRICES:** The successful bidder shall furnish, to the Owner, a unit price breakdown for all materials. The Owner may at his own discretion, add to or delete from the materials, using the unit price breakdown submitted to and accepted by the Owner.
- MAINTENANCE PERIOD:** The irrigation system shall be maintained for a period of 90 days after final acceptance of installation. Maintenance shall include checking of the system 2 times per week. Contractor shall be responsible to replace/repair any broken or malfunctioning parts of the system including those damaged by accidents or vandalism. Repairs shall be made immediately at the time of inspection or when notified by the Landscape Architect.
- The irrigation system shall provide 100% coverage with a minimum of 90% overlap of water spray.
- The system is design to provide sprinkler precipitation rates that are nearly equal in each zone. Mixing of sprinklers with widely varying precipitation rates in a zone will not be accepted.
- Irrigation mainline shall be made of Class 200 PVC and all laterals shall be Class 200 PVC, except flexible PVC (or Toro funny pipe) for flexible swing joint and Schedule 40 PVC risers for spray heads in shrub areas. Schedule 80 galvanized steel pipe is to be used for all above ground fittings. Pipe locations shall be adjusted in the field. When laying out mains and laterals, locate pipe near edges of pavement or against buildings wherever possible, to allow space for plant rootballs. Coordinate pipe locations with plantings. Bury all mains and laterals 18" min. below surface. Depth shall be measured to top of pipe.
- Keep pop-up sprinkler heads a minimum of 8" from edges of pavement and curbing, and heads on risers a minimum of 18", or as indicated in the plans.
- All heads located in shrub or groundcover beds shall be installed on a riser as per details in the plans. All other heads shall be installed on a swing joint as per details in the plans.
- Place irrigation control wire in conduit in the same trench as mains and under the main. ASI wire shall be #14 or larger solid copper U.L. approved underground direct burial cable and shall be continuous with no splices from controller to solenoid valve.
- Valve locations are schematic and shall be adjusted in the field. Each valve shall be in a separate valve box (10" x 16" min.). When grouping valve boxes in grass or groundcover areas, set boxes a minimum of 12' apart to allow grass or groundcover to grow between them. When possible, hide valve boxes in shrub beds, a minimum of 12' from edge of beds. Set all valve boxes, concrete or plastic, in ground with cover flush with finish grade, and level, with a minimum of 6" of pea gravel at the bottom of the box, with at least 2" of clearance from the bottom of the valve to the top of the gravel.
- TESTING:** Notify the Landscape Architect in writing when testing will be conducted. Conduct test in the presence of the Landscape Architect. After all PVC assembly is completed the lines shall be flushed to insure that no rocks, sand, or other foreign debris remains in the lines. The mains shall be filled with water and all outlets shall be capped and plugged. The main shall be pressurized to 100 PSI for a minimum of one hour. No section of the main will be approved if the pressure drops more than 5 PSI at the end of the one hour period. Leaks shall be repaired immediately and the system shall be re-tested until found satisfactory by the Landscape Architect.




BACKFLOW PREVENTION ASSEMBLY DETAIL IRRIGATION SYSTEM ONLY (REFER TO CIVIL DRAWINGS)



| Inlet Pressure psi | 12" Spacing | | 18" Spacing | | 24" Spacing | |
|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|
| | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) |
| 15 | 273 | 155 | 314 | 250 | 424 | 322 |
| 20 | 318 | 169 | 353 | 294 | 508 | 368 |
| 30 | 360 | 220 | 419 | 350 | 586 | 414 |
| 40 | 395 | 255 | 465 | 402 | 652 | 474 |
| 50 | 417 | 285 | 528 | 420 | 720 | 488 |
| 60 | 460 | 290 | 596 | 455 | 780 | 514 |



| Inlet Pressure psi | 12" Spacing | | 18" Spacing | | 24" Spacing | |
|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|--------------------|
| | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) | Nominal Flow (gph) |
| 15 | 273 | 155 | 314 | 250 | 424 | 322 |
| 20 | 318 | 169 | 353 | 294 | 508 | 368 |
| 30 | 360 | 220 | 419 | 350 | 586 | 414 |
| 40 | 395 | 255 | 465 | 402 | 652 | 474 |
| 50 | 417 | 285 | 528 | 420 | 720 | 488 |
| 60 | 460 | 290 | 596 | 455 | 780 | 514 |



XFS SUBSURFACE DRIPLINE END FEED LAYOUT

XFS SUBSURFACE DRIPLINE CENTERFEED LAYOUT



169 E FLAGLER ST. SUITE 727 MIAMI, FL. 33131 P: 786.588.7260

CLIENT
801 ARTHUR GODFREY ROAD

801 ARTHUR GODFREY ROAD, MIAMI BEACH, FL 33140

CONSULTANTS
MEP CONSULTANT:
H. VIDAL & ASSOCIATES INC. 241 NW S RIVER DR. MIAMI, FL 33128 P: 305.571.1860

STRUCTURAL
VHCE
99 NW 27TH AVE MIAMI, FL 33125 P: 305.969.9423

LANDSCAPE ARCHITECTS:
GARDNER + SEMLER LANDSCAPE ARCHITECTURE 17670 NW 78TH AVE, SUITE 214 MIAMI, FL 33015 P: 305.392.1016

SEAL / SIGNATURE

Digitally signed by Kenneth Eric Gardner DN: c=US, st=Florida, l=Hialeah, o=GSLA DESIGN INC., cn=Kenneth Eric Gardner, email=ken@gslladesign.com Date: 2023.06.13 11:40:39 -04'00'

KEN GARDNER
FL LA #1569

ISSUES

| DESCRIPTION | REVISION NUMBER | DATE |
|-------------|-----------------|------|
| | | |

FILE INFORMATION

Project: 9768.00
Drawn: CSLA
Checked: KG
Project Phase: --

SHEET NAME
IRRIGATION SPECS AND DETAILS

LA-104