

# Sunset Harbour Miami Beach, Florida

traffic study



prepared for:  
**Deco Capital Group, LLC**

**Traf Tech**  
ENGINEERING, INC.

**Revised July 2018**

# Traf Tech

ENGINEERING, INC.

July 27, 2018

Mr. Bradley W. Colmer  
Managing Principal  
Deco Capital Group, LLC  
119 Washington Avenue, Suite 505  
Miami Beach, Florida 33139

**Re: Sunset Harbour- Traffic Engineering Study  
Miami Beach, Florida**

Dear Bradley:

Traf Tech Engineering, Inc. is pleased to provide you with the results of the traffic study undertaken for the proposed Sunset Harbor project planned to be located at 1759 Purdy Avenue in Miami Beach, Florida. The revised study addresses the traffic impacts created by the proposed project to the surrounding street system.

It has been a pleasure working with Deco Capital Group, LLC on this project.

Sincerely,

**TRAF TECH ENGINEERING, INC.**

Joaquin E. Vargas, P.E.  
Senior Transportation Engineer



July 27, 2018

8400 North University Drive, Suite 309, Tamarac, Florida 33321

Tel: (954) 582-0988 Fax: (954) 582-0989

## TABLE OF CONTENTS

---

<b>INTRODUCTION.....</b>	1
<b>INVENTORY .....</b>	3
Existing Land Use.....	3
Proposed Land Uses and Access.....	3
<b>EXISTING CONDITIONS .....</b>	4
Roadway System.....	4
Nearby Intersections.....	4
<b>TRAFFIC COUNTS .....</b>	6
<b>TRIP GENERATION.....</b>	8
<b>TRIP DISTRIBUTION AND TRAFFIC ASSIGNMENT .....</b>	10
<b>TRAFFIC ANALYSES .....</b>	14
Future Conditions Traffic Volumes .....	14
Level of Service Analyses.....	15
Valet Operation .....	19
<b>CONCLUSIONS AND RECOMMENDATIONS.....</b>	21

### LIST OF FIGURES

FIGURE 1 – Project Location Map .....	2
FIGURE 2 – Existing Lane Geometry .....	5
FIGURE 3 – Existing Traffic Counts – Peak Hour .....	7
FIGURE 4A – New Project Traffic Assignment .....	11
FIGURE 4B – Pass-by Trips.....	12
FIGURE 4C – Valet Trips .....	13
FIGURE 5 – Background Traffic (Year 2020) .....	16
FIGURE 6 – Total Traffic with Project (Year 2020).....	17

### LIST OF TABLES

TABLE 1 – Trip Generation Summary.....	8
TABLE 2 – Project Trip Distribution .....	10
TABLE 3 – Signalized Intersection Capacity/LOS Analyses .....	18
TABLE 4 – Unsignalized Intersections Capacity/LOS Analyses .....	18
TABLE 5 – Signalized Intersections 95 <sup>th</sup> Queue .....	19
TABLE 6 – Unsignalized Intersections 95 <sup>th</sup> Queue .....	19

## **INTRODUCTION**

---

Sunset Harbour is a proposed mixed-use development, including retail and residential units planned to be located at 1759 Purdy Avenue in the City of Miami Beach in Miami-Dade County, Florida. The location of the project site is illustrated in Figure 1 on the following page.

Traf Tech Engineering, Inc. was retained by Deco Capital Group, LLC to conduct a traffic study<sup>1</sup> in connection with the proposed development. The study addresses trip generation and the traffic impacts created by the proposed project on the nearby transportation network. This study is divided into seven (7) sections, as listed below:

1. Inventory
2. Existing Conditions
3. Traffic Counts
4. Trip Generation
5. Trip Distribution and Traffic Assignment
6. Traffic Impact Analysis
7. Conclusions and Recommendations

---

<sup>1</sup> The traffic methodology was discussed and agreed with the City of Miami Beach staff and is included in Appendix A



**Traf Tech**  
ENGINEERING, INC.

### PROJECT LOCATION MAP

**FIGURE 1**  
Sunset Harbour  
Miami Beach, Florida

## INVENTORY

---

### **Existing Land Use and Access**

The project site is currently vacant.

### **Proposed Land Use and Access**

An 19,214 square-foot commercial building plus 12 residential units (ownership) with a parking structure on site.

The proposed access to the parking structure will be off of Bay Road. An internal pedestrian connection roadway linking Purdy Avenue and Bay Road is proposed near the north property line (Pedestrian Promenade). Valet service is being considered for the residents and 80% of the retail customers. The valet station is anticipated to be located on Purdy Avenue and all entrance and exiting to the garage will occur on Bay Road.

## **EXISTING CONDITIONS**

---

This section addresses the existing roadway system located in the vicinity of the project site and nearby intersections.

### **Roadway System**


The roadway system located near the project site includes Dade Boulevard, 17<sup>th</sup> Street, West Avenue, Bay Road, Purdy Avenue, 18<sup>th</sup> Street, and 20<sup>th</sup> Street. Dade Boulevard is a 4-lane facility while 17<sup>th</sup> Street, West Avenue, Bay Road, Purdy Avenue, 18<sup>th</sup> Street and 20<sup>th</sup> Street are generally 2-lane local streets.

### **Nearby Intersections**

With the assistance of City of Miami Beach staff, nine intersections (were identified as the locations that will be impacted the most by the proposed project. These intersections include:

1. Dade Boulevard and Purdy Avenue (signalized)
2. Dade Boulevard and Bay Road (signalized)
3. Dade Boulevard and West Avenue (stop controlled)
4. 17<sup>th</sup> Street and West Avenue (signalized)
5. 18<sup>th</sup> Street and West Avenue
6. 18<sup>th</sup> Street and Bay Road
7. 18<sup>th</sup> Street and Purdy Avenue
8. 20th Street and West Avenue
9. 20th Street and Bay Road (stop controlled)

Figure 2 shows the existing lane geometry of the study intersections selected for analysis purposes. The number of lanes on the street system surrounding the project site is also depicted in the figure.



**Traf Tech**  
ENGINEERING, INC.

## EXISTING LANE GEOMETRY

**FIGURE 2**  
Sunset Harbour  
Miami Beach, Florida

## TRAFFIC COUNTS


---

Traf Tech Engineering, Inc., in association with Traffic Survey Specialists, Inc., collected intersection turning movement counts at the following nine (9) intersections located within the study area:

- Dade Boulevard and Purdy Avenue (signalized)
- Dade Boulevard and Bay Road (signalized)
- Dade Boulevard and West Avenue (stop controlled)
- 17<sup>th</sup> Street and West Avenue (signalized)
- 18<sup>th</sup> Street and West Avenue
- 18<sup>th</sup> Street and Bay Road
- 18<sup>th</sup> Street and Purdy Avenue
- 20th Street and West Avenue
- 20th Street and Bay Road

The intersection turning movement counts were collected on Friday, December 15, 2017 . The intersection turning movement counts were recorded during the afternoon (4:30 PM to 7:00 PM) peak period. At the intersection of 20<sup>th</sup> Street and Bay Road, 12-hour turning movement counts were collected on March 9, 2018 from 9 AM to 9 PM.

Figure 3 summarizes the results of the intersection turning movement counts. Appendix C contains the intersection turning movement counts, as collected in the field. The signal timing plans were obtained from the Miami-Dade County's ftp site and are also contained in Appendix C.



**Traf Tech**  
ENGINEERING, INC.

**EXISTING TRAFFIC COUNTS – PM Peak Hour**  
**(December 15, 2017)**

**FIGURE 3**  
Sunset Harbour  
Miami Beach, Florida

## TRIP GENERATION

---

The trip generation for the project was based on information contained in the Institute of Transportation Engineer's (ITE) *Trip Generation Manual* (10<sup>th</sup> Edition). According to the subject ITE manual, the most appropriate “land use” categories for the proposed land uses includes: Land Use 820 – Shopping Center and Land Use 220 – Multifamily Housing. Table 1 summarizes the trips associated with the proposed development.

TABLE 1 Trip Generation Summary (Proposed Uses) Sunset Harbour					
Land Use	Size	Daily Trips	PM Peak Hour		
			Total Trips	Inbound	Outbound
Retail (LUC 820)	19,214 sf	1,958	160	77	83
Residential (LUC 220)	12 units	50	9	6	3
<b>Subtotal</b>		<b>2,008</b>	<b>169</b>	<b>83</b>	<b>86</b>
Internalization (5%)		-100	-8	-4	-4
Multimodal Trip Reduction (20%)		-382	-32	-16	-16
<b>Gross Trips</b>		<b>1,526</b>	<b>129</b>	<b>63</b>	<b>66</b>
Pass-by (Retail -34%)		-499	-41	-21	-20
<b>Net New Trips</b>		<b>1,027</b>	<b>88</b>	<b>42</b>	<b>46</b>

Source: Institute of Transportation Engineer's (ITE) *Trip Generation Manual* (10<sup>th</sup> Edition)

As indicated in Table 1, the new trips anticipated to be generated by the proposed development consist of approximately 1,027 daily trips and approximately 86 trips during the weekday PM peak hour (42 inbound and 46 outbound).

The trip generation rates/equations used to determine the trips associated with the proposed land uses are presented below:

---

## **ITE Land Use 820 – Shopping Center**

### Weekday Daily Trip Generation

$$\ln T = 0.68 \ln (X) + 5.57$$

Where T = number of weekday daily trips and

X = 1,000 Sq. feet of gross leasable area

### Weekday PM Peak Hour of Adjacent Street

$$\ln T = 0.74 \ln (X) + 2.89 \text{ (48% inbound and 52% outbound)}$$

Where T = number of weekday peak hour trips and

X = 1,000 Sq. feet of gross leasable area

## **ITE Land Use 220 – Multifamily Housing**

### Weekday Daily Trip Generation

$$T = 7.56 (X) + 40.86$$

Where T = number of weekday daily trips and

X = number of dwelling units

### Weekday PM Peak Hour of Adjacent Street

$$\ln T = 0.89 \ln (X) - 0.02 \text{ (63% inbound and 37% outbound)}$$

Where T = number of weekday peak hour trips and

X = number of dwelling units

## TRIP DISTRIBUTION AND TRAFFIC ASSIGNMENT

---

The trip distribution and traffic assignment for the project were based on Miami-Dade County's Cardinal Distribution information for the study area. Table 2 summarizes the County's cardinal distribution data for Traffic Analysis Zone 639, which is applicable to the project site from the latest SERPM data published by Miami-Dade County.


<b>TABLE 2</b> <b>Project Trip Distribution</b> <b>Sunset Harbour</b>		
	<b>Direction</b>	<b>% of Total Trips</b>
North:	Northwest	9.8
	Northeast	15.2
South:	Southwest	2.3
	Southeast	19.6
East:	Northeast	5.8
	Southeast	3.5
West:	Northwest	17.0
	Southwest	26.8
<b>Total</b>		100.00%

Source: *Miami-Dade County. LEGEND: 2040*

Based on the above, the following traffic assignment was assumed for the proposed development:

- 25% to and from the west via Dade Boulevard
- 19% to and from the west via MacArthur Causeway – Alton Road (reflected at the intersection of Dade Boulevard and West Avenue)
- 5.5% to and from the east via Dade Boulevard
- 3.5% to and from the east via 17 Street
- 25% to and from the north via Alton Road – N. Bay Road. (reflected at the intersection of 20<sup>th</sup> Street and West Avenue). The 25% was distributed as follows:
  - 9% to and from the north via West Avenue
  - 8% to and from the north via Bay Road
  - 8% to and from the north via Purdy Avenue
- 22% to and from the south via West Avenue


The new peak hour traffic generated by the project was assigned to the nearby transportation network using the traffic assignment documented above. The new project traffic assignment is summarized in Figures 4A, 4B, and 4C.



Traf Tech  
ENGINEERING, INC.

### NEW PROJECT TRAFFIC ASSIGNMENT (Weekday New PM Peak Hour Trips)

**FIGURE 4A**  
Sunset Harbour  
Miami Beach, Florida



Traf Tech  
ENGINEERING, INC.

### NEW PROJECT TRAFFIC ASSIGNMENT (Weekday Pass-by Trips)

**FIGURE 4B**  
Sunset Harbour  
Miami Beach, Florida

Valet Trips =  $0.80 \times (\text{Inbound trips} - \text{Internalization} - \text{Multimodal reduction})$

Where:

Inbound trips = 77 (from trip generation table)


$$\text{Internalization} = 77 \times 0.05 = 4$$

$$\text{Multimodal reduction} = 0.20 \times (77 - 4) = 15 \text{ (multimodal reduction was applied after internalization)}$$

$$\text{Valet Trips} = 0.80 \times (77 - 4 - 15) = 46.4, \text{ say } 47$$

Please note that valet trips already include pass-by trips since were calculated based on In-bound trips

**Assumption:**  
Valet trips were not subtracted from net new and pass-by trips (conservative assumption – double counting impacts)



## TRAFFIC ANALYSIS

---

This section of the study is divided into three parts. The first part consists of developing the future conditions traffic volumes for the study area. The second part includes level-of-service analyses for existing and future conditions. The final section focusses on valet parking.

### **Future Conditions Traffic Volumes**

Two sets of future traffic volumes were developed. The first set includes project buildout conditions without the proposed project and the second set adds the new trips anticipated to be generated by the project.

In order to develop year 2020 traffic volumes (project anticipated to be built and occupied by the year 2020), without the proposed project, two separate analyses were undertaken. The first analysis converts the existing peak hour traffic counts collected in the field during the month of December to average peak season conditions. Based on FDOT's Peak Season Factor Category report, 1.04 and 1.0 factors are required to convert traffic counts collected in second week of December and first week of March to average peak season conditions (refer to Appendix D). The second analysis includes a growth factor to project 2017 peak season traffic volumes to the year 2020. Based on traffic growth data published by the FDOT for a nearby traffic count stations, minimal/negligible traffic growth has occurred during the past five years (refer to Appendix D). However, in order to assess impacts with a conservative approach, and to account for unforeseen approved project (committed trips) that may impact the study intersections, a one percent (1%) growth rate was used for purposes of this study. Additionally, trips associated with the approved 1901 Alton, Trader Joes, 1747 Bay Road Development, and 1750 Alton were added as committed developments.

---


The new trips generated by the Sunset Harbour (refer to Figure 4) were added to the 2020 background traffic in order to develop total traffic conditions. The future traffic projections for the study intersections (peak season adjustments, traffic growth rates, committed developments and project traffic) are presented in tabular format in Appendix E. Figures 5 and 6 present the year 2020 future traffic volumes for the study area.

Figure 5 includes background traffic only (without the proposed project) and Figure 6 includes the additional traffic anticipated to be generated by the Sunset Harbour project.

### **Level of Service Analyses**

Intersection capacity/level of service analyses were conducted for the eight study intersections. The analyses were undertaken following the capacity/level of service procedures outlined in the Highway Capacity Manual (HCM) using the SYNCHRO software. The results of the capacity analyses are summarized in Tables 3 and 4. As indicated in Tables 3 and 4, all study intersections are currently operating at an acceptable level of service. All study intersections are currently operating at an acceptable level of service. In the year 2020 with the proposed project in place, all intersections are expected to continue to operate at an acceptable level of service.


Tables 5 and 6 summarize the existing turn lane storage and the expected queues at all turn lanes of the study intersections.



**Traf Tech**  
ENGINEERING, INC.

**BACKGROUND TRAFFIC – Year 2020**  
(Weekdays PM Peak Hour Trips)

**FIGURE 5**  
Sunset Harbour  
Miami Beach, Florida



**Traf Tech**  
ENGINEERING, INC.

**TOTAL TRAFFIC with PROJECT – Year 2020**  
**(Weekdays PM Peak Hour Trips)**

**FIGURE 6**  
Sunset Harbour  
Miami Beach, Florida

TABLE 3			
Intersection Level of Service – (Signalized Intersections)			
Sunset Harbour			
		Future Traffic Conditions	
	2017	2020	2020
Intersection	Existing	w/o Project	With Project
Dade Blvd & Purdy Ave	B	B	B
Dade Blvd & Bay Road/17th St	C	C	D
West Ave & Dade Blvd	B	B	B
17 <sup>th</sup> St & West Ave	D	D	D

Source: *Highway Capacity Manual*

TABLE 4			
Intersection Level of Service (Unsignalized Intersections)			
Sunset Harbour			
		Future Traffic Conditions	
	2017	2020	2020
Intersection/Movement	Existing	w/o Project	With Project
18 St & West Ave	A	B	B
18 St & Bay Rd	A	A	A
18 St & Purdy Ave	A	A	B
20 St & West Ave	B	B	B
20 St & Bay Rd	B	B	B
Bay Rd & Driveway			A

Source: *Highway Capacity Manual*

NOTE: All intersections on Table 4 are all-way stop and were analyzed as such, except the access driveway.

TABLE 5				
95th Queue – (Signalized Intersections)				
Sunset Harbour				
Intersection	Storage Bay (ft)	2017	Future Traffic Conditions	
			2020	2020
		Existing (ft)	w/o Project (ft)	With Project (ft)
Dade Blvd & Purdy Ave				
EBL	80	67	78	105
SBL	100	108	111	111
17 <sup>th</sup> St & West Ave				
NBL	170	169	199	184
WBL	160	170	174	173
SBL	50	28	27	26

Source: *Highway Capacity Manual*

TABLE 6				
95th Queue (Unsignalized Intersections)				
Sunset Harbour				
Intersection/Movement	Storage Bay (ft)	2017	Future Traffic Conditions	
			2020	2020
		Existing (ft)	w/o Project (ft)	With Project (ft)
18 St & Purdy Ave				
NBL	100	0.1	0.1	0.1
SBL	100	0.1	0.1	0.1
20 St & West Ave				
WBL	85	1.0	1.0	1.1

Source: *Highway Capacity Manual*

The computer printouts of the intersection capacity analyses are contained in Appendix F.

## Valet Operation

The proposed development will provide valet parking service to 80% of retail customers. Valet stand is anticipated to be located on Purdy Ave, and all entrance and exiting to the garage will occur on Bay Road. Thus, all vehicles will be dropped-off along Purdy Ave, will head north towards 18<sup>th</sup> Street, turn right on 18<sup>th</sup> Street, and right on Bay Road to

---

enter garage. Once a car is claimed, the vehicle will exit garage on Bay Road, head south toward Dade Boulevard, turn right on Dade Boulevard, and right on Purdy Avenue to be picked up near the valet stand.

In order to determine the stacking requirements associated with the valet operation, a queuing analysis was undertaken. The maximum number of inbound vehicles associated with this project, during a one-hour period, is approximately 47 vehicles (80% of the retail customers)

A queuing analysis was conducted in order to ensure that the stacking is sufficient to accommodate the maximum inbound vehicular demand anticipated at this facility.

The length of queue anticipated was determined using information contained in ITE's *Transportation and Land Development*, Chapter 8 – Drive-In Facilities<sup>1</sup>. For this analysis, the following input variables were used:

- Service Rate: It was assumed that the average time to park/unpark a vehicle by a valet runner is approximately 3.5 minutes, or 17 vehicles per hour per valet runner. Assuming up to six (6) valet runners, the maximum service rate of the facility is 120 vehicles in a one-hour period.
- Demand Rate: As indicated above, a maximum of 47 vehicles will arrive during the highest hour (i.e., PM peak). Please refer to calculations in Appendix F.

Using equation 8-9b and Table 8-11 of ITE's *Transportation and Land Development*, the maximum length of queue at the 95% confidence level, is two vehicles. Therefore, the valet station should provide stacking for at least two (2) vehicles. The results of the ITE queuing procedure is contained in Appendix F.

---

<sup>1</sup> By Vergil G. Stover and Frank J. Koepke.

## **CONCLUSIONS AND RECOMMENDATIONS**

---

Sunset Harbour is a proposed mixed-use development, including retail and residential units planned to be located at 1759 Purdy Avenue in the City of Miami Beach in Miami-Dade County, Florida.

The project site is currently vacant. Proposed to the site is an 19,214 square-foot commercial building plus 12 residential units (ownership) with a parking structure on site.

The proposed access to the parking structure will be off of Bay Road. An internal pedestrian connection roadway linking Purdy Avenue and Bay Road is proposed near the north property line (Pedestrian Promenade). Valet service is being considered for 80% of the retail customers. The valet station is anticipated to be located on Purdy Avenue and all entrance and exiting to the garage will occur on Bay Road.

Traf Tech Engineering, Inc. was retained by Deco Capital Group, LLC to conduct a traffic study in connection with the proposed development. The conclusions and recommendations of the traffic study are presented below:

- The new trips anticipated to be generated by the proposed development consist of approximately 1,027 daily trips and approximately 86 trips during the weekday PM peak hour (42 inbound and 46 outbound).
- All study intersections are currently operating at an acceptable level of service. In the year 2020 with the proposed project in place, all intersections are expected to continue to operate at an acceptable level of service.
- The maximum length of queue at the 95% confidence level, is two (2) vehicles. Therefore, the valet station should provide stacking for at least two (2) vehicles.

## **TRANSPORTATION DEMAND MANAGEMENT (TDM) PLAN**

---

Traf Tech Engineering, Inc. prepared a Transportation Demand Management (TDM) plan for the proposed development.

### Introduction

Travel Demand Management plans (TDM) establish policies and mechanisms to reduce automobile trips to and from designated facilities. TDM plans usually use several approaches to address all modes of transportation likely to be used to provide access to a facility such as single occupant driving, carpooling, transit, bicycling and walking. The goal of TDM plans is to increase the use of alternatives modes to single occupant driving, i.e., to reduce the number of automobile trips to and from the facility and consequently, minimizing automobile traffic impacts on the street system.

Successful TDM plans not only address all modes of transportation, but also use policies such as inducements for alternative modes (subsidies), physical enhancements (bike lockers, preferential parking for carpools) and disincentives for automobile use (no free parking for employees).

Potential measures for each mode are addressed below. Use of an employee transportation subsidy is also presented.

### Pedestrian Access

Walking not only reduces automobile trips and their contribution to congestion and emissions, it also provides health benefits to the employees who use this mode of transportation. It is, however, the mode that is least likely to be used for a number of reasons. It is unlikely that employees of the restaurant/bar use will reside within a reasonable walking distance (within  $\frac{1}{4}$  -  $\frac{1}{2}$  mile) of the subject facility. However, the area near the subject project is a high pedestrian traffic area and therefore, many future customers of the Sunset Harbour development are expected to be walking trips. Sidewalks exist on the east and west sides of project as well as safe pedestrian crosswalks

---

(with ramps and pedestrian signals).

### Bicycling

The site of the Sunset Harbour project offers two potential approaches to encourage cycling, the use of the Citi Bike program and use of retail employee-owned bicycles.

Use of Citi Bike could be supported by providing monthly passes to employees. Monthly passes are \$15.00 for unlimited 30 minute rides and \$25.00 for unlimited 60 minute rides. Within the immediate area of the project, there is one convenient Citi Bike rental station (Station 177 - Purdy Ave & 18th Street (Marina), and Station 187 - West Ave & 20th Street (Publix on the Bay)) and employees will be informed of the Citi Bike Stations.

### Mass Transit

There is a wealth of transit options for the Sunset Harbour development. These transit routes include A, M, and 115. The nearest bus stop for these services is located at the intersection of Dade Boulevard and Purdue Avenue. These transit routes provide frequent service and access to all of Miami-Dade County as well as connections to other destinations outside of the County. Employers of the restaurant can provide a significant inducement to employees to use public transportation (Miami-Dade Transit, MDT) through a transit subsidy. Transit subsidies can also provide tax benefits to both employees and employers.

#### MDT offers three methods to provide transit subsidies:

The employee uses pre-tax dollars from their salary to purchase monthly transit passes. There is no income tax on the portion of their salary used for transit passes. The pre-tax funds also reduce the employees' taxable salary, reducing the total amount of income tax paid by the employees. The employer pays the total cost of a monthly transit pass using a tax-deductible (to the employer) subsidy. The employer receives a tax deduction equivalent to the value of the transit subsidies provided to the employees. The transit subsidy is a fringe benefit to employees and is not taxable income.

---

Both the employer and employees share the cost of transit passes, paying for them with pre-tax dollars. The employer reduces his/her payroll taxes. Employees do not pay income tax on the money used for transit passes.

MDT monthly passes if purchased by an individual are \$112.50. Corporate discounts are available based on the number of participating employees. For 4 – 99 employees, monthly passes are \$101.25 per employee, for 100 or more employees, the cost is \$95.65 per employee.

#### Carpooling

Carpooling is historically the least effective alternative transportation mode, even when implemented on a regional basis. Given the relatively small employee base of a single employer, it is unlikely that carpooling will provide a significant amount of trip reduction. However, preferential parking could be made available to employees that carpool.

# **APPENDIX A**


## **Traffic Methodology**

**From:** Akcay, Firat <[FiratAkcay@miamibeachfl.gov](mailto:FiratAkcay@miamibeachfl.gov)>  
**Sent:** Tuesday, October 10, 2017 1:25 PM  
**To:** Joaquin@traftech.biz  
**Cc:** Munday, Tui; 'Claudia Lamus'; Ferrer, Josiel  
**Subject:** RE: PB 10-02-2017 Sunset Harbor

Joaquin,

From the methodology meeting with Joaquin on Friday and after meeting with Josiel for an extended review of the project our suggested scope. The traffic study shall include, at a minimum, the following scope items:

**Project Location: 1752 Bay Road**



**Project Scope:** Joaquin, please provide final proposed development plan by land use and number of units for residential component as the study from 2015 suggests 15 units compared to 12 units with the latest plans you provided.

If you have any information regarding the possible tenants of the retail component as well as for the restaurant component, please provide this information for trip generation purposes.

Otherwise, we suggest shopping center 820(equation) for the retail land uses.

**Traffic Counts:** The West Ave Bridge and Dade Boulevard construction is scheduled to be completed on the 17<sup>th</sup> of this month.

Generally we would allow at least 3 months' time to allow for traffic to normalize and drivers to adjust to the new traffic pattern after the implementation of the new bridge.

Provide the date of hearing for the Planning Board Meeting. Based on the date, our Department is willing to allow traffic counts to be collected as soon as 2 weeks following opening of the bridge, the week of October 31<sup>st</sup>, if meeting date and time of review are a concern.

The intersections that will need to be counted:

Dade Blvd -	Purdy Avenue
	Bay Road
	West Avenue
17 <sup>th</sup> Street -	West Avenue
18 <sup>th</sup> Street-	West Avenue
	Bay Road
	Purdy Avenue
20 <sup>th</sup> Street-	West Avenue
	Bay Road(please collect multimodal counts for an AWSC warrant analysis)

#### **Committed Developments:**

Reach out to the Planning Department and copy me to obtain information on committed developments in the area.

#### **Valet and Parking:**

According to the site plan submitted, there is a parking deficit of 4 vehicles.

The valet plan needs to be submitted as well as pick up and drop off locations.

Will the restaurant have a separate valet station than the residential and retail valet service?

Please provide as much detail on this as possible.

#### **Trip reduction factors:**

Multimodal trip reduction: 20%

Internalization – Please use methodology presented in ITE Trip Generation Manual 9<sup>th</sup> Edition, Chapter 7, Multi-Use Developments.

#### **Master Plan:**

According to the Bicycle Pedestrian Master Plan, we are implementing a bicycle greenway along West Avenue. This greenway will continue over the West Avenue Bridge. Can you please collect geometric data on West Avenue, north of Dade Boulevard for a feasibility study of a 6 feet bicycle lane?

#### **Travel Demand Management Plan:**

Please provide a TDM plan.

#### **Peer Review:**

The type of peer review will be a Level B, in the amount of \$5800.00

Thank you and please feel free to contact us with any questions,



**Firat Akcay, Transportation Analyst**

TRANSPORTATION DEPARTMENT

1688 Meridian Avenue, Suite 801, Miami Beach, FL 33139

Tel: 305-673-7000 X 6839 / [www.miamibeachfl.gov](http://www.miamibeachfl.gov)

*We are committed to providing excellent public service and safety to all who live, work and play in our vibrant, tropical, historic, community.*



Please do not print this e-mail unless necessary.

---

**From:** Munday, Tui  
**Sent:** Monday, October 09, 2017 1:21 PM  
**To:** Akcay, Firat; Ferrer, Josiel  
**Cc:** 'Joaquin@traftech.biz'  
**Subject:** RE: PB 10-02-2017 Sunset Harbor

What was the decision about peer review and the price/level of the peer review?



**Tui Munday**, Senior Planner  
PLANNING DEPARTMENT  
1700 Convention Center Drive, Miami Beach, FL 33139  
Tel: 305-673-7000 X 6320 / Fx: 305-673-7559 / [www.miamibeachfl.gov](http://www.miamibeachfl.gov)

*We are committed to providing excellent public service and safety to all who live, work and play in our vibrant, tropical, historic, community.*



Please do not print this e-mail unless necessary.

---

**From:** [Joaquin@traftech.biz](mailto:joaquin@traftech.biz) [mailto:[joaquin@traftech.biz](mailto:joaquin@traftech.biz)]  
**Sent:** Friday, October 06, 2017 10:38 AM  
**To:** Akcay, Firat; Ferrer, Josiel  
**Cc:** Munday, Tui  
**Subject:** PB 10-02-2017 Sunset Harbor

Firat and Josiel,


Will see you around 2PM to discuss the traffic methodology. Josiel may remember, we evaluated this project back in late 2015 (see attached study without appendix) and had to rely on old traffic counts because at that time the area was under construction. The project is very similar (less residential units). It consists of two restaurants 5,768 sf and retail of about 12,498 sf plus 12 residential units.

Joaquin

Joaquin E. Vargas, P.E.  
**Traf Tech** ENGINEERING  
8400 N. University Drive, Suite 309  
Tamarac, Florida 33321  
Tel: (954) 582-0988  
Fax: (954) 582-0989  
Mobile: (954) 643-1671  
[joaquin@traftech.biz](mailto:joaquin@traftech.biz)

# **APPENDIX B**

## **Site Plan – Sunset Harbour**



## **APPENDIX C**

### **Signal Timing Plan and Traffic Counts**

# TOD Schedule Report

for 4130: West Av&17 St

Print Date:

11/20/2017

Print Time:

6:14 PM

<u>Asset</u>	<u>Intersection</u>	<u>TOD Schedule</u>	<u>Op Mode</u>	<u>Plan #</u>	<u>Cycle</u>	<u>Offset</u>	<u>TOD Setting</u>	<u>Active PhaseBank</u>	<u>Active Maximum</u>
4130	West Av&17 St	DOW-2		N/A	0	0	N/A	0	Max 0
<b>Splits</b>									
<u>PH 1</u>	<u>PH 2</u>	<u>PH 3</u>	<u>PH 4</u>	<u>PH 5</u>	<u>PH 6</u>	<u>PH 7</u>	<u>PH 8</u>		
-	WBT	-	NBT	WBL	EBT	-	SBT		
0	0	0	0	0	0	0	0		
									

Active Phase Bank: Phase Bank 1

<u>Phase</u>	<u>Walk</u>			<u>Don't Walk</u>			<u>Min Initial</u>			<u>Veh Ext</u>			<u>Max Limit</u>			<u>Max 2</u>			<u>Yellow</u>	<u>Red</u>	
	Phase Bank			1	2	3	1	2	3	1	2	3	1	2	3	1	2	3			
1 -	0	-	0	-	0	0	0	-	0	0	-	0	0	-	0	0	-	0	0	0	
2 WBT	7	-	7	-	7	24	-	24	-	24	7	-	7	-	5	1	-	1	-	1	2.2
3 -	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0
4 NBT	7	-	7	-	7	20	-	20	-	20	7	-	7	-	5	2.5	-	2.5	-	2.5	2.2
5 WBL	0	-	0	-	0	0	-	0	-	0	5	-	5	-	0	2	-	2	-	2	2
6 EBT	7	-	7	-	7	24	-	24	-	24	7	-	7	-	5	1	-	1	-	1	2.2
7 -	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0
8 SBT	0	-	0	-	0	0	-	0	-	0	7	-	7	-	5	2.5	-	2.5	-	2.5	2.2

Last In Service Date: unknown

### Permitted Phases

**12345678**

Default	-2-456-8
External Permit 0	-2-4-6--
External Permit 1	-2-4-6--
External Permit 2	-2-4-6--

# TOD Schedule Report

for 4130: West Av&17 St

Print Date:

11/20/2017

Print Time:

6:14 PM

		Green Time										
Current TOD Schedule	Plan	Cycle	1	2	3	4	5	6	7	8	Ring Offset	Offset
		-	WBT	-	NBT	WBL	EBT	-	SBT			
1		160	0	69	0	79	14	49	0	79	0	72
2		160	0	69	0	79	14	49	0	79	0	72
3		120	0	59	0	49	14	39	0	49	0	72
4		130	0	69	0	49	14	49	0	49	0	54
5		130	0	77	0	41	22	49	0	41	0	60
6		130	0	69	0	49	14	49	0	49	0	44
7		105	0	64	0	29	9	49	0	29	0	72
8		120	0	59	0	49	9	44	0	49	0	109
9		120	0	59	0	49	9	44	0	49	0	111
10		130	0	69	0	49	9	54	0	49	0	44
13		105	0	64	0	29	9	49	0	29	0	67
14		105	0	64	0	29	9	49	0	29	0	75
15		130	0	69	0	49	9	54	0	49	0	66
16		130	0	69	0	49	9	54	0	49	0	114
17		130	0	69	0	49	9	54	0	49	0	44
18		90	0	49	0	29	9	34	0	29	0	75
19		90	0	49	0	29	9	34	0	29	0	75
20		130	0	69	0	49	9	54	0	49	0	75
23		90	0	49	0	29	9	34	0	29	0	75

## Local TOD Schedule

Time	Plan	DOW
0000	8	Su M T W Th F S
0030	Free	M T W Th
0100	Free	Su F S
0600	8	Su M T W Th F S
0800	7	Su S
0800	5	M T W Th F
0930	13	S
1000	14	Su S
1030	4	S
1200	14	S
1300	4	S
1515	16	M T W Th F
1600	7	Su S
1830	4	Su S
2000	8	Su M T W Th F S
2330	Free	M T W Th

## Current Time of Day Function

Time	Function	Settings *	Day of Week
0000	TOD OUTPUTS	-----	SuM T W ThF S

## Local Time of Day Function

Time	Function	Settings *	Day of Week
0000	TOD OUTPUTS	-----	Sum T W ThF S

## \* Settings

- Blank - FREE - Phase Bank 1, Max 1
- Blank - Plan - Phase Bank 1, Max 2
- 1 - Phase Bank 2, Max 1
- 2 - Phase Bank 2, Max 2
- 3 - Phase Bank 3, Max 1
- 4 - Phase Bank 3, Max 2
- 5 - EXTERNAL PERMIT 1
- 6 - EXTERNAL PERMIT 2
- 7 - X-PED OMIT
- 8 - TBA

**No Calendar Defined/Enabled**

# TOD Schedule Report

**for 4131: Bay Rd&Dade Blvd&17 St**

Print Date:

11/20/2017

Print Time:

6:14 PM

<u>Asset</u>	<u>Intersection</u>	<u>TOD Schedule</u>	<u>Op Mode</u>	<u>Plan #</u>	<u>Cycle</u>	<u>Offset</u>	<u>TOD Setting</u>	<u>Active PhaseBank</u>	<u>Active Maximum</u>
4131	Bay Rd&Dade Blvd&17 St	DOW-2		N/A	0	0	N/A	0	Max 0

## Splits

<u>PH 1</u>	<u>PH 2</u>	<u>PH 3</u>	<u>PH 4</u>	<u>PH 5</u>	<u>PH 6</u>	<u>PH 7</u>	<u>PH 8</u>
-	SWT	-	WBT	-	NET	-	-
0	0	0	0	0	0	0	0



## Active Phase Bank: Phase Bank 1

<u>Phase</u>	<u>Walk</u>			<u>Don't Walk</u>			<u>Min Initial</u>			<u>Veh Ext</u>			<u>Max Limit</u>			<u>Max 2</u>			<u>Yellow</u>		<u>Red</u>									
	Phase Bank			1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3									
1 -	0	-	0	0	0	-	0	0	-	0	0	-	0	0	-	0	0	-	0	0	0	0								
2 SWT	0	-	0	0	0	-	0	14	-	14	-	14	2.5	-	2.5	-	2.5	12	-	12	-	12	80	-	80	-	80	4	2.9	
3 -	4	-	4	4	15	-	15	15	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	0	0	0	0
4 WBT	0	-	0	0	0	-	0	14	-	14	-	14	3.5	-	3.5	-	3.5	10	-	10	-	10	80	-	80	-	50	4	3.7	
5 -	0	-	0	0	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	0	0	0	0	0
6 NET	0	-	0	0	0	-	0	14	-	14	-	14	2.5	-	2.5	-	2.5	12	-	12	-	12	80	-	80	-	80	4	2.9	
7 -	0	-	0	0	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	0	0	0	0	0
8 -	0	-	0	0	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	-	0	0	-	0	0	0	0	0	0

Last In Service Date: unknown

## Permitted Phases

12345678

Default	-234-6--
External Permit 0	-234-6--
External Permit 1	-234-6--
External Permit 2	-234-6--

<u>Green Time</u>												
<u>Current TOD Schedule</u>	<u>Plan</u>	<u>Cycle</u>	1	2	3	4	5	6	7	8	<u>Ring Offset</u>	<u>Offset</u>
			-	SWT	-	WBT	-	NET	-	-	-	-
1			85	0	27	13	30	0	27	0	0	0
2			120	0	62	13	30	0	62	0	0	20
3			130	0	72	13	30	0	72	0	0	6
4			95	0	37	13	30	0	37	0	0	0
5			80	0	22	13	30	0	22	0	0	0
6			90	0	32	13	30	0	32	0	0	68
13			90	0	32	13	30	0	32	0	0	0
25			140	0	82	13	30	0	82	0	0	122
26			180	0	122	13	30	0	122	0	0	58
27			140	0	82	13	30	0	82	0	0	64
28			140	0	82	13	30	0	82	0	0	114

## Local TOD Schedule

<u>Time</u>	<u>Plan</u>	<u>DOW</u>
0000	Free	Su M T W Th F S
0530	2	M T W Th F
0700	6	M T W Th F
0930	5	Su M T W Th F S
1030	2	Su
1515	Free	M T W Th F
1830	2	M T W Th F
2030	Free	Su
2330	Free	M T W Th F

**TOD Schedule Report**

for 4131: Bay Rd&amp;Dade Blvd&amp;17 St

Print Date:

11/20/2017

Print Time:

6:14 PM

**Current Time of Day Function**

<u>Time</u>	<u>Function</u>	<u>Settings *</u>	<u>Day of Week</u>
0000	TOD OUTPUTS	-----	SuM T W ThF S
0000	TOD LOCAL MULTIFU	----4---	SuM T W ThF S
0500	TOD LOCAL MULTIFU	-----	SuM T W ThF S
0530	TOD OUTPUTS	----3--	M T W ThF
1600	TOD OUTPUTS	----4---	M T W ThF
2330	TOD OUTPUTS	-----	M T W ThF

**Local Time of Day Function**

<u>Time</u>	<u>Function</u>	<u>Settings *</u>	<u>Day of Week</u>
0000	TOD OUTPUTS	-----	SuM T W ThF S
0000	TOD LOCAL MULTIFUNCT	----4---	SUM T W ThF S
0500	TOD LOCAL MULTIFUNCT	-----	SUM T W ThF S
0530	TOD OUTPUTS	----3--	M T W ThF
0930	TOD OUTPUTS	----2-	Su S
1600	TOD OUTPUTS	----4---	M T W ThF
2030	TOD OUTPUTS	-----	Su S
2330	TOD OUTPUTS	-----	M T W ThF

**\* Settings**

- Blank - FREE - Phase Bank 1, Max 1
- Blank - Plan - Phase Bank 1, Max 2
- 1 - Phase Bank 2, Max 1
- 2 - Phase Bank 2, Max 2
- 3 - Phase Bank 3, Max 1
- 4 - Phase Bank 3, Max 2
- 5 - EXTERNAL PERMIT 1
- 6 - EXTERNAL PERMIT 2
- 7 - X-PED OMIT
- 8 - TBA

**No Calendar Defined/Enabled**

# TOD Schedule Report

for 6593: Dade Blvd&Purdy Av

Print Date:

11/21/2017

Print Time:

10:11 AM

<u>Asset</u>	<u>Intersection</u>	<u>TOD Schedule</u>	<u>Op Mode</u>	<u>Plan #</u>	<u>Cycle</u>	<u>Offset</u>	<u>TOD Setting</u>	<u>Active PhaseBank</u>	<u>Active Maximum</u>
6593	Dade Blvd&Purdy Av	DOW-3		N/A	0	0	N/A	0	Max 0
<b>Splits</b>									
<u>PH 1</u>	<u>PH 2</u>	<u>PH 3</u>	<u>PH 4</u>	<u>PH 5</u>	<u>PH 6</u>	<u>PH 7</u>	<u>PH 8</u>		
-	WBT	-	-	-	EBT	-	SBT		
0	0	0	0	0	0	0	0		

Active Phase Bank: Phase Bank 1

<u>Phase</u>	<u>Walk</u>			<u>Don't Walk</u>			<u>Min Initial</u>			<u>Veh Ext</u>			<u>Max Limit</u>			<u>Max 2</u>			<u>Yellow</u>		<u>Red</u>											
	Phase Bank			1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	1	2	3	0										
1 -	0	-	0	0	0	-	0	0	-	0	0	-	0	0	-	0	0	-	0	0	0	0										
2 WBT	0	-	0	0	0	-	0	14	-	14	-	14	1	-	1	-	1	35	-	55	-	55	0									
3 -	0	-	0	0	0	-	0	0	-	0	0	-	0	0	-	0	0	-	0	0	0	0										
4 -	0	-	0	0	0	-	0	0	-	0	0	-	0	0	-	0	0	-	0	0	0	0										
5 -	0	-	0	0	0	-	0	0	-	0	0	-	0	0	-	0	0	-	0	0	0	0										
6 EBT	0	-	0	0	0	-	0	14	-	14	-	14	1	-	1	-	1	35	-	55	-	55	0									
7 -	0	-	0	0	0	-	0	0	-	0	0	-	0	0	-	0	0	-	0	0	0	0										
8 SBT	7	-	7	-	7	17	-	17	-	17	7	-	7	-	7	2.5	-	2.5	-	2.5	12	-	14	-	22	36	-	0	-	0	4	2

Last In Service Date: unknown

## Permitted Phases

12345678

Default	-2---6-8
External Permit 0	-2---6-8
External Permit 1	-2---6-8
External Permit 2	-2---6-8

<b>Green Time</b>												
<u>Current TOD Schedule</u>	<u>Plan</u>	<u>Cycle</u>	1	2	3	4	5	6	7	8	<u>Ring Offset</u>	<u>Offset</u>
			-	WBT	-	-	-	EBT	-	SBT	-	
2			80	0	43	0	0	0	43	0	25	0
3			130	0	83	0	0	0	83	0	35	0
4			90	0	52	0	0	0	52	0	26	0
13			90	0	53	0	0	0	53	0	25	0
20			110	0	73	0	0	0	73	0	25	0
25			140	0	103	0	0	0	103	0	25	0
26			180	0	143	0	0	0	143	0	25	0
27			140	0	103	0	0	0	103	0	25	0
28			140	0	103	0	0	0	103	0	25	0

## Local TOD Schedule

<u>Time</u>	<u>Plan</u>	<u>DOW</u>
0000	Free	Su M T W Th F S
0530	2	M T W Th F
0700	13	M T W Th F
0930	2	Su M T W Th F S
1515	3	M T W Th F
1830	2	M T W Th F
2030	Free	Su
2330	Free	M T W Th F

**TOD Schedule Report**

for 6593: Dade Blvd&amp;Purdy Av

Print Date:

11/21/2017

Print Time:

10:11 AM

**Current Time of Day Function**

<u>Time</u>	<u>Function</u>	<u>Settings *</u>	<u>Day of Week</u>
0000	TOD OUTPUTS	-----	SuM T W ThF S
0000	TOD LOCAL MULTIFU	----4---	SuM T W ThF S
0030	TOD OUTPUTS	-----1	SuM T W ThF S
0500	TOD LOCAL MULTIFU	-----	SuM T W ThF S
0600	TOD OUTPUTS	-----	SuM T W ThF S
2330	TOD OUTPUTS	-----1	M T W ThF

**Local Time of Day Function**

<u>Time</u>	<u>Function</u>	<u>Settings *</u>	<u>Day of Week</u>
0000	TOD OUTPUTS	-----	SuM T W ThF S
0000	TOD LOCAL MULTIFUNCT	----4---	SUM T W ThF S
0030	TOD OUTPUTS	-----1	SUM T W ThF S
0500	TOD LOCAL MULTIFUNCT	-----	SUM T W ThF S
0600	TOD OUTPUTS	-----	SUM T W ThF S
2000	TOD OUTPUTS	-----1	Su S
2330	TOD OUTPUTS	-----1	M T W ThF

**\* Settings**

- Blank - FREE - Phase Bank 1, Max 1
- Blank - Plan - Phase Bank 1, Max 2
- 1 - Phase Bank 2, Max 1
- 2 - Phase Bank 2, Max 2
- 3 - Phase Bank 3, Max 1
- 4 - Phase Bank 3, Max 2
- 5 - EXTERNAL PERMIT 1
- 6 - EXTERNAL PERMIT 2
- 7 - X-PED OMIT
- 8 - TBA

**No Calendar Defined/Enabled**

## TRAFFIC SURVEY SPECIALISTS, INC.

DADE BOULEVARD &amp; PURDY AVENUE

MIAMI BEACH, FLORIDA

COUNTED BY: RALPH MARTINEZ

NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109

DELRAY BEACH, FLORIDA

PHONE (561)272-3255

Site Code : 00170211

Start Date: 12/15/17

File I.D. : DADEPURD

Page : 1

## ALL VEHICLES

PURDY AVENUE				DADE BOULEVARD				-----				DADE BOULEVARD				DADE BOULEVARD					
From North				From East				From South				From West									
	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
Date 12/15/17	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	--	
16:30	0	21	0	34	0	0	137	9	0	0	0	0	0	29	91	0	0	29	91	0	321
16:45	0	16	0	40	0	0	146	13	0	0	0	0	0	42	115	0	0	42	115	0	372
17:00	0	13	0	43	1	0	119	17	0	0	0	0	0	29	104	0	0	29	104	0	326
17:15	0	15	0	44	0	0	120	19	0	0	0	0	0	38	128	0	0	38	128	0	364
Hr Total	0	65	0	161	1	0	522	58	0	0	0	0	0	138	438	0	0	138	438	0	1383
17:30	0	8	0	47	0	0	121	17	0	0	0	0	1	42	82	0	0	42	82	0	318
17:45	0	12	0	52	0	0	111	17	0	0	0	0	0	40	113	0	0	40	113	0	345
18:00	0	12	0	32	0	0	85	25	0	0	0	0	0	40	110	0	0	40	110	0	304
18:15	1	13	0	33	0	0	89	21	0	0	0	0	0	24	102	0	0	24	102	0	283
Hr Total	1	45	0	164	0	0	406	80	0	0	0	0	1	146	407	0	0	146	407	0	1250
18:30	0	4	0	30	4	0	102	20	0	0	0	0	0	17	81	0	0	17	81	0	258
18:45	0	16	0	30	0	0	124	22	0	0	0	0	0	28	111	0	0	28	111	0	331
Hr Total	0	20	0	60	4	0	226	42	0	0	0	0	0	45	192	0	0	45	192	0	589
*TOTAL*	1	130	0	385	5	0	1154	180	0	0	0	0	1	329	1037	0	0	329	1037	0	3222

TRAFFIC SURVEY SPECIALISTS, INC.


DADE BOULEVARD & PURDY AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: RALPH MARTINEZ  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561) 272-3255


Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : DADEPURD  
Page : 2

**ALL VEHICLES**

PURDY AVENUE				DADE BOULEVARD				-----				DADE BOULEVARD				
From North		From East		From South				From West								
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
<b>Date 12/15/17 -----</b>																
<b>Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17</b>																
<b>Peak start 16:30</b>				<b>16:30</b>				<b>16:30</b>				<b>16:30</b>				
Volume	0	65	0	161	1	0	522	58	0	0	0	0	0	138	438	0
Percent	0%	29%	0%	71%	0%	0%	90%	10%	0%	0%	0%	0%	0%	24%	76%	0%
Pk total	226				581				0					576		
Highest	<b>17:15</b>			<b>16:45</b>				<b>16:30</b>				<b>17:15</b>				
Volume	0	15	0	44	0	0	146	13	0	0	0	0	0	38	128	0
Hi total	59				159				0					166		
PHF	.96				.91				.0					.87		



**DADE BOULEVARD**



## TRAFFIC SURVEY SPECIALISTS, INC.

DADE BOULEVARD & PURDY AVENUE  
 MIAMI BEACH, FLORIDA  
 COUNTED BY: RALPH MARTINEZ  
 NOT SIGNALIZED


85 SE 4TH AVENUE, UNIT 109  
 DELRAY BEACH, FLORIDA  
 PHONE (561)272-3255

Site Code : 00170211  
 Start Date: 12/15/17  
 File I.D. : DADEPURD  
 Page : 1

## PEDESTRIANS &amp; BIKES

PURDY AVENUE				DADE BOULEVARD				DADE BOULEVARD								
From North				From East				From South				From West				
Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total
<b>Date 12/15/17 -----</b>																
16:30	0	8	0	5	0	0	0	0	5	0	4	0	1	0	6	29
16:45	0	17	0	7	0	0	0	0	2	0	4	0	1	0	11	42
17:00	0	8	0	4	0	1	0	0	2	0	1	0	1	0	5	22
17:15	0	5	0	8	0	0	0	1	0	0	0	0	2	0	16	32
Hr Total	0	38	0	24	0	1	0	1	9	0	9	0	5	0	38	125
17:30	0	12	0	5	0	2	0	0	6	0	3	0	6	0	7	41
17:45	0	9	0	4	0	0	0	0	1	0	5	0	1	0	13	33
18:00	0	9	0	3	0	0	0	1	0	0	0	0	0	0	6	19
18:15	0	1	0	2	0	0	0	0	2	0	0	0	1	0	7	13
Hr Total	0	31	0	14	0	2	0	1	9	0	8	0	8	0	33	106
18:30	0	8	0	3	0	1	0	1	1	0	0	0	0	0	12	26
18:45	0	2	0	9	0	0	0	0	3	0	1	0	1	0	5	21
Hr Total	0	10	0	12	0	1	0	1	4	0	1	0	1	0	17	47
<b>*TOTAL*</b>																
	0	79	0	50	0	4	0	3	22	0	18	0	14	0	88	278

1 North



Miami Beach, Florida

December 15, 2017

drawn by Luis Fabriano  
NOT signalized

TRAFFIC SURVEY SPECIALISTS, INC.

**DADE BOULEVARD & BAY ROAD**

85 SE 4TH AVENUE, UNIT 109

Site Code : 00170211

MIAMI BEACH, FLORIDA

**DELRAY BEACH, FLORIDA**

Start Date: 12/15/17

COUNTED BY: SEBASTIAN SALVO

PHONE (561) 272-3255

File I.D. : DADE BAY

SIGNALIZED WITH STOP

Page : 1

ALL VEHICLES

BAY ROAD				DADE BOULEVARD				17TH STREET				DADE BOULEVARD				
From North				From East				From South				From West				
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
Date 12/15/17	-----															
16:30	0	0	0	7	0	0	59	2	0	86	0	1	0	0	42	71   268
16:45	0	0	0	5	0	0	52	4	0	103	0	2	0	0	41	83   290
17:00	0	0	0	2	0	0	42	6	0	94	0	1	0	0	40	75   260
17:15	0	0	0	10	0	0	59	14	0	83	0	0	0	0	55	104   325
Hr Total	0	0	0	24	0	0	212	26	0	366	0	4	0	0	178	333   1143
17:30	0	0	2	7	0	0	46	5	0	89	0	0	0	0	41	49   239
17:45	0	0	2	9	0	0	54	2	0	75	0	0	0	0	43	80   265
18:00	0	0	0	12	0	0	27	7	0	68	0	0	1	0	42	75   232
18:15	0	0	0	11	0	0	39	4	0	59	0	1	0	0	44	74   232
Hr Total	0	0	4	39	0	0	166	18	0	291	0	1	1	0	170	278   968
18:30	0	0	7	17	0	0	39	9	0	69	0	1	0	0	27	61   230
18:45	0	0	3	6	0	0	53	6	0	99	0	1	0	0	44	81   293
Hr Total	0	0	10	23	0	0	92	15	0	168	0	2	0	0	71	142   523

## TRAFFIC SURVEY SPECIALISTS, INC.


DADE BOULEVARD & BAY ROAD  
MIAMI BEACH, FLORIDA  
COUNTED BY: SEBASTIAN SALVO  
SIGNALIZED WITH STOP

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561) 272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : DADE\_BAY  
Page : 2

## ALL VEHICLES

BAY ROAD		DADE BOULEVARD			17TH STREET			DADE BOULEVARD								
From North		From East			From South			From West								
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
Date 12/15/17 -----																
Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17																
Peak start 16:30																
Volume	0	0	0	24	0	0	212	26	0	366	0	4	0	0	178	333
Percent	0%	0%	0%	100%	0%	0%	89%	11%	0%	99%	0%	1%	0%	0%	35%	65%
Pk total	24				238				370				511			
Highest	17:15				17:15				16:45				17:15			
Volume	0	0	0	10	0	0	59	14	0	103	0	2	0	0	55	104
Hi total	10				73				105				159			
PHF	.60				.82				.88				.80			



## DADE BOULEVARD

366	212	24
212	602	
24		
-----		
0	0	

178	178	511
178	178	
333	333	
333		

0	0	
0		
0		
0		

## ALL VEHICLES

Intersection Total  
1,143

703

17TH STREET

238	212	26
238	212	26
420	0	
420	0	

0	0	0
0	0	0
182	178	4
182	178	4

## DADE BOULEVARD

370	0	4
370	0	4
0	4	0
0	4	0

0	0	
0		
0		
0		

## TRAFFIC SURVEY SPECIALISTS, INC.

DADE BOULEVARD & BAY ROAD  
MIAMI BEACH, FLORIDA  
COUNTED BY: SEBASTIAN SALVO  
SIGNALIZED WITH STOP


85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : DADE\_BAY  
Page : 1

## PEDESTRIANS &amp; BIKES

BAY ROAD				DADE BOULEVARD				17TH STREET				DADE BOULEVARD					
From North				From East				From South				From West					
	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total
<b>Date 12/15/17</b>																	
16:30	0	5	0	3	0	1	0	1	0	0	0	0	0	0	0	0	10
16:45	0	1	0	6	0	1	0	6	0	0	0	0	0	0	0	0	14
17:00	0	4	0	3	0	0	0	3	0	1	0	0	0	0	0	0	11
17:15	0	4	0	5	0	2	0	0	0	0	0	0	0	0	0	0	11
Hr Total	0	14	0	17	0	4	0	10	0	1	0	0	0	0	0	0	46
17:30	0	5	0	0	0	1	0	2	0	0	0	0	0	0	0	0	8
17:45	0	2	0	6	0	3	0	6	0	1	0	0	0	1	0	0	19
18:00	0	5	0	0	0	0	0	0	0	0	0	0	0	0	0	0	5
18:15	0	0	0	3	0	1	0	6	0	2	0	0	0	0	0	0	12
Hr Total	0	12	0	9	0	5	0	14	0	3	0	0	0	1	0	0	44
18:30	0	6	0	2	0	0	0	3	0	0	0	0	0	0	0	0	11
18:45	0	1	0	0	0	0	0	5	0	0	0	0	0	0	0	0	6
Hr Total	0	7	0	2	0	0	0	8	0	0	0	0	0	0	0	0	17
<b>*TOTAL*</b>																	
	0	33	0	28	0	9	0	32	0	4	0	0	0	1	0	0	107

↑ North



Miami Beach, Florida

December 15, 2017

drawn by: Luis Palomino

signalized w/ stop

## TRAFFIC SURVEY SPECIALISTS, INC.

DADE BOULEVARD & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: GERMAIN CAMPUSANO  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : DADEWEST  
Page : 1

## ALL VEHICLES

WEST AVENUE				DADE BOULEVARD				WEST AVENUE				DADE BOULEVARD				
From North		From East		From South		From West										
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
<b>Date 12/15/17</b>																
16:30	1	14	24	7	0	16	54	35	0	2	39	25	0	3	38	0   258
16:45	0	20	24	7	0	15	40	22	0	3	24	23	0	2	34	0   214
17:00	0	20	31	6	0	21	43	39	0	1	37	23	0	1	39	0   261
17:15	0	14	25	6	0	24	56	26	0	2	28	19	0	3	48	0   251
Hr Total	1	68	104	26	0	76	193	122	0	8	128	90	0	9	159	0   984
17:30	0	18	23	1	0	18	45	34	0	2	23	11	0	5	34	0   214
17:45	0	15	29	4	0	29	51	30	0	1	29	16	0	1	41	0   246
18:00	0	13	37	7	0	16	27	31	0	1	37	22	0	0	44	0   235
18:15	0	18	25	4	0	22	36	28	0	1	22	17	0	4	38	2   217
Hr Total	0	64	114	16	0	85	159	123	0	5	111	66	0	10	157	2   912
18:30	0	15	32	5	0	17	39	23	0	4	33	23	0	0	26	1   218
18:45	0	11	23	2	0	15	54	25	0	4	32	24	0	6	37	1   234
Hr Total	0	26	55	7	0	32	93	48	0	8	65	47	0	6	63	2   452
<b>*TOTAL*</b>	1	158	273	49	0	193	445	293	0	21	304	203	0	25	379	4   2348

## TRAFFIC SURVEY SPECIALISTS, INC.


DADE BOULEVARD & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: GERMAIN CAMPUSANO  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255



Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : DADEWEST  
Page : 2

## ALL VEHICLES

WEST AVENUE				DADE BOULEVARD				WEST AVENUE				DADE BOULEVARD				
From North				From East				From South				From West				
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
<b>Date 12/15/17</b>																
<b>Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17</b>																
Peak start 16:30				16:30				16:30				16:30				
Volume	1	68	104	26	0	76	193	122	0	8	128	90	0	9	159	0
Percent	1%	34%	52%	13%	0%	19%	49%	31%	0%	4%	57%	40%	0%	5%	95%	0%
Pk total	199				391				226				168			
Highest	17:00				17:15				16:30				17:15			
Volume	0	20	31	6	0	24	56	26	0	2	39	25	0	3	48	0
Hi total	57				106				66				51			
PHF	.87				.92				.86				.82			



## DADE BOULEVARD



## WEST AVENUE

## TRAFFIC SURVEY SPECIALISTS, INC.

DADE BOULEVARD & WEST AVENUE  
 MIAMI BEACH, FLORIDA  
 COUNTED BY: GERMAIN CAMPUSANO  
 NOT SIGNALIZED


85 SE 4TH AVENUE, UNIT 109  
 DELRAY BEACH, FLORIDA  
 PHONE (561)272-3255

Site Code : 00170211  
 Start Date: 12/15/17  
 File I.D. : DADEWEST  
 Page : 1

## PEDESTRIANS &amp; BIKES

WEST AVENUE				DADE BOULEVARD				WEST AVENUE				DADE BOULEVARD				
From North				From East				From South				From West				
Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total
<b>Date 12/15/17</b>																
16:30	0	3	0	3	0	4	0	6	0	0	0	0	3	0	5	24
16:45	0	0	0	2	0	1	0	8	0	0	0	1	0	1	5	18
17:00	0	0	0	1	0	1	0	1	0	1	0	1	0	0	3	8
17:15	0	0	0	0	0	2	0	6	0	0	0	0	0	0	5	13
Hr Total	0	3	0	6	0	8	0	21	0	1	0	2	0	4	0	63
17:30	0	2	0	0	0	3	0	3	0	0	0	0	1	0	2	11
17:45	0	1	0	1	0	0	0	4	0	0	0	1	0	0	0	7
18:00	0	0	0	3	0	2	0	11	0	2	0	0	0	2	0	29
18:15	0	1	0	0	0	2	0	10	0	1	0	0	0	3	0	23
Hr Total	0	4	0	4	0	7	0	28	0	3	0	1	0	6	0	70
18:30	0	0	0	0	0	4	0	3	0	0	0	2	0	5	0	13
18:45	0	0	0	2	0	2	0	10	0	0	0	0	0	3	0	26
Hr Total	0	0	0	2	0	6	0	13	0	0	0	2	0	8	0	53
<b>*TOTAL*</b>	0	7	0	12	0	21	0	62	0	4	0	5	0	18	0	186

↑  
North



Miami Beach, Florida

December 15, 2017

Drawn by: Luis Palomino  
NOT signalized

## TRAFFIC SURVEY SPECIALISTS, INC.

17TH STREET &amp; WEST AVENUE

MIAMI BEACH, FLORIDA

COUNTED BY: MICHAEL MALONE

SIGNALIZED

85 SE 4TH AVENUE, UNIT 109

DELRAY BEACH, FLORIDA

PHONE (561)272-3255

Site Code : 00170211

Start Date: 12/15/17

File I.D. : 17STWEST

Page : 1

## ALL VEHICLES

WEST AVENUE				17TH STREET				WEST AVENUE				17TH STREET					
From North				From East				From South				From West					
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total	
<b>Date 12/15/17</b>																	
16:30	0	3	40	1	0	27	46	14	0	38	57	30	0	0	34	37	327
16:45	0	4	32	0	0	31	51	3	0	41	51	41	0	0	41	46	341
17:00	0	5	45	0	0	28	64	6	0	30	59	41	0	1	36	41	356
<u>17:15</u>	<u>0</u>	<u>3</u>	<u>49</u>	<u>0</u>	<u>0</u>	<u>34</u>	<u>47</u>	<u>12</u>	<u>1</u>	<u>32</u>	<u>46</u>	<u>29</u>	<u>0</u>	<u>0</u>	<u>49</u>	<u>49</u>	<u>351</u>
Hr Total	0	15	166	1	0	120	208	35	1	141	213	141	0	1	160	173	1375
17:30	0	3	35	0	0	35	52	3	0	32	42	33	0	0	14	34	283
17:45	0	2	50	1	0	38	43	6	0	26	48	38	0	0	42	42	336
18:00	0	7	45	0	0	36	37	7	0	34	55	26	0	0	38	40	325
<u>18:15</u>	<u>0</u>	<u>6</u>	<u>43</u>	<u>1</u>	<u>0</u>	<u>24</u>	<u>33</u>	<u>12</u>	<u>0</u>	<u>23</u>	<u>38</u>	<u>31</u>	<u>0</u>	<u>0</u>	<u>37</u>	<u>41</u>	<u>289</u>
Hr Total	0	18	173	2	0	133	165	28	0	115	183	128	0	0	131	157	1233
18:30	0	2	49	0	0	32	43	7	0	34	48	32	0	0	32	34	313
<u>18:45</u>	<u>0</u>	<u>7</u>	<u>37</u>	<u>0</u>	<u>0</u>	<u>27</u>	<u>33</u>	<u>5</u>	<u>1</u>	<u>46</u>	<u>57</u>	<u>32</u>	<u>1</u>	<u>0</u>	<u>44</u>	<u>44</u>	<u>334</u>
Hr Total	0	9	86	0	0	59	76	12	1	80	105	64	1	0	76	78	647
<b>*TOTAL*</b>																	
	0	42	425	3	0	312	449	75	2	336	501	333	1	1	367	408	3255

## TRAFFIC SURVEY SPECIALISTS, INC.


17TH STREET & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: MICHAEL MALONE  
SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255


Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 17STWEST  
Page : 2

## ALL VEHICLES

WEST AVENUE				17TH STREET				WEST AVENUE				17TH STREET				
From North				From East				From South				From West				
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
Date 12/15/17 -----																
Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17																
Peak start 16:30				16:30				16:30				16:30				
Volume	0	15	166	1	0	120	208	35	1	141	213	141	0	1	160	173
Percent	0%	8%	91%	1%	0%	33%	57%	10%	0%	28%	43%	28%	0%	0%	48%	52%
Pk total	182				363				496				334			
Highest	17:15				17:00				16:45				17:15			
Volume	0	3	49	0	0	28	64	6	0	41	51	41	0	0	49	49
Hi total	52				98				133				98			
PHF	.88				.93				.93				.85			



## 17TH STREET



## TRAFFIC SURVEY SPECIALISTS, INC.

17TH STREET & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: MICHAEL MALONE  
SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255


Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 17STWEST  
Page : 1

## PEDESTRIANS &amp; BIKES

WEST AVENUE				17TH STREET				WEST AVENUE				17TH STREET				
From North				From East				From South				From West				
Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total
<b>Date 12/15/17</b>																
16:30	0	1	0	16	0	5	0	6	0	4	0	7	0	2	0	7   48
16:45	0	10	0	16	0	6	0	15	0	5	0	16	0	8	0	7   83
17:00	0	4	0	6	0	6	0	6	0	0	0	15	0	2	0	6   45
<u>17:15</u>	<u>0</u>	<u>4</u>	<u>0</u>	<u>9</u>	<u>0</u>	<u>11</u>	<u>0</u>	<u>10</u>	<u>0</u>	<u>3</u>	<u>0</u>	<u>8</u>	<u>0</u>	<u>4</u>	<u>0</u>	<u>15   64</u>
Hr Total	0	19	0	47	0	28	0	37	0	12	0	46	0	16	0	35   240
17:30	0	12	0	9	0	12	0	18	0	3	0	8	0	6	0	9   77
17:45	0	3	0	2	0	10	0	23	0	3	0	18	0	4	0	4   67
18:00	0	6	0	13	0	9	0	23	0	0	0	16	0	2	0	7   76
<u>18:15</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>5</u>	<u>0</u>	<u>3</u>	<u>0</u>	<u>12</u>	<u>0</u>	<u>3</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>4</u>	<u>0</u>	<u>5   34</u>
Hr Total	0	22	0	29	0	34	0	76	0	9	0	43	0	16	0	25   254
18:30	0	9	0	13	0	5	0	11	0	1	0	11	0	4	0	8   62
<u>18:45</u>	<u>0</u>	<u>4</u>	<u>0</u>	<u>16</u>	<u>0</u>	<u>4</u>	<u>0</u>	<u>8</u>	<u>0</u>	<u>3</u>	<u>0</u>	<u>5</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>10   51</u>
Hr Total	0	13	0	29	0	9	0	19	0	4	0	16	0	5	0	18   113
<b>*TOTAL*</b>	0	54	0	105	0	71	0	132	0	25	0	105	0	37	0	78   607

↑  
North

NEW BRIDGE



Miami Beach, Florida

December 15, 2017

drawn by: Miss Pabmino  
Signaled

## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: WILLIAN DE LUNA VARGAS  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561) 272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 18STWEST  
Page : 1

## ALL VEHICLES

WEST AVENUE				18TH STREET				WEST AVENUE				18TH STREET					
From North				From East				From South				From West					
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total	
<b>Date 12/15/17</b>																	
16:30	0	3	17	13	0	3	2	7	0	18	47	7	0	20	3	20	160
16:45	1	3	22	9	0	2	5	4	0	19	32	2	0	16	3	24	142
17:00	1	1	17	15	0	1	2	3	1	24	41	2	0	14	6	28	156
<u>17:15</u>	<u>0</u>	<u>4</u>	<u>20</u>	<u>23</u>	<u>0</u>	<u>1</u>	<u>7</u>	<u>4</u>	<u>0</u>	<u>26</u>	<u>38</u>	<u>2</u>	<u>0</u>	<u>18</u>	<u>4</u>	<u>22</u>	<u>169</u>
Hr Total	2	11	76	60	0	7	16	18	1	87	158	13	0	68	16	94	627
17:30	0	1	20	11	0	1	2	2	0	26	35	3	0	13	2	25	141
17:45	1	3	21	28	0	2	1	2	0	19	37	6	0	22	2	26	170
18:00	0	4	20	15	0	2	1	4	0	22	45	5	0	14	6	21	159
<u>18:15</u>	<u>0</u>	<u>1</u>	<u>19</u>	<u>23</u>	<u>0</u>	<u>3</u>	<u>2</u>	<u>1</u>	<u>0</u>	<u>24</u>	<u>32</u>	<u>2</u>	<u>1</u>	<u>15</u>	<u>7</u>	<u>26</u>	<u>156</u>
Hr Total	1	9	80	77	0	8	6	9	0	91	149	16	1	64	17	98	626
18:30	0	0	13	12	0	2	0	6	0	22	38	0	1	11	4	33	142
<u>18:45</u>	<u>0</u>	<u>1</u>	<u>15</u>	<u>12</u>	<u>0</u>	<u>2</u>	<u>1</u>	<u>2</u>	<u>0</u>	<u>30</u>	<u>30</u>	<u>1</u>	<u>0</u>	<u>20</u>	<u>5</u>	<u>21</u>	<u>140</u>
Hr Total	0	1	28	24	0	4	1	8	0	52	68	1	1	31	9	54	282
<b>*TOTAL*</b>	<b>3</b>	<b>21</b>	<b>184</b>	<b>161</b>	<b>0</b>	<b>19</b>	<b>23</b>	<b>35</b>	<b>1</b>	<b>230</b>	<b>375</b>	<b>30</b>	<b>2</b>	<b>163</b>	<b>42</b>	<b>246</b>	<b>1535</b>

## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: WILLIAN DE LUNA VARGAS  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255


Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 18STWEST  
Page : 2

## ALL VEHICLES


WEST AVENUE		18TH STREET		WEST AVENUE		18TH STREET										
From North		From East		From South		From West										
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
Date 12/15/17																

Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17

Peak start 17:15				17:15				17:15				17:15				
Volume	1	12	81	77	0	6	11	12	0	93	155	16	0	67	14	94
Percent	1%	7%	47%	45%	0%	21%	38%	41%	0%	35%	59%	6%	0%	38%	8%	54%
Pk total	171				29				264				175			
Highest	17:45				17:15				18:00				17:45			
Volume	1	3	21	28	0	1	7	4	0	22	45	5	0	22	2	26
Hi total	53				12				72				50			
PHF	.81				.60				.92				.88			



## 18TH STREET



## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET &amp; WEST AVENUE

MIAMI BEACH, FLORIDA

COUNTED BY: WILLIAN DE LUNA VARGAS

NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109

DELRAY BEACH, FLORIDA

PHONE (561) 272-3255

Site Code : 00170211

Start Date: 12/15/17


File I.D. : 18STWEST

Page : 1

## PEDESTRIANS &amp; BIKES

WEST AVENUE				18TH STREET				WEST AVENUE				18TH STREET							
From North				From East				From South				From West							
	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total		
Date 12/15/17																			
16:30	0	0	0	13	0	0	0	4	0	0	0	6	0	0	0	8	31		
16:45	0	0	0	14	0	0	0	3	0	0	0	3	0	1	0	7	28		
17:00	0	0	0	8	0	1	0	5	0	1	0	1	0	0	0	7	23		
<u>17:15</u>	0	0	0	11	0	0	0	7	0	0	0	12	0	0	0	4	34		
Hr Total	0	0	0	46	0	1	0	19	0	1	0	22	0	1	0	26	116		
17:30	0	2	0	7	0	0	0	6	0	0	0	3	0	2	0	7	27		
17:45	0	0	0	8	0	0	0	18	0	0	0	3	0	0	0	9	38		
18:00	0	0	0	4	0	0	0	10	0	0	0	3	0	0	0	12	29		
<u>18:15</u>	0	0	0	4	0	1	0	5	0	0	0	10	0	1	0	10	31		
Hr Total	0	2	0	23	0	1	0	39	0	0	0	19	0	3	0	38	125		
18:30	0	1	0	11	0	1	0	0	0	0	0	2	0	0	0	10	25		
<u>18:45</u>	0	0	0	4	0	0	0	2	0	0	0	0	0	0	0	13	19		
Hr Total	0	1	0	15	0	1	0	2	0	0	0	2	0	0	0	23	44		
<b>*TOTAL*</b>	0	3	0	84	0	3	0	60	0	1	0	43	0	4	0	87	285		

↑ North



Miami Beach, Florida

December 15, 2017

drawn by: Luis Palomino  
NOT SIGNALIZED

## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET &amp; BAY ROAD

MIAMI BEACH, FLORIDA

COUNTED BY: ROLANDO MARTINEZ

NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109

DELRAY BEACH, FLORIDA

PHONE (561)272-3255

Site Code : 00170211

Start Date: 12/15/17

File I.D. : 18ST\_BAY

Page : 1

## ALL VEHICLES

BAY ROAD				18TH STREET				BAY ROAD				18TH STREET							
From North				From East				From South				From West							
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Total		
Date 12/15/17																			
16:30	0	22	5	14	0	2	26	10	0	1	3	4	0	6	18	0	111		
16:45	0	18	4	11	0	2	18	10	0	5	3	6	1	7	18	2	105		
17:00	0	27	5	14	0	3	22	17	0	2	5	5	0	11	20	0	131		
17:15	0	20	6	7	0	10	26	17	0	5	8	6	0	14	17	4	140		
Hr Total	0	87	20	46	0	17	92	54	0	13	19	21	1	38	73	6	487		
17:30	1	16	4	12	0	6	17	21	0	1	2	7	0	11	17	4	119		
17:45	0	16	8	11	0	5	29	13	0	0	4	6	0	6	24	7	129		
18:00	0	13	10	9	0	0	24	11	0	1	4	11	1	11	18	3	116		
18:15	0	21	9	10	0	2	22	21	0	1	2	5	1	11	14	4	123		
Hr Total	1	66	31	42	0	13	92	66	0	3	12	29	2	39	73	18	487		
18:30	0	21	11	12	1	6	18	11	0	0	8	8	0	12	19	8	135		
18:45	0	16	8	13	2	5	19	15	1	1	4	6	0	11	21	2	124		
Hr Total	0	37	19	25	3	11	37	26	1	1	12	14	0	23	40	10	259		
*TOTAL*	1	190	70	113	3	41	221	146	1	17	43	64	3	100	186	34	1233		

## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET &amp; BAY ROAD

MIAMI BEACH, FLORIDA

COUNTED BY: ROLANDO MARTINEZ

NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109

DELRAY BEACH, FLORIDA

PHONE (561)272-3255

Site Code : 00170211


Start Date: 12/15/17

File I.D. : 18ST\_BAY


Page : 2

## ALL VEHICLES

BAY ROAD				18TH STREET				BAY ROAD				18TH STREET				
From North				From East				From South				From West				
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
<b>Date 12/15/17</b>																
<b>Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17</b>																
Peak start 17:00				17:00				17:00				17:00				
Volume	1	79	23	44	0	24	94	68	0	8	19	24	0	42	78	15
Percent	1%	54%	16%	30%	0%	13%	51%	37%	0%	16%	37%	47%	0%	31%	58%	11%
Pk total	147				186				51				135			
Highest	17:00				17:15				17:15				17:45			
Volume	0	27	5	14	0	10	26	17	0	5	8	6	0	6	24	7
Hi total	46				53				19				37			
PHF	.80				.88				.67				.91			



## 18TH STREET



## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET &amp; BAY ROAD

MIAMI BEACH, FLORIDA

COUNTED BY: ROLANDO MARTINEZ

NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109

DELRAY BEACH, FLORIDA

PHONE (561)272-3255

Site Code : 00170211

Start Date: 12/15/17


File I.D. : 18ST\_BAY

Page : 1

## PEDESTRIANS &amp; BIKES

BAY ROAD				18TH STREET				BAY ROAD				18TH STREET								
From North				From East				From South				From West								
Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total
Date 12/15/17																				
16:30	0	6	0	15		0	1	0	4		0	1	0	6		0	3	0	2	38
16:45	0	3	0	15		0	4	0	5		0	0	0	4		0	2	0	9	42
17:00	0	0	0	18		0	0	0	1		0	3	0	4		0	1	0	5	32
<u>17:15</u>	<u>0</u>	<u>5</u>	<u>0</u>	<u>11</u>	<u> </u>	<u>0</u>	<u>2</u>	<u>0</u>	<u>2</u>	<u> </u>	<u>0</u>	<u>3</u>	<u>0</u>	<u>11</u>	<u> </u>	<u>0</u>	<u>7</u>	<u>0</u>	<u>3</u>	<u>44</u>
Hr Total	0	14	0	59		0	7	0	12		0	7	0	25		0	13	0	19	156
17:30	0	6	0	5		0	0	0	0		0	6	0	10		0	3	0	5	35
17:45	0	3	0	17		0	1	0	2		0	1	0	0		0	2	0	10	36
18:00	0	4	0	8		0	1	0	2		0	5	0	6		0	0	0	8	34
<u>18:15</u>	<u>0</u>	<u>3</u>	<u>0</u>	<u>10</u>	<u> </u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>5</u>	<u> </u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>3</u>	<u> </u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>6</u>	<u>28</u>
Hr Total	0	16	0	40		0	3	0	9		0	12	0	19		0	5	0	29	133
18:30	0	1	0	17		0	3	0	9		0	2	0	5		0	2	0	4	43
<u>18:45</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>20</u>	<u> </u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>9</u>	<u> </u>	<u>0</u>	<u>3</u>	<u>0</u>	<u>9</u>	<u> </u>	<u>0</u>	<u>2</u>	<u>0</u>	<u>13</u>	<u>57</u>
Hr Total	0	2	0	37		0	3	0	18		0	5	0	14		0	4	0	17	100
*TOTAL*	0	32	0	136		0	13	0	39		0	24	0	58		0	22	0	65	389

↑ North



Miami Beach, Florida

December 15, 2017

drawn by: Luis Falconino  
NOT SIGNALIZED

## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET & PURDY AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: MARISA CRUZ  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 18STPURD  
Page : 1

## ALL VEHICLES

PURDY AVENUE				18TH STREET				PURDY AVENUE				DRIVEWAY					
From North				From East				From South				From West					
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total	
<b>Date 12/15/17</b>																	
16:30	0	2	22	0	0	20	2	11	0	1	19	16	0	2	0	11	106
16:45	0	3	30	1	0	17	1	12	1	4	23	23	1	2	0	7	125
17:00	0	4	37	3	0	19	0	18	0	2	18	17	0	3	6	2	129
<u>17:15</u>	<u>0</u>	<u>7</u>	<u>34</u>	<u>1</u>	<u>1</u>	<u>20</u>	<u>2</u>	<u>15</u>	<u>0</u>	<u>4</u>	<u>25</u>	<u>25</u>	<u>0</u>	<u>3</u>	<u>4</u>	<u>3</u>	<u>144</u>
Hr Total	0	16	123	5	1	76	5	56	1	11	85	81	1	10	10	23	504
17:30	0	3	31	1	0	17	2	9	1	3	19	23	0	3	5	2	119
17:45	0	7	35	2	0	27	3	8	0	1	32	28	0	6	3	12	164
18:00	0	5	21	0	0	24	1	9	0	4	29	23	0	0	5	10	131
<u>18:15</u>	<u>0</u>	<u>10</u>	<u>25</u>	<u>3</u>	<u>0</u>	<u>15</u>	<u>0</u>	<u>15</u>	<u>2</u>	<u>2</u>	<u>23</u>	<u>21</u>	<u>0</u>	<u>5</u>	<u>3</u>	<u>10</u>	<u>134</u>
Hr Total	0	25	112	6	0	83	6	41	3	10	103	95	0	14	16	34	548
18:30	0	9	20	1	2	20	1	12	1	0	13	22	0	4	8	3	116
<u>18:45</u>	<u>0</u>	<u>4</u>	<u>28</u>	<u>0</u>	<u>0</u>	<u>18</u>	<u>1</u>	<u>9</u>	<u>3</u>	<u>4</u>	<u>20</u>	<u>24</u>	<u>0</u>	<u>1</u>	<u>2</u>	<u>5</u>	<u>119</u>
Hr Total	0	13	48	1	2	38	2	21	4	4	33	46	0	5	10	8	235
<b>*TOTAL*</b>	0	54	283	12	3	197	13	118	8	25	221	222	1	29	36	65	1287

## TRAFFIC SURVEY SPECIALISTS, INC.


18TH STREET & PURDY AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: MARISA CRUZ  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255


Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 18STPURD  
Page : 2

## ALL VEHICLES

PURDY AVENUE				18TH STREET				PURDY AVENUE				DRIVEWAY				
From North				From East				From South				From West				
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
Date 12/15/17 -----																
Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17																
Peak start 17:15				17:15				17:15				17:15				
Volume	0	22	121	4	1	88	8	41	1	12	105	99	0	12	17	27
Percent	0%	15%	82%	3%	1%	64%	6%	30%	0%	6%	48%	46%	0%	21%	30%	48%
Pk total	147				138				217				56			
Highest	17:45				17:15				17:45				17:45			
Volume	0	7	35	2	1	20	2	15	0	1	32	28	0	6	3	12
Hi total	44				38				61				21			
PHF	.84				.91				.89				.67			



## DRIVEWAY



## TRAFFIC SURVEY SPECIALISTS, INC.

18TH STREET & PURDY AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: MARISA CRUZ  
NOT SIGNALIZED


85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 18STPURD  
Page : 1

## PEDESTRIANS &amp; BIKES

PURDY AVENUE				18TH STREET				PURDY AVENUE				DRIVEWAY				
From North				From East				From South				From West				
Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total
<b>Date 12/15/17</b>																
16:30	0	2	0	17	0	1	0	12	0	0	0	2	0	2	0	42
16:45	0	2	0	13	0	1	0	3	0	2	0	7	0	1	0	44
17:00	0	2	0	7	0	2	0	7	0	0	0	5	0	1	0	29
<u>17:15</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>9</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>6</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>2</u>	<u>0</u>	<u>2</u>	<u>0</u>	<u>26</u>
Hr Total	0	7	0	46	0	4	0	28	0	2	0	16	0	6	0	141
17:30	0	1	0	10	0	1	0	2	0	0	0	9	0	1	0	32
17:45	0	2	0	1	0	0	0	4	0	0	0	6	0	0	0	13
18:00	0	2	0	7	0	0	0	8	0	2	0	5	0	4	0	28
<u>18:15</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>2</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>9</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>2</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>16</u>
Hr Total	0	5	0	20	0	2	0	23	0	2	0	22	0	5	0	89
18:30	0	0	0	18	0	0	0	9	0	0	0	2	0	0	0	30
<u>18:45</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>23</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>15</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>6</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>56</u>
Hr Total	0	0	0	41	0	0	0	24	0	0	0	8	0	1	0	86
<b>*TOTAL*</b>	0	12	0	107	0	6	0	75	0	4	0	46	0	12	0	316

North



Miami Beach, Florida

December 15, 2017

Taunby: his Palomino  
not signalized

## TRAFFIC SURVEY SPECIALISTS, INC.

20TH STREET & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: RICH MENDEZ  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561)272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 20STWEST  
Page : 1

## ALL VEHICLES

DRIVEWAY		20TH STREET				WEST AVENUE				20TH STREET							
From North		From East		From South		From West											
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total	
<u>Date 12/15/17</u>																	
16:30	0	0	1	0	0	39	31	0	0	11	0	48	1	0	58	12	201
16:45	0	0	0	0	0	31	38	1	0	7	0	38	0	0	54	14	183
17:00	0	0	0	0	0	39	52	0	0	9	1	32	0	0	63	8	204
<u>17:15</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>2</u>	<u>0</u>	<u>32</u>	<u>55</u>	<u>0</u>	<u>0</u>	<u>6</u>	<u>0</u>	<u>41</u>	<u>0</u>	<u>0</u>	<u>44</u>	<u>20</u>	<u>200</u>
Hr Total	0	0	1	2	0	141	176	1	0	33	1	159	1	0	219	54	788
17:30	0	0	1	0	0	33	56	0	0	9	0	32	0	2	76	9	218
17:45	0	0	0	2	0	33	49	0	2	2	2	29	0	1	48	10	178
18:00	0	0	1	0	0	27	49	0	0	9	1	31	0	1	49	10	178
<u>18:15</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>0</u>	<u>29</u>	<u>38</u>	<u>0</u>	<u>0</u>	<u>4</u>	<u>0</u>	<u>25</u>	<u>1</u>	<u>1</u>	<u>54</u>	<u>12</u>	<u>164</u>
Hr Total	0	0	2	2	0	122	192	0	2	24	3	117	1	5	227	41	738
18:30	0	0	0	0	0	21	50	1	0	9	0	35	0	0	54	7	177
<u>18:45</u>	<u>0</u>	<u>0</u>	<u>1</u>	<u>0</u>	<u>0</u>	<u>24</u>	<u>38</u>	<u>0</u>	<u>0</u>	<u>13</u>	<u>0</u>	<u>27</u>	<u>0</u>	<u>0</u>	<u>49</u>	<u>12</u>	<u>164</u>
Hr Total	0	0	1	0	0	45	88	1	0	22	0	62	0	0	103	19	341
<b>*TOTAL*</b>	0	0	4	4	0	308	456	2	2	79	4	338	2	5	549	114	1867

## TRAFFIC SURVEY SPECIALISTS, INC.


20TH STREET & WEST AVENUE  
MIAMI BEACH, FLORIDA  
COUNTED BY: RICH MENDEZ  
NOT SIGNALIZED

85 SE 4TH AVENUE, UNIT 109  
DELRAY BEACH, FLORIDA  
PHONE (561) 272-3255

Site Code : 00170211  
Start Date: 12/15/17  
File I.D. : 20STWEST  
Page : 2

## ALL VEHICLES

DRIVEWAY		20TH STREET				WEST AVENUE				20TH STREET						
From North		From East		From South		From West										
UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	UTurn	Left	Thru	Right	Total
<b>Date 12/15/17</b>																
<b>Peak Hour Analysis By Entire Intersection for the Period: 16:30 to 19:00 on 12/15/17</b>																
<b>Peak start 16:45</b>				<b>16:45</b>				<b>16:45</b>				<b>16:45</b>				
Volume	0	0	1	2	0	135	201	1	0	31	1	143	0	2	237	51
Percent	0%	0%	33%	67%	0%	40%	60%	0%	0%	18%	1%	82%	0%	1%	82%	18%
Pk total	3				337				175				290			
Highest	17:15				17:00				17:15				17:30			
Volume	0	0	0	2	0	39	52	0	0	6	0	41	0	2	76	9
Hi total	2				91				47				87			
PHF	.38				.93				.93				.83			



## 20TH STREET

31			
201	234		
2			
2			
237			
237	290		
237			
51			
51	51		
51			

## ALL VEHICLES

524			
717			
717			
805			
362			

## Intersection Total

20TH STREET	175		
135	31		
1			
51			
187	31		
187			
WEST AVENUE	31		
1			
143	143		
143			
0	0		

## TRAFFIC SURVEY SPECIALISTS, INC.

20TH STREET & WEST AVENUE  
 MIAMI BEACH, FLORIDA  
 COUNTED BY: RICH MENDEZ  
 NOT SIGNALIZED


85 SE 4TH AVENUE, UNIT 109  
 DELRAY BEACH, FLORIDA  
 PHONE (561) 272-3255

Site Code : 00170211  
 Start Date: 12/15/17  
 File I.D. : 20STWEST  
 Page : 1

## PEDESTRIANS &amp; BIKES

DRIVEWAY	20TH STREET				WEST AVENUE				20TH STREET								
	From North		From East		From South		From West										
	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Left	BIKES	Right	Peds	Total
<u>Date 12/15/17</u>																	
16:30	0	2	0	1	0	1	0	4	0	2	0	18	0	1	0	0	29
16:45	0	2	0	4	0	0	0	1	0	0	0	22	0	0	0	4	33
17:00	0	2	0	5	0	0	0	5	0	4	0	25	0	1	0	3	45
<u>17:15</u>	0	4	0	4	0	0	0	1	0	4	0	13	0	0	0	4	30
Hr Total	0	10	0	14	0	1	0	11	0	10	0	78	0	2	0	11	137
17:30	0	2	0	6	0	0	0	1	0	2	0	19	0	0	0	2	32
17:45	0	2	0	7	0	0	0	5	0	1	0	18	0	0	0	4	37
18:00	0	4	0	5	0	0	0	2	0	6	0	13	0	0	0	2	32
<u>18:15</u>	0	1	0	6	0	0	0	6	0	1	0	18	0	2	0	3	37
Hr Total	0	9	0	24	0	0	0	14	0	10	0	68	0	2	0	11	138
18:30	0	0	0	11	0	0	0	2	0	0	0	15	0	0	0	6	34
<u>18:45</u>	0	1	0	7	0	0	0	0	0	1	0	12	0	0	0	1	22
Hr Total	0	1	0	18	0	0	0	2	0	1	0	27	0	0	0	7	56
 *TOTAL*																	
	0	20	0	56	0	1	0	27	0	21	0	173	0	4	0	29	331

↑ North



Miami Beach, Florida

December 15, 2017

drawn by: Luis Palomino

not signalized

# Traf Tech Engineering, Inc.

File Name : Bay Rd & 20th Street  
 Site Code : 00000000  
 Start Date : 3/9/2018  
 Page No : 1

	Groups Printed- Auto - Heavy Vehicles																				
	Bay Rd Southbound					20th Street Westbound				Bay Rd Northbound				20th Street Eastbound							
Start Time	Right	Thru	Left	U-Turns	App. Total	Right	Thru	Left	U-Turns	App. Total	Right	Thru	Left	U-Turns	App. Total	Right	Thru	Left	U-Turns	App. Total	Int. Total
09:00 AM	0	0	0	0	0	0	36	25	0	61	27	0	1	0	28	2	34	0	0	36	125
09:15 AM	0	0	0	0	0	0	32	29	0	61	30	0	10	0	40	4	14	0	0	18	119
09:30 AM	0	0	0	0	0	0	31	18	0	49	32	0	4	0	36	3	18	0	0	21	106
09:45 AM	0	0	0	0	0	0	31	19	0	50	38	0	2	0	40	2	25	0	0	27	117
Total	0	0	0	0	0	0	130	91	0	221	127	0	17	0	144	11	91	0	0	102	467
10:00 AM	0	0	0	0	0	0	34	23	0	57	33	0	3	0	36	6	21	0	0	27	120
10:15 AM	0	0	0	0	0	0	39	34	0	73	45	0	4	0	49	9	20	0	0	29	151
10:30 AM	0	0	0	0	0	0	31	20	0	51	51	0	6	0	57	6	22	0	0	28	136
10:45 AM	0	0	0	0	0	0	20	8	0	28	0	0	0	0	0	4	31	0	0	35	63
Total	0	0	0	0	0	0	124	85	0	209	129	0	13	0	142	25	94	0	0	119	470
11:00 AM	0	0	0	0	0	0	22	19	0	41	36	0	4	0	40	11	22	0	0	33	114
11:15 AM	0	0	0	0	0	0	32	8	0	40	33	0	0	0	33	4	26	0	0	30	103
11:30 AM	0	0	0	0	0	0	28	26	0	54	54	0	1	0	55	9	21	0	0	30	139
11:45 AM	0	0	0	0	0	0	32	22	0	54	33	0	6	0	39	7	29	0	0	36	129
Total	0	0	0	0	0	0	114	75	0	189	156	0	11	0	167	31	98	0	0	129	485
12:00 PM	0	0	0	0	0	0	34	19	0	53	40	0	2	0	42	16	29	0	0	45	140
12:15 PM	0	0	0	0	0	0	38	16	0	54	45	0	4	0	49	6	29	0	1	36	139
12:30 PM	0	0	0	0	0	0	31	20	0	51	40	0	6	0	46	14	23	0	0	37	134
12:45 PM	0	0	0	0	0	0	27	13	0	40	41	0	8	0	49	10	28	0	0	38	127
Total	0	0	0	0	0	0	130	68	0	198	166	0	20	0	186	46	109	0	1	156	540
01:00 PM	0	0	0	0	0	0	42	19	0	61	48	0	8	0	56	7	24	0	0	31	148
01:15 PM	0	0	0	0	0	0	30	20	0	50	39	0	2	0	41	16	29	0	0	45	136
01:30 PM	0	0	0	0	0	0	30	15	0	45	45	0	9	0	54	3	31	0	0	34	133
01:45 PM	0	0	0	0	0	0	33	19	0	52	26	0	4	0	30	11	28	0	0	39	121
Total	0	0	0	0	0	0	135	73	0	208	158	0	23	0	181	37	112	0	0	149	538
02:00 PM	0	0	0	0	0	0	34	17	0	51	43	0	4	0	47	6	25	0	0	31	129
02:15 PM	0	0	0	0	0	0	30	20	0	50	42	0	7	0	49	10	33	0	0	43	142
02:30 PM	0	0	0	0	0	0	36	16	0	52	54	0	6	0	60	3	20	0	0	23	135
02:45 PM	0	0	0	0	0	0	28	14	0	42	35	0	3	0	38	5	17	0	1	23	103
Total	0	0	0	0	0	0	128	67	0	195	174	0	20	0	194	24	95	0	1	120	509
03:00 PM	0	0	0	0	0	0	36	14	0	50	54	0	4	0	58	4	26	0	0	30	138
03:15 PM	0	0	0	0	0	0	36	22	0	58	33	0	3	0	36	9	28	0	0	37	131
03:30 PM	0	0	0	0	0	0	40	18	0	58	42	0	6	0	48	3	37	0	0	40	146
03:45 PM	0	0	0	0	0	0	32	17	0	49	28	0	4	1	33	7	30	0	0	37	119
Total	0	0	0	0	0	0	144	71	0	215	157	0	17	1	175	23	121	0	0	144	534

# Traf Tech Engineering, Inc.

File Name : Bay Rd & 20th Street  
 Site Code : 00000000  
 Start Date : 3/9/2018  
 Page No : 2

## Groups Printed- Auto - Heavy Vehicles


	Bay Rd Southbound					20th Street Westbound					Bay Rd Northbound					20th Street Eastbound					
Start Time	Right	Thru	Left	U-Turns	App. Total	Right	Thru	Left	U-Turns	App. Total	Right	Thru	Left	U-Turns	App. Total	Right	Thru	Left	U-Turns	App. Total	Int. Total
04:00 PM	0	0	0	0	0	0	37	13	0	50	41	0	4	0	45	2	26	0	0	28	123
04:15 PM	0	0	0	0	0	0	52	16	0	68	33	0	5	0	38	4	30	0	0	34	140
04:30 PM	0	0	0	0	0	0	66	18	0	84	39	0	4	0	43	8	29	0	0	37	164
04:45 PM	0	0	0	0	0	0	49	11	0	60	32	0	4	0	36	2	27	0	0	29	125
Total	0	0	0	0	0	0	204	58	0	262	145	0	17	0	162	16	112	0	0	128	552
05:00 PM	0	0	0	0	0	0	30	8	0	38	32	0	1	0	33	2	17	0	0	19	90
05:15 PM	0	0	0	0	0	0	64	26	0	90	44	0	5	0	49	4	29	0	0	33	172
05:30 PM	0	0	0	0	0	0	57	12	0	69	38	0	7	0	45	4	21	0	0	25	139
05:45 PM	0	0	0	0	0	0	43	14	0	57	35	0	3	0	38	0	31	0	0	31	126
Total	0	0	0	0	0	0	194	60	0	254	149	0	16	0	165	10	98	0	0	108	527
06:00 PM	0	0	0	0	0	0	47	26	0	73	36	0	5	0	41	2	20	0	0	22	136
06:15 PM	0	0	0	0	0	0	39	15	0	54	27	0	5	0	32	4	29	0	0	33	119
06:30 PM	0	0	0	0	0	0	30	28	0	58	58	0	5	0	63	4	24	0	0	28	149
06:45 PM	0	0	0	0	0	0	34	17	0	51	41	0	1	0	42	13	24	0	0	37	130
Total	0	0	0	0	0	0	150	86	0	236	162	0	16	0	178	23	97	0	0	120	534
07:00 PM	0	0	0	0	0	0	28	23	0	51	37	0	5	0	42	10	24	0	0	34	127
07:15 PM	0	0	0	0	0	0	39	25	0	64	33	0	9	0	42	8	21	0	0	29	135
07:30 PM	0	0	0	0	0	0	28	29	0	57	32	0	8	0	40	8	16	0	9	33	130
07:45 PM	0	0	0	0	0	0	34	26	0	60	37	0	7	0	44	12	15	0	1	28	132
Total	0	0	0	0	0	0	129	103	0	232	139	0	29	0	168	38	76	0	10	124	524
08:00 PM	0	0	0	0	0	0	35	24	0	59	35	0	7	0	42	10	18	0	0	28	129
08:15 PM	0	0	0	0	0	0	37	28	0	65	32	0	5	0	37	8	20	0	0	28	130
08:30 PM	0	0	0	0	0	0	31	22	0	53	40	0	6	0	46	4	19	0	0	23	122
08:45 PM	0	0	0	0	0	0	36	25	0	61	38	0	8	0	46	5	20	0	0	25	132
Total	0	0	0	0	0	0	139	99	0	238	145	0	26	0	171	27	77	0	0	104	513
Grand Total	0	0	0	0	0	0	1721	936	0	2657	1807	0	225	1	2033	311	1180	0	12	1503	6193
Apprch %	0	0	0	0	0	0	64.8	35.2	0	88.9	0	11.1	0	20.7	78.5	0	0.8				
Total %	0	0	0	0	0	0	27.8	15.1	0	42.9	29.2	0	3.6	0	32.8	5	19.1	0	0.2	24.3	
Auto	0	0	0	0	0	0	1716	923	0	2639	1798	0	222	0	2020	306	1171	0	0	1477	6136
% Auto	0	0	0	0	0	0	99.7	98.6	0	99.3	99.5	0	98.7	0	99.4	98.4	99.2	0	0	98.3	99.1
Heavy Vehicles	0	0	0	0	0	0	5	13	0	18	9	0	3	1	13	5	9	0	12	26	57
% Heavy Vehicles	0	0	0	0	0	0	0.3	1.4	0	0.7	0.5	0	1.3	100	0.6	1.6	0.8	0	100	1.7	0.9

# Traf Tech Engineering, Inc.

File Name : Bay Rd & 20th Street  
Site Code : 00000000  
Start Date : 3/9/2018  
Page No : 3

# Traf Tech Engineering, Inc.

File Name : Bay Rd & 20th Street  
Site Code : 00000000  
Start Date : 3/9/2018  
Page No : 4



# Traf Tech Engineering, Inc.

File Name : Bay Rd & 20th Street  
 Site Code : 00000000  
 Start Date : 3/9/2018  
 Page No : 1

Groups Printed- Peds

	Bay Rd Southbound					20th Street Westbound					Bay Rd Northbound					20th Street Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
09:00 AM	0	0	0	0	0	0	0	0	1	1	0	0	0	17	17	0	0	0	3	3	21
09:15 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	17	17	0	0	0	3	3	20
09:30 AM	0	0	0	0	0	0	0	0	6	6	0	0	0	16	16	0	0	0	2	2	24
09:45 AM	0	0	0	0	0	0	0	0	3	3	0	0	0	18	18	0	0	0	1	1	22
Total	0	0	0	0	0	0	0	0	10	10	0	0	0	68	68	0	0	0	9	9	87
10:00 AM	0	0	0	0	0	0	0	0	1	1	0	0	0	15	15	0	0	0	0	0	16
10:15 AM	0	0	0	0	0	0	0	0	2	2	0	0	0	33	33	0	0	0	0	0	35
10:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	22	22	0	0	0	4	4	26
10:45 AM	0	0	0	0	0	0	0	0	1	1	0	0	0	0	0	0	0	0	0	0	1
Total	0	0	0	0	0	0	0	0	4	4	0	0	0	70	70	0	0	0	4	4	78
11:00 AM	0	0	0	0	0	0	0	0	4	4	0	0	0	16	16	0	0	0	0	0	20
11:15 AM	0	0	0	0	0	0	0	0	2	2	0	0	0	20	20	0	0	0	0	0	22
11:30 AM	0	0	0	0	0	0	0	0	0	0	0	0	0	19	19	0	0	0	2	2	21
11:45 AM	0	0	0	0	0	0	0	0	4	4	0	0	0	33	33	0	0	0	1	1	38
Total	0	0	0	0	0	0	0	0	10	10	0	0	0	88	88	0	0	0	3	3	101
12:00 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	34	34	0	0	0	1	1	36
12:15 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	34	34	0	0	0	2	2	38
12:30 PM	0	0	0	0	0	0	0	0	5	5	0	0	0	39	39	0	0	0	1	1	45
12:45 PM	0	0	0	0	0	0	0	0	6	6	0	0	0	23	23	0	0	0	1	1	30
Total	0	0	0	0	0	0	0	0	14	14	0	0	0	130	130	0	0	0	5	5	149
01:00 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	26	26	0	0	0	1	1	28
01:15 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	21	21	0	0	0	8	8	30
01:30 PM	0	0	0	0	0	0	0	0	3	3	0	0	0	27	27	0	0	0	4	4	34
01:45 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	25	25	0	0	0	0	0	27
Total	0	0	0	0	0	0	0	0	7	7	0	0	0	99	99	0	0	0	13	13	119
02:00 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	17	17	0	0	0	0	0	18
02:15 PM	0	0	0	0	0	0	0	0	4	4	0	0	0	13	13	0	0	0	2	2	19
02:30 PM	0	0	0	0	0	0	0	0	5	5	0	0	0	41	41	0	0	0	1	1	47
02:45 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	14	14	0	0	0	2	2	18
Total	0	0	0	0	0	0	0	0	12	12	0	0	0	85	85	0	0	0	5	5	102
03:00 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	14	14	0	0	0	1	1	17
03:15 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	14	14	0	0	0	0	0	15
03:30 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	18	18	0	0	0	2	2	22
03:45 PM	0	0	0	0	0	0	0	0	11	11	0	0	0	23	23	0	0	0	1	1	35
Total	0	0	0	0	0	0	0	0	16	16	0	0	0	69	69	0	0	0	4	4	89

# Traf Tech Engineering, Inc.

File Name : Bay Rd & 20th Street  
 Site Code : 00000000  
 Start Date : 3/9/2018  
 Page No : 2

Groups Printed- Peds

	Bay Rd Southbound					20th Street Westbound					Bay Rd Northbound					20th Street Eastbound					
Start Time	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Right	Thru	Left	Peds	App. Total	Int. Total
04:00 PM	0	0	0	0	0	0	0	0	3	3	1	0	0	16	17	0	0	0	1	1	21
04:15 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	13	13	0	0	0	1	1	16
04:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	18	18	0	0	0	0	0	18
04:45 PM	0	0	0	0	0	0	0	0	4	4	0	0	0	19	19	0	0	0	0	0	23
Total	0	0	0	0	0	0	0	0	9	9	1	0	0	66	67	0	0	0	2	2	78
05:00 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	16	16	0	0	0	0	0	17
05:15 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	21	21	0	0	0	0	0	23
05:30 PM	0	0	0	0	0	0	0	0	5	5	0	0	0	19	19	0	0	0	5	5	29
05:45 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	24	24	0	0	0	2	2	28
Total	0	0	0	0	0	0	0	0	10	10	0	0	0	80	80	0	0	0	7	7	97
06:00 PM	0	0	0	0	0	0	0	0	3	3	0	0	0	15	15	0	0	0	3	3	21
06:15 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	29	29	0	0	0	1	1	31
06:30 PM	0	0	0	0	0	0	0	0	0	0	0	0	0	28	28	0	0	0	8	8	36
06:45 PM	0	0	0	0	0	0	0	0	3	3	0	0	0	15	15	0	0	0	0	0	18
Total	0	0	0	0	0	0	0	0	7	7	0	0	0	87	87	0	0	0	12	12	106
07:00 PM	0	0	0	0	0	0	0	0	5	5	0	0	0	26	26	0	0	0	5	5	36
07:15 PM	0	0	0	0	0	0	0	0	6	6	0	0	0	15	15	0	0	0	0	0	21
07:30 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	22	22	0	0	0	1	1	25
07:45 PM	0	0	0	0	0	0	0	0	3	3	0	0	0	23	23	0	0	0	2	2	28
Total	0	0	0	0	0	0	0	0	16	16	0	0	0	86	86	0	0	0	8	8	110
08:00 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	26	26	0	0	0	3	3	31
08:15 PM	0	0	0	0	0	0	0	0	5	5	0	0	0	20	20	0	0	0	2	2	27
08:30 PM	0	0	0	0	0	0	0	0	2	2	0	0	0	21	21	0	0	0	2	2	25
08:45 PM	0	0	0	0	0	0	0	0	1	1	0	0	0	23	23	0	0	0	3	3	27
Total	0	0	0	0	0	0	0	0	10	10	0	0	0	90	90	0	0	0	10	10	110
Grand Total	0	0	0	0	0	0	0	0	125	125	1	0	0	1018	1019	0	0	0	82	82	1226
Apprch %	0	0	0	0	0	0	0	0	100	100	0.1	0	0	99.9	1019	0	0	0	100	100	
Total %	0	0	0	0	0	0	0	0	10.2	10.2	0.1	0	0	83	83.1	0	0	0	6.7	6.7	

# **APPENDIX D**

## **Peak Season Conversion Factors Historical Traffic Data and Committed Developments**

2016 PEAK SEASON FACTOR CATEGORY REPORT - REPORT TYPE: ALL  
 CATEGORY: 8700 MIAMI-DADE NORTH

MOCF: 0.98  
 PSCF

WEEK	DATES	SF	
=====			
1	01/01/2016 - 01/02/2016	1.02	1.04
2	01/03/2016 - 01/09/2016	1.03	1.05
3	01/10/2016 - 01/16/2016	1.04	1.06
4	01/17/2016 - 01/23/2016	1.03	1.05
5	01/24/2016 - 01/30/2016	1.02	1.04
6	01/31/2016 - 02/06/2016	1.00	1.02
7	02/07/2016 - 02/13/2016	0.99	1.01
* 8	02/14/2016 - 02/20/2016	0.97	0.99
* 9	02/21/2016 - 02/27/2016	0.97	0.99
*10	02/28/2016 - 03/05/2016	0.98	1.00
*11	03/06/2016 - 03/12/2016	0.98	1.00
*12	03/13/2016 - 03/19/2016	0.98	1.00
*13	03/20/2016 - 03/26/2016	0.98	1.00
*14	03/27/2016 - 04/02/2016	0.98	1.00
*15	04/03/2016 - 04/09/2016	0.98	1.00
*16	04/10/2016 - 04/16/2016	0.98	1.00
*17	04/17/2016 - 04/23/2016	0.98	1.00
*18	04/24/2016 - 04/30/2016	0.98	1.00
*19	05/01/2016 - 05/07/2016	0.98	1.00
*20	05/08/2016 - 05/14/2016	0.99	1.01
21	05/15/2016 - 05/21/2016	0.99	1.01
22	05/22/2016 - 05/28/2016	0.99	1.01
23	05/29/2016 - 06/04/2016	1.00	1.02
24	06/05/2016 - 06/11/2016	1.00	1.02
25	06/12/2016 - 06/18/2016	1.01	1.03
26	06/19/2016 - 06/25/2016	1.02	1.04
27	06/26/2016 - 07/02/2016	1.02	1.04
28	07/03/2016 - 07/09/2016	1.03	1.05
29	07/10/2016 - 07/16/2016	1.03	1.05
30	07/17/2016 - 07/23/2016	1.03	1.05
31	07/24/2016 - 07/30/2016	1.03	1.05
32	07/31/2016 - 08/06/2016	1.02	1.04
33	08/07/2016 - 08/13/2016	1.02	1.04
34	08/14/2016 - 08/20/2016	1.02	1.04
35	08/21/2016 - 08/27/2016	1.02	1.04
36	08/28/2016 - 09/03/2016	1.02	1.04
37	09/04/2016 - 09/10/2016	1.02	1.04
38	09/11/2016 - 09/17/2016	1.01	1.03
39	09/18/2016 - 09/24/2016	1.01	1.03
40	09/25/2016 - 10/01/2016	1.00	1.02
41	10/02/2016 - 10/08/2016	1.00	1.02
42	10/09/2016 - 10/15/2016	0.99	1.01
43	10/16/2016 - 10/22/2016	1.00	1.02
44	10/23/2016 - 10/29/2016	1.00	1.02
45	10/30/2016 - 11/05/2016	1.01	1.03
46	11/06/2016 - 11/12/2016	1.01	1.03
47	11/13/2016 - 11/19/2016	1.02	1.04
48	11/20/2016 - 11/26/2016	1.02	1.04
49	11/27/2016 - 12/03/2016	1.02	1.04
50	12/04/2016 - 12/10/2016	1.02	1.04
51	12/11/2016 - 12/17/2016	1.02	1.04
52	12/18/2016 - 12/24/2016	1.03	1.05
53	12/25/2016 - 12/31/2016	1.04	1.06

\* PEAK SEASON

21-FEB-2017 10:54:35

830UPD

6\_8700\_PKSEASON.TXT

FLORIDA DEPARTMENT OF TRANSPORTATION  
 TRANSPORTATION STATISTICS OFFICE  
 2016 HISTORICAL AADT REPORT

COUNTY: 87 - MIAMI-DADE

SITE: 0012 - SR 907/ALTON RD, 200' N OF 20 ST (MIAMI BEACH)

YEAR	AADT	DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2016	46000 C	N 22500	S 23500	9.00	54.50	3.70
2015	46000 C	N 22500	S 23500	9.00	54.70	3.20
2014	47500 S	N 22000	S 25500	9.00	54.50	2.50
2013	47500 F	N 22000	S 25500	9.00	52.40	2.50
2012	48500 C	N 22500	S 26000	9.00	55.70	2.50
2011	47000 C	N 22500	S 24500	9.00	55.10	3.50
2010	46000 C	N 23000	S 23000	8.98	54.08	3.50
2009	47000 C	N 23500	S 23500	8.99	53.24	3.90
2008	46500 C	N 23000	S 23500	9.09	55.75	2.10
2007	47500 C	N 23000	S 24500	8.01	54.34	2.20
2006	46500 C	N 23000	S 23500	7.97	54.22	3.00
2005	46500 F	N 22500	S 24000	8.80	53.80	5.30
2004	46500 C	N 22500	S 24000	9.00	53.30	5.30
2003	42500 C	N 20500	S 22000	8.80	53.40	4.80
2002	44000 C	N 21500	S 22500	9.80	52.30	1.70
2001	45500 C	N 22500	S 23000	8.20	53.50	5.00


AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE  
 S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE  
 V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN

\*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

**Traffic Trends - V2.0**  
**SR 907/ALTON RD -- 200' N OF 20 ST**

PIN#	0
Location	1

County:	Miami-Dade
Station #:	0012
Highway:	SR 907/ALTON RD



Traffic (ADT/AADT)		
Year	Count*	Trend**
2012	48500	48400
2013	47500	47800
2014	47500	47100
2015	46000	46500
2016	46000	45800
2017	N/A	45200
2018	N/A	44500
2020	N/A	43200

TRANPLAN Forecasts/Trends		

\*\* Annual Trend Increase: -650  
 Trend R-squared: 89.89%  
 Trend Annual Historic Growth Rate: -1.34%  
 Trend Growth Rate (2016 to Design Year): -1.42%  
 Printed: 16-Jan-18

**Straight Line Growth Option**

\*Axe-Adjusted

FLORIDA DEPARTMENT OF TRANSPORTATION  
 TRANSPORTATION STATISTICS OFFICE  
 2016 HISTORICAL AADT REPORT

COUNTY: 87 - MIAMI-DADE

SITE: 2542 - SR 907/ALTON RD, 200' S OF VENETIAN CSWY

YEAR	AADT	DIRECTION 1	DIRECTION 2	*K FACTOR	D FACTOR	T FACTOR
2016	30000 C	N 15000	S 15000	9.00	54.50	5.90
2015	41000 C	N 21000	S 20000	9.00	54.70	1.60
2014	30500 F	N 14000	S 16500	9.00	54.50	7.60
2013	30500 C	N 14000	S 16500	9.00	52.40	7.60
2012	37000 C	N 19000	S 18000	9.00	55.70	7.50
2011	39500 C	N 19000	S 20500	9.00	55.10	1.50
2010	39000 C	N 20000	S 19000	8.98	54.08	1.50
2009	38500 C	N 19000	S 19500	8.99	53.24	6.20
2008	37500 C	N 17500	S 20000	9.09	55.75	4.80
2007	39500 C	N 18500	S 21000	8.01	54.34	5.20
2006	36500 C	N 17500	S 19000	7.97	54.22	1.60
2005	34000 C	N 17000	S 17000	8.80	53.80	9.30
2004	39000 C	N 18500	S 20500	9.00	53.30	9.30
2003	32500 C	N 16000	S 16500	8.80	53.40	10.60
2002	33000 C	N 16000	S 17000	9.80	52.30	5.80
2001	32500 C	N 16500	S 16000	8.20	53.50	5.50


AADT FLAGS: C = COMPUTED; E = MANUAL ESTIMATE; F = FIRST YEAR ESTIMATE  
 S = SECOND YEAR ESTIMATE; T = THIRD YEAR ESTIMATE; R = FOURTH YEAR ESTIMATE  
 V = FIFTH YEAR ESTIMATE; 6 = SIXTH YEAR ESTIMATE; X = UNKNOWN

\*K FACTOR: STARTING WITH YEAR 2011 IS STANDARDK, PRIOR YEARS ARE K30 VALUES

**Traffic Trends - V2.0**  
**SR 907/ALTON RD -- 200' S OF VENETIAN CSWY**

PIN#	0
Location	2

County:	Miami-Dade
Station #:	2542
Highway:	SR 907/ALTON RD




\*\* Annual Trend Increase: -350  
 Trend R-squared: 1.25%  
 Trend Annual Historic Growth Rate: -1.01%  
 Trend Growth Rate (2016 to Design Year): -1.06%  
 Printed: 16-Jan-18

**Straight Line Growth Option**

Year	Traffic (ADT/AADT)	
	Count*	Trend**
2012	37000	34500
2013	30500	34200
2014	30500	33800
2015	41000	33500
2016	30000	33100
2017	N/A	32800
2018	N/A	32400
2020	N/A	31700

TRANPLAN Forecasts/Trends


\*Axe-Adjusted



**Traf Tech**  
ENGINEERING, INC.


## NEW PROJECT TRAFFIC ASSIGNMENT (Weekday New Peak Hour Trips)


**FIGURE 4**  
1750 Alton  
Miami Beach, Florida



**Traf Tech**  
ENGINEERING, INC.

**NEW PROJECT TRAFFIC ASSIGNMENT**  
(Weekday New Peak Hour Trips)





**TABLE A4**  
**17th Street Hotel**  
**PM PEAK HOUR INTERSECTION APPROACH VOLUMES**

INTERSECTION NO	INTERSECTION NAME	APPROACH	MOVEMENT	PM PEAK HR COUNT	DATE OF COUNT	PHF	SF	PM PEAK SEASONALLY ADJUSTED (EXISTING) (2012)	BACKGROUND GROWTH @ 0.62% FOR 3 YEARS	COMMITTED DEVELOPMENT (2015)	TOTAL TRAFFIC (VPH) (PROPOSED W/O PROJECT) (2015)		SITE TRAFFIC (VPH) (VALET OPERATION) (PROPOSED W/ PROJECT) (2015)	
											1	2	3	4
1 Alton Road & 17 Street	WESTBOUND	SBR	171	1.02	174	3	0	176	23	0	201	0	0	0
		SBT	810	1.02	826	15	0	842	0	0	842	0	0	0
		SEL	203	1.02	213	4	0	217	0	0	217	0	0	0
		<b>TOTAL</b>	<b>1190</b>	<b>1.02</b>	<b>1214</b>	<b>23</b>	<b>0</b>	<b>1237</b>	<b>23</b>	<b>0</b>	<b>1260</b>	<b>0</b>	<b>0</b>	<b>0</b>
		WER	301	1.02	307	6	0	313	0	0	313	0	0	0
	TOTAL	WBT	144	1.02	147	3	0	150	4	0	154	0	0	0
		WBL	272	1.02	277	5	0	283	0	0	283	0	0	0
		<b>TOTAL</b>	<b>717</b>	<b>1.02</b>	<b>731</b>	<b>14</b>	<b>0</b>	<b>745</b>	<b>4</b>	<b>0</b>	<b>749</b>	<b>0</b>	<b>0</b>	<b>0</b>
	NORTHBOUND	NBR	173	1.02	176	3	0	180	4	0	184	0	0	0
		NBT	786	1.02	802	15	0	817	10	0	827	0	0	0
		NBL	59	1.02	59	1	0	61	5	0	60	0	0	0
		<b>TOTAL</b>	<b>1018</b>	<b>1.02</b>	<b>1038</b>	<b>19</b>	<b>0</b>	<b>1068</b>	<b>20</b>	<b>0</b>	<b>1111</b>	<b>0</b>	<b>0</b>	<b>0</b>
		EBR	75	1.02	78	1	0	79	0	0	79	0	0	0
2 17 Street & West Avenue	EASTBOUND	EBT	142	1.02	145	3	0	148	0	0	148	0	0	0
		EBL	372	1.02	379	7	0	387	0	0	387	0	0	0
		<b>TOTAL</b>	<b>590</b>	<b>1.02</b>	<b>602</b>	<b>11</b>	<b>0</b>	<b>613</b>	<b>0</b>	<b>0</b>	<b>613</b>	<b>0</b>	<b>0</b>	<b>0</b>
		<b>TOTAL</b>	<b>2615</b>	<b>1.02</b>	<b>3585</b>	<b>67</b>	<b>0</b>	<b>3692</b>	<b>47</b>	<b>33</b>	<b>3732</b>	<b>0</b>	<b>0</b>	<b>0</b>
		SBR	0	1.02	0	0	0	0	0	0	0	0	0	0
	WESTBOUND	SBT	0	1.02	0	0	0	0	0	0	0	0	0	0
		SEL	0	1.02	0	0	0	0	0	0	0	0	0	0
		<b>TOTAL</b>	<b>0</b>	<b>1.02</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>
		WER	0	1.02	0	0	0	0	0	0	0	0	0	0
		WBT	176	1.02	180	3	0	190	11	0	201	0	0	0
	NORTHBOUND	WBL	301	1.02	307	6	0	313	19	0	333	0	0	0
		<b>TOTAL</b>	<b>477</b>	<b>1.02</b>	<b>487</b>	<b>9</b>	<b>0</b>	<b>503</b>	<b>30</b>	<b>0</b>	<b>566</b>	<b>0</b>	<b>0</b>	<b>0</b>
		NBR	265	1.02	270	5	0	275	0	0	275	0	0	0
		NBT	0	1.02	0	0	0	0	0	0	0	0	0	0
		NBL	215	1.02	219	4	0	237	0	0	237	0	0	0
	EASTBOUND	<b>TOTAL</b>	<b>480</b>	<b>1.02</b>	<b>490</b>	<b>9</b>	<b>0</b>	<b>513</b>	<b>0</b>	<b>0</b>	<b>513</b>	<b>0</b>	<b>0</b>	<b>0</b>
		EER	259	1.02	264	5	0	282	0	0	282	0	0	0
		EBT	228	1.02	233	4	0	244	0	0	244	0	0	0
		EBL	0	1.02	0	0	0	0	0	0	0	0	0	0
		<b>TOTAL</b>	<b>487</b>	<b>1.02</b>	<b>497</b>	<b>9</b>	<b>0</b>	<b>526</b>	<b>0</b>	<b>0</b>	<b>526</b>	<b>0</b>	<b>0</b>	<b>0</b>
		<b>TOTAL</b>	<b>1444</b>		<b>1473</b>	<b>28</b>	<b>47</b>	<b>1641</b>	<b>30</b>	<b>33</b>	<b>1604</b>			

INTERSECTION NO.	INTERSECTION NAME	APPROACH	MOVEMENT	PM PEAK HR COUNT	DATE OF COUNT	PHF	SF	PM PEAK SEASONALLY ADJUSTED (EXISTING) (2012)	BACKGROUND GROWTH @ 0.62% FOR 3 YEARS	COMMITTED DEVELOPMENT	TOTAL TRAFFIC (VPH) (PROPOSED W/O PROJECT) (2015)		TOTAL TRAFFIC (VPH) (PROPOSED W/ PROJECT) (2016)	
											1	2	3	4
3	Dade Boulevard & West Avenue	SOUTHBOUND	SBR	50		1.02	51				0	62	0	52
			SEJ	0		1.02	0				0	0	0	0
			SBL	90		1.02	92				7	101	0	101
			<b>TOTAL</b>	<b>140</b>		<b>1.02</b>	<b>143</b>				<b>7</b>	<b>162</b>	<b>0</b>	<b>162</b>
			SWBR	91		1.02	93				0	95	0	95
		SOUTHWESTBOUND	SWAT	181		1.02	185				14	202	0	202
			SWBL	0		1.02	0				0	0	0	0
			<b>TOTAL</b>	<b>272</b>		<b>1.02</b>	<b>277</b>				<b>6</b>	<b>297</b>	<b>0</b>	<b>297</b>
		NORTHBOUND	NBR	0		1.02	0				0	0	0	0
			NBT	0		1.02	0				0	0	0	0
4	Alton Road & Dade Boulevard	NORTHBOUND	NBL	0		1.02	0				0	0	0	0
			<b>TOTAL</b>	<b>0</b>		<b>1.02</b>	<b>0</b>				<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>
			NEBR	0		1.02	242				0	0	0	0
			*NEBT	237		1.02	242				5	0	246	12
			*NEBL	25		1.02	26				0	21	47	0
		NORTHEASTBOUND	<b>TOTAL</b>	<b>262</b>		<b>1.02</b>	<b>267</b>				<b>5</b>	<b>21</b>	<b>293</b>	<b>12</b>
			<b>TOTAL</b>	<b>674</b>		<b>1.02</b>	<b>697</b>				<b>13</b>	<b>42</b>	<b>742</b>	<b>12</b>
			SBR	43		1.02	44				1	0	46	0
			SEJ	90		1.02	918				17	13	948	9
			SBL	50		1.02	51				1	7	59	0
5	West Avenue	WESTBOUND	SEU	22		1.02	22				0	0	23	0
			<b>TOTAL</b>	<b>1015</b>		<b>1.02</b>	<b>1013</b>				<b>19</b>	<b>20</b>	<b>1015</b>	<b>9</b>
			WBR	96		1.02	98				2	0	100	0
			WEBT	110		1.02	112				2	7	121	0
			WBL	269		1.02	274				5	0	280	2
		NORTHBOUND	<b>TOTAL</b>	<b>475</b>		<b>1.02</b>	<b>485</b>				<b>9</b>	<b>7</b>	<b>501</b>	<b>2</b>
			NBR	224		1.02	228				4	0	233	1
			NBT	1141		1.02	1164				22	7	1193	9
			NBL	74		1.02	75				1	7	84	0
			<b>TOTAL</b>	<b>1439</b>		<b>1.02</b>	<b>1468</b>				<b>27</b>	<b>14</b>	<b>1609</b>	<b>10</b>
6	West Avenue	EASTBOUND	*EBR	59		1.02	60				1	0	61	12
			*EBT	101		1.02	103				2	7	112	0
		EASTBOUND	*EBL	97		1.02	99				0	0	101	0
			<b>TOTAL</b>	<b>257</b>		<b>1.02</b>	<b>252</b>				<b>5</b>	<b>7</b>	<b>274</b>	<b>12</b>
		<b>TOTAL</b>	<b>3186</b>								<b>3727</b>	<b>61</b>	<b>48</b>	<b>3569</b>
												<b>33</b>	<b>0</b>	<b>3392</b>

TABLE A4  
17th Street Hotel  
PM PEAK HOUR INTERSECTION APPROACH VOLUMES

INTERSECTION NO.	INTERSECTION NAME	APPROACH	MOVEMENT	PM PEAK HR COUNT	DATE OF COUNT	PHF	SF	PM PEAK SEASONALLY ADJUSTED (EXISTING) (2012)	BACKGROUND GROWTH @ 0.8% FOR 3 YEARS	COMMITTED DEVELOPMENT	TOTAL TRAFFIC (VPH) (PROPOSED W/ PROJECT) (2016)		TOTAL TRAFFIC (VPH) VALET OPERATION (PROPOSED W/ PROJECT) (2015)	
											11	10	12	13
5	17 Street / Bay Road & Dade Boulevard	SBR	23			1.02		23	0	27	51	0	0	51
		SBT	0			1.02		0	0	0	0	0	0	0
		SBL	0			1.02		0	0	0	0	0	0	0
		<b>TOTAL</b>	<b>23</b>			<b>1.02</b>		<b>23</b>	<b>0</b>	<b>27</b>	<b>51</b>	<b>0</b>	<b>0</b>	<b>51</b>
		WBR	0			1.02		0	0	0	0	0	0	0
		WBL	0			1.02		0	0	0	0	0	0	0
		<b>TOTAL</b>	<b>357</b>			<b>1.02</b>		<b>364</b>	<b>7</b>	<b>21</b>	<b>392</b>	<b>11</b>	<b>0</b>	<b>403</b>
		NBR	526			1.02		516	10	20	546	0	0	546
		NBRT	319			1.02		325	6	0	331	12	0	343
		NEBL	0			1.02		0	0	0	0	0	0	0
6	Alton Road & 20 Street	<b>TOTAL</b>	<b>825</b>			<b>1.02</b>		<b>842</b>	<b>16</b>	<b>20</b>	<b>877</b>	<b>12</b>	<b>0</b>	<b>899</b>
		SWBR	659			1.02		70	1	14	86	0	0	86
		SWBT	162			1.02		165	3	0	168	0	0	168
		<b>TOTAL</b>	<b>231</b>			<b>1.02</b>		<b>236</b>	<b>4</b>	<b>14</b>	<b>264</b>	<b>0</b>	<b>0</b>	<b>264</b>
		<b>TOTAL</b>	<b>1436</b>			<b>1.02</b>		<b>1465</b>	<b>27</b>	<b>82</b>	<b>1574</b>	<b>23</b>	<b>0</b>	<b>1697</b>
		SBR	205			1.02		209	4	32	265	0	0	265
		SBT	846			1.02		863	16	0	879	9	0	888
		SBL	23			1.02		23	0	0	24	0	0	24
		<b>TOTAL</b>	<b>1074</b>			<b>1.02</b>		<b>1095</b>	<b>21</b>	<b>32</b>	<b>1168</b>	<b>9</b>	<b>0</b>	<b>1177</b>
		WBR	12			1.02		12	0	0	12	0	0	12
7	West Street	WBRT	1			1.02		1	0	0	1	0	0	1
		WBL	2			1.02		2	0	0	2	0	0	2
		<b>TOTAL</b>	<b>15</b>			<b>1.02</b>		<b>15</b>	<b>0</b>	<b>0</b>	<b>16</b>	<b>0</b>	<b>0</b>	<b>16</b>
		NBR	13			1.02		13	0	0	14	0	0	14
		NBRT	1089			1.02		1111	21	0	1132	9	0	1141
		NBL	1C7			1.02		109	2	16	127	0	0	127
		NEBU	19			1.02		19	0	0	20	0	0	20
		<b>TOTAL</b>	<b>1228</b>			<b>1.02</b>		<b>1253</b>	<b>23</b>	<b>16</b>	<b>1282</b>	<b>9</b>	<b>0</b>	<b>1301</b>
		EBR	22			1.02		22	0	0	23	0	0	23
		EBLT	5			1.02		3	0	0	8	0	0	8
		EBL	247			1.02		252	5	45	302	0	0	302
		<b>TOTAL</b>	<b>277</b>			<b>1.02</b>		<b>283</b>	<b>5</b>	<b>45</b>	<b>333</b>	<b>0</b>	<b>0</b>	<b>333</b>
		<b>TOTAL</b>	<b>2394</b>			<b>1.02</b>		<b>2446</b>	<b>60</b>	<b>113</b>	<b>2698</b>	<b>18</b>	<b>0</b>	<b>2826</b>

TABLE A4

## 17th Street Hotel

## PM PEAK HOUR INTERSECTION APPROACH VOLUMES

INTERSECTION NO.	INTERSECTION NAME	APPROACH MOVEMENT	PM PEAK HR COUNT	DATE OF COUNT	SF PHF	PM PEAK SEASONALLY ADJUSTED (EXISTING) (2012)	BACKGROUND GROWTH @ 0.62% FOR 3 YEARS	COMMITTED DEVELOPMENT	TOTAL TRAFFIC (VPH) (PROPOSED W/O PROJECT) (2015)	SITE TRAFFIC (VPH) VALET OPERATION	TOTAL TRAFFIC (VPH) (PROPOSED W/ PROJECT) (2016)			
7 Alton Road & Lincoln Road	SOUTHBOUND	SBR	100			1.02	102	2	0	104	0	0	104	
		SBT	1025			1.02	1046	20	0	1065	0	0	1065	
		SBU	25			1.02	26	0	0	26	0	0	26	
		<b>TOTAL</b>	<b>1150</b>			<b>1.02</b>	<b>1173</b>	<b>22</b>	<b>0</b>	<b>1195</b>	<b>0</b>	<b>0</b>	<b>1195</b>	
		WBT	0			1.02	0	0	0	0	0	0	0	
	WESTBOUND	WBL	0			1.02	0	0	0	0	0	0	0	
		<b>TOTAL</b>	<b>0</b>			<b>1.02</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	
		NBR	0			1.02	0	0	0	0	0	0	0	
		NBT	938			1.02	957	18	0	975	9	0	984	
		NBL	70			1.02	71	1	0	73	0	0	73	
	NORTHBOUND	<b>TOTAL</b>	<b>1008</b>			<b>1.02</b>	<b>1028</b>	<b>19</b>	<b>0</b>	<b>1047</b>	<b>9</b>	<b>0</b>	<b>1056</b>	
		EBR	65			1.02	65	1	0	68	3	0	71	
		EBT	0			1.02	0	0	0	0	0	0	0	
		EBL	68			1.02	69	1	0	71	14	33	118	
		<b>TOTAL</b>	<b>133</b>			<b>1.02</b>	<b>136</b>	<b>3</b>	<b>0</b>	<b>138</b>	<b>17</b>	<b>33</b>	<b>188</b>	
8 Lincoln Road & West Avenue	EASTBOUND	<b>TOTAL</b>	<b>2291</b>			<b>1.02</b>	<b>2337</b>	<b>44</b>	<b>0</b>	<b>2381</b>	<b>26</b>	<b>33</b>	<b>2440</b>	
		SBR	89			1.02	91	2	0	92	0	0	92	
		SBT	397			1.02	405	3	0	413	2	0	415	
		SBL	25			1.02	26	0	0	26	17	33	75	
		<b>TOTAL</b>	<b>511</b>			<b>1.02</b>	<b>521</b>	<b>10</b>	<b>0</b>	<b>531</b>	<b>19</b>	<b>33</b>	<b>583</b>	
	WESTBOUND	WBT	42			1.02	43	1	0	44	0	0	44	
		WBL	45			1.02	45	1	0	47	0	0	47	
		<b>TOTAL</b>	<b>133</b>			<b>1.02</b>	<b>138</b>	<b>3</b>	<b>0</b>	<b>138</b>	<b>0</b>	<b>0</b>	<b>138</b>	
		NBR	46			1.02	47	1	0	48	0	0	48	
		NBT	411			1.02	419	9	0	427	0	0	427	
	NORTHBOUND	<b>TOTAL</b>	<b>470</b>			<b>1.02</b>	<b>478</b>	<b>9</b>	<b>0</b>	<b>488</b>	<b>0</b>	<b>0</b>	<b>488</b>	
		EBR	23			1.02	23	0	0	24	0	0	24	
		EBT	28			1.02	30	1	0	30	0	0	30	
		EBL	54			1.02	55	1	0	55	0	0	55	
		<b>TOTAL</b>	<b>106</b>			<b>1.02</b>	<b>108</b>	<b>2</b>	<b>0</b>	<b>110</b>	<b>0</b>	<b>0</b>	<b>110</b>	
9 17 Street & Alton Court	TOTAL	<b>TOTAL</b>	<b>1220</b>			<b>1.02</b>	<b>1244</b>	<b>23</b>	<b>0</b>	<b>1268</b>	<b>19</b>	<b>33</b>	<b>1320</b>	
		SBR	15			1.02	15	0	0	16	0	30	46	
		SBT	0			1.02	0	0	0	0	0	0	0	
		SBL	12			1.02	12	0	0	12	0	12	12	
		<b>TOTAL</b>	<b>27</b>			<b>1.02</b>	<b>28</b>	<b>1</b>	<b>0</b>	<b>28</b>	<b>0</b>	<b>30</b>	<b>58</b>	
	WESTBOUND	WBT	11			1.02	11	0	0	11	1	0	1	
		WBL	435			1.02	444	9	7	459	33	33	44	
		<b>TOTAL</b>	<b>446</b>			<b>1.02</b>	<b>465</b>	<b>9</b>	<b>7</b>	<b>470</b>	<b>33</b>	<b>33</b>	<b>518</b>	
		NBR	78			1.02	80	1	0	81	0	0	81	
		NBT	1			1.02	1	0	0	1	0	0	1	
	NORTHBOUND	<b>TOTAL</b>	<b>105</b>			<b>1.02</b>	<b>107</b>	<b>2</b>	<b>0</b>	<b>109</b>	<b>0</b>	<b>0</b>	<b>109</b>	
		EBR	0			1.02	0	0	0	0	0	0	0	
		EBT	489			1.02	495	9	0	508	0	0	508	
		EBL	4			1.02	4	0	4	0	0	0	4	
		<b>TOTAL</b>	<b>493</b>			<b>1.02</b>	<b>503</b>	<b>9</b>	<b>0</b>	<b>512</b>	<b>0</b>	<b>0</b>	<b>512</b>	
1071	<b>TOTAL</b>						<b>0.936</b>			<b>1072</b>	<b>7</b>	<b>33</b>	<b>63</b>	<b>1216</b>

Notes:

- Volumes extrapolated from PD&E TMC data.

1 Intersection Name

2 Intersection Approach

3 Intersection Approach Movement

4 TMC data provided by RCA, Inc.

5 Date of Count

6 Peak Hour Factor

7 Seasonal Factor obtained from DOT

B Seasonally Adjusted TMC = Count \* SF (These are the volumes utilized in the existing condition intersection LOS).

9 A/C 62 percent background growth was utilized with a project build-out of three years.


10 Computed Traffic.

11 Proposed Traffic w/o Project = Peak Seasonally Adjusted TMC + Background+Committed

12 Site traffic assignment

13 Site traffic assignment for Valet Operation.


14 Total Traffic = Net Traffic + Site Traffic (These are the volumes utilized in the proposed intersection LOS analysis).



- IN
- OUT
- Project Location


# Exhibit 9A

## PROJECT TRIP ASSIGNMENT



**Traf Tech**  
ENGINEERING, INC.

**NEW PROJECT TRAFFIC ASSIGNMENT**  
**(Weekday New PM Peak Hour Trips)**



# **APPENDIX E**

## **Future Turning Movement Volumes**

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### Dade Boulevard and Purdy Avenue PM Peak Hour

Description	Dade Boulevard Northbound			Purdy Avenue Southbound			Dade Boulevard Eastbound			Dade Boulevard Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017)				65	161		138	438		522	58	
Season Adjustment Factor	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	0	0	0	68	0	167	144	456	0	543	60	
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments:									58		56	
1901 Alton												
Trader Joes												
1750 Alton												
Other Committed Developments									5		9	
1747 Bay Road Development											2	
2020 Background Traffic	0	0	0	70	0	173	149	532	0	626	62	
Sunset Harbour Trips												
Pass-by												
Valet												
2020 Total Traffic	0	0	0	70	0	173	170	521	0	626	109	

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### Dade Boulevard and Bay Road PM Peak Hour

Description	17 Street Northbound			Bay Road Southbound			Dade Boulevard Eastbound			Dade Boulevard Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017) Season Adjustment Factor	366 1.04			24 1.04			178 1.04			333 1.04		
	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	381 0			0 0			25 0			185 346		
	0	220	27	0	185	346	0	220	27	0	220	27
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments:												
1901 Alton	10											
Trader Joes	3											
1750 Alton	21											
Other Committed Developments												
1747 Bay Road Development												
2020 Background Traffic	426	0	0	0	0	55	0	259	377	0	302	48
Sunset Harbour Trips												
Pass-by												
Valet												
2020 Total Traffic	426	0	0	0	0	124	0	259	377	0	292	69

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### 17th Street and West Avenue PM Peak Hour

Description	West Avenue Northbound			West Avenue Southbound			17th Street Eastbound			17th Street Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017)	142	213	141	15	166	1	1	160	173	120	208	35
Season Adjustment Factor	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	148	222	147	16	173	1	1	166	180	125	216	36
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments:												
1901 Alton												
Trader Joes	10		42				15	3				
1750 Alton							7	13				7
Other Committed Developments												
1747 Bay Road Development												
2020 Background Traffic	176	228	193	16	178	1	16	181	198	129	230	38
Sunset Harbour Trips		9		2	11							2
Pass-by												
Valet												
2020 Total Traffic	176	237	193	18	189	1	16	181	198	129	230	40

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### Dade Boulevard and West Avenue PM Peak Hour

Description	West Avenue Northbound			West Avenue Southbound			Dade Boulevard Eastbound			Dade Boulevard Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017) Season Adjustment Factor	8      128      90			69      104      26			9      159      1.04			76      193      122		
	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	8      133      94			72      108      27			9      165      0			79      201      127		
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments: 1901 Alton Trader Joes 1750 Alton Other Committed Developments 1747 Bay Road Development							58			56		
2020 Background Traffic	9      137      96			83      111      29			5			9		
Sunset Harbour Trips Pass-by Valet				11			11			2		
				10			13			11		
				10			233			81		
2020 Total Traffic	<b>9      148      96</b>			<b>104      124      29</b>			<b>10      233      0</b>			<b>81      285      131</b>		

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### 18th Street and West Avenue PM Peak Hour

Description	West Avenue Northbound			West Avenue Southbound			18th Street Eastbound			18th Street Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017)	93	155	16	13	81	77	67	14	94	6	11	12
Season Adjustment Factor	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	97	161	17	14	84	80	70	15	98	6	11	12
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments: 1901 Alton Trader Joes 1750 Alton Other Committed Developments 1747 Bay Road Development												
2020 Background Traffic	100	166	17	14	87	83	72	15	111	6	12	13
Sunset Harbour Trips Pass-by Valet	11				4		4		24		10	
<b>2020 Total Traffic</b>	<b>111</b>	<b>166</b>	<b>17</b>	<b>14</b>	<b>87</b>	<b>87</b>	<b>76</b>	<b>15</b>	<b>145</b>	<b>6</b>	<b>12</b>	<b>13</b>

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### 18th Street and Bay Road PM Peak Hour

Description	Bay Road Northbound			Bay Road Southbound			18th Street Eastbound			18th Street Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017)	8	19	24	80	23	44	42	78	15	24	94	68
Season Adjustment Factor	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	8	20	25	83	24	46	44	81	16	25	98	71
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments: 1901 Alton Trader Joes 1750 Alton Other Committed Developments 1747 Bay Road Development												
2020 Background Traffic	9	26	35	86	25	47	45	85	16	26	101	73
Sunset Harbour Trips Pass-by Valet	3	3	28	3					13	15	11	47
2020 Total Traffic	12	29	73	86	28	47	45	85	87	41	101	73

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### 18th Street and Purdy Avenue PM Peak Hour

Description	Purdy Avenue Northbound			Purdy Avenue Southbound			18th Street Eastbound			18th Street Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017)	13	105	99	22	121	4	12	17	27	89	8	41
Season Adjustment Factor	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	14	109	103	23	126	4	12	18	28	93	8	43
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments:												
1901 Alton												
Trader Joes												
1750 Alton												
Other Committed Developments												
1747 Bay Road Development			1									
2020 Background Traffic	14	113	107	24	130	4	13	18	29	95	9	44
Sunset Harbour Trips			10	3								3
Pass-by			11									
Valet			47									
2020 Total Traffic	14	113	175	27	130	4	13	18	29	95	9	47

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### 20th Street and West Avenue PM Peak Hour

Description	West Avenue Northbound			Driveway Southbound			20th Street Eastbound			20th Street Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (12/15/2017)	31	1	143	0	1	2	2	237	51	135	201	1
Season Adjustment Factor	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04	1.04
2017 Peak Season Traffic	32	1	149	0	1	2	2	246	53	140	209	1
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments: 1901 Alton Trader Joes 1750 Alton Other Committed Developments 1747 Bay Road Development												
2020 Background Traffic	33	1	153	0	1	2	2	254	55	145	215	1
Sunset Harbour Trips Pass-by Valet			3					6		4	6	
<b>2020 Total Traffic</b>	<b>33</b>	<b>1</b>	<b>156</b>	<b>0</b>	<b>1</b>	<b>2</b>	<b>2</b>	<b>260</b>	<b>55</b>	<b>149</b>	<b>221</b>	<b>1</b>

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

## FUTURE TURNING MOVEMENT VOLUME ANALYSIS

### 20th Street and West Avenue PM Peak Hour

Description	Bay Road Northbound			Southbound			20th Street Eastbound			20th Street Westbound		
	Left	Through	Right	Left	Through	Right	Left	Through	Right	Left	Through	Right
Existing Traffic (3/9/2018)	20		153					101	10	78	211	
Season Adjustment Factor	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
2017 Peak Season Traffic	20	0	153	0	0	0	0	101	10	78	211	0
Annual Growth Rate	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%	1.0%
Committed Developments: 1901 Alton Trader Joes 1750 Alton Other Committed Developments 1747 Bay Road Development												
2020 Background Traffic	20	0	156	0	0	0	0	103	10	80	215	0
Sunset Harbour Trips Pass-by Valet			3					3		3	3	
<b>2020 Total Traffic</b>	<b>20</b>	<b>0</b>	<b>159</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>106</b>	<b>10</b>	<b>83</b>	<b>218</b>	<b>0</b>

Sunset Harbour	PM Peak		
	INS	OUTS	Total
Net New Trips	42	46	88
Pass-by	21	20	41
Gross Trips	63	66	129

# **APPENDIX F**

## **Intersection Capacity Analyses**

# HCM 2010 Signalized Intersection Summary

## 101: Dade Boulevard & Purdy Avenue


---



Movement	EBL	EBT	WBT	WBR	SBL	SBR		
Lane Configurations	↑ ↗	↑ ↘	↑ ↖		↑ ↗	↑ ↘		
Traffic Volume (veh/h)	144	456	543	60	68	167		
Future Volume (veh/h)	144	456	543	60	68	167		
Number	1	6	2	12	3	18		
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0		
Ped-Bike Adj(A_pbT)	1.00			0.97	1.00	1.00		
Parking Bus, Adj	1.00	1.00	1.00	0.90	0.90	0.90		
Adj Sat Flow, veh/h/in	1676	1676	1676	1710	1676	1676		
Adj Flow Rate, veh/h	157	496	590	65	74	182		
Adj No. of Lanes	1	1	1	0	1	1		
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92		
Percent Heavy Veh, %	2	2	2	2	2	2		
Cap, veh/h	437	1255	996	110	228	203		
Arrive On Green	0.75	0.75	0.75	0.75	0.16	0.16		
Sat Flow, veh/h	696	1676	1331	147	1437	1282		
Grp Volume(v), veh/h	157	496	0	655	74	182		
Grp Sat Flow(s), veh/h/in	696	1676	0	1478	1437	1282		
Q Serve(g_s), s	17.1	13.7	0.0	26.0	5.9	18.1		
Cycle Q Clear(g_c), s	43.2	13.7	0.0	26.0	5.9	18.1		
Prop In Lane	1.00			0.10	1.00	1.00		
Lane Grp Cap(c), veh/h	437	1255	0	1106	228	203		
V/C Ratio(X)	0.36	0.40	0.00	0.59	0.32	0.90		
Avail Cap(c_a), veh/h	437	1255	0	1106	387	345		
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00		
Upstream Filter(I)	1.00	1.00	0.00	0.56	1.00	1.00		
Uniform Delay (d), s/veh	17.1	5.8	0.0	7.4	48.5	53.6		
Incr Delay (d2), s/veh	2.3	0.9	0.0	1.3	0.6	12.4		
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0		
%ile BackOfQ(50%), veh/in	3.5	6.7	0.0	11.0	2.4	7.1		
LnGrp Delay(d), s/veh	19.4	6.8	0.0	8.7	49.1	66.0		
LnGrp LOS	B	A		A	D	E		
Approach Vol, veh/h		653	655		256			
Approach Delay, s/veh		9.8	8.7		61.1			
Approach LOS		A	A		E			
Timer	1	2	3	4	5	6	7	8
Assigned Phs		2			6		8	
Phs Duration (G+Y+R <sub>c</sub> ), s		103.4			103.4		26.6	
Change Period (Y+R <sub>c</sub> ), s		6.1			6.1		6.0	
Max Green Setting (G <sub>max</sub> ), s		83.0			83.0		35.0	
Max Q Clear Time (g <sub>c+l1</sub> ), s		28.0			45.2		20.1	
Green Ext Time (p <sub>c</sub> ), s		1.7			1.8		0.5	
Intersection Summary								
HCM 2010 Ctrl Delay			17.8					
HCM 2010 LOS			B					

## Timings

### 101: Dade Boulevard & Purdy Avenue



Lane Group	EBL	EBT	WBT	SBL	SBR
Lane Configurations	↑ ↗	↑ ↘	↗ ↙	↖ ↗	↖ ↘
Traffic Volume (vph)	144	456	543	68	167
Future Volume (vph)	144	456	543	68	167
Turn Type	Perm	NA	NA	Prot	Perm
Protected Phases		6	2	8	
Permitted Phases		6			8
Detector Phase		6	2	8	8
Switch Phase					
Minimum Initial (s)	14.0	14.0	14.0	7.0	7.0
Minimum Split (s)	20.8	20.8	22.1	30.0	30.0
Total Split (s)	89.1	89.1	89.1	41.0	41.0
Total Split (%)	68.5%	68.5%	68.5%	31.5%	31.5%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.1	2.1	2.1	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.1	6.1	6.1	6.0	6.0
Lead/Lag					
Lead-Lag Optimize?					
Recall Mode	C-Min	C-Min	C-Min	None	None
Act Effect Green (s)	106.1	106.1	106.1	11.9	11.9
Actuated g/C Ratio	0.82	0.82	0.82	0.09	0.09
v/c Ratio	0.33	0.40	0.54	0.57	0.68
Control Delay	5.7	4.8	6.3	72.3	20.8
Queue Delay	0.0	0.0	1.4	0.0	0.0
Total Delay	5.7	4.8	7.7	72.3	20.8
LOS	A	A	A	E	C
Approach Delay		5.0	7.7	35.7	
Approach LOS		A	A	D	

#### Intersection Summary

Cycle Length: 130.1

Actuated Cycle Length: 130.1

Offset: 86 (66%), Referenced to phase 2:WBT and 6:EBTL, Start of Yellow

Natural Cycle: 75

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.68

Intersection Signal Delay: 11.2


Intersection LOS: B

Intersection Capacity Utilization 78.7%

ICU Level of Service D

Analysis Period (min) 15

Splits and Phases: 101: Dade Boulevard & Purdy Avenue



## Queues

### 101: Dade Boulevard & Purdy Avenue



Lane Group	EBL	EBT	WBT	SBL	SBR
Lane Group Flow (vph)	157	496	655	74	182
v/c Ratio	0.33	0.40	0.54	0.57	0.68
Control Delay	5.7	4.8	6.3	72.3	20.8
Queue Delay	0.0	0.0	1.4	0.0	0.0
Total Delay	5.7	4.8	7.7	72.3	20.8
Queue Length 50th (ft)	26	91	142	61	0
Queue Length 95th (ft)	67	174	273	108	75
Internal Link Dist (ft)		273	491	484	
Turn Bay Length (ft)	80		100		
Base Capacity (vph)	473	1230	1213	385	434
Starvation Cap Reductn	0	0	349	0	0
Spillback Cap Reductn	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0
Reduced v/c Ratio	0.33	0.40	0.76	0.19	0.42


### Intersection Summary

HCM Signalized Intersection Capacity Analysis  
102: 17th Street/Bay Road & Dade Boulevard

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑	↑		↑	↑	↑	↑				↑
Traffic Volume (vph)	0	185	346	0	220	27	381	0	0	0	0	25
Future Volume (vph)	0	185	346	0	220	27	381	0	0	0	0	25
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.9	6.9		6.9		7.7					6.9
Lane Util. Factor	1.00	1.00	1.00		1.00		1.00					1.00
Frpb, ped/bikes	1.00	1.00		0.99		1.00						1.00
Flpb, ped/bikes	1.00	1.00		1.00		1.00						1.00
Fr <sub>t</sub>	1.00	0.85		0.99		1.00						0.86
Flt Protected	1.00	1.00		1.00		0.95						1.00
Satd. Flow (prot)	1509	1282		1477		1433						1233
Flt Permitted	1.00	1.00		1.00		0.95						1.00
Satd. Flow (perm)	1509	1282		1477		1433						1233
Peak-hour factor, PHF	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
Adj. Flow (vph)	0	213	398	0	253	31	438	0	0	0	0	29
RTOR Reduction (vph)	0	0	267	0	10	0	0	0	0	0	0	19
Lane Group Flow (vph)	0	213	131	0	274	0	438	0	0	0	0	10
Confl. Peds. (#/hr)	17				17			10	10			
Confl. Bikes (#/hr)			1			14			4			
Parking (#/hr)	0	0	0	0	0	0	0	0	0	0	0	10
Turn Type	NA	custom		NA		Prot						Perm
Protected Phases		6				4						
Permitted Phases	6			2								6
Actuated Green, G (s)	14.0	14.0		14.0		14.0						14.0
Effective Green, g (s)	14.0	14.0		14.0		14.0						14.0
Actuated g/C Ratio	0.33	0.33		0.33		0.33						0.33
Clearance Time (s)	6.9	6.9		6.9		7.7						6.9
Vehicle Extension (s)	2.5	2.5		2.5		3.5						2.5
Lane Grp Cap (vph)	495	421		485		470						405
v/s Ratio Prot		0.10				c0.31						
v/s Ratio Perm	0.14		c0.19									0.01
v/c Ratio	0.43	0.31		0.56		0.93						0.02
Uniform Delay, d1	11.2	10.7		11.8		13.8						9.7
Progression Factor	1.00	1.00		1.00		1.00						1.00
Incremental Delay, d2	0.4	0.3		1.2		25.7						0.0
Delay (s)	11.6	11.0		13.0		39.5						9.7
Level of Service	B	B		B		D						A
Approach Delay (s)	11.2		13.0			39.5						9.7
Approach LOS	B			B		D						A
<b>Intersection Summary</b>												
HCM 2000 Control Delay	20.7		HCM 2000 Level of Service		C							
HCM 2000 Volume to Capacity ratio	0.75											
Actuated Cycle Length (s)	42.6		Sum of lost time (s)		14.6							
Intersection Capacity Utilization	64.8%		ICU Level of Service		C							
Analysis Period (min)	15											
c Critical Lane Group												

## Timings

### 102: 17th Street/Bay Road & Dade Boulevard



Lane Group	EBT	EBR	WBT	NBL	SBR
Lane Configurations	↑	↗	↑	↖	↗
Traffic Volume (vph)	185	346	220	381	25
Future Volume (vph)	185	346	220	381	25
Turn Type	NA	custom	NA	Prot	Perm
Protected Phases			6		4
Permitted Phases				2	6
Detector Phase	6	6	2	4	6
Switch Phase					
Minimum Initial (s)	14.0	14.0	14.0	14.0	14.0
Minimum Split (s)	20.9	20.9	20.9	21.7	20.9
Total Split (s)	20.9	20.9	20.9	21.7	20.9
Total Split (%)	49.1%	49.1%	49.1%	50.9%	49.1%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.9	2.9	2.9	3.7	2.9
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.9	6.9	6.9	7.7	6.9
Lead/Lag					
Lead-Lag Optimize?					
Recall Mode	Min	Min	Min	None	Min
Act Effect Green (s)	14.0	14.0	14.0	14.0	14.0
Actuated g/C Ratio	0.33	0.33	0.33	0.33	0.33
v/c Ratio	0.43	0.58	0.57	0.93	0.05
Control Delay	14.5	5.6	16.7	47.1	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0
Total Delay	14.5	5.6	16.7	47.1	0.2
LOS	B	A	B	D	A
Approach Delay	8.7		16.7		
Approach LOS	A		B		

#### Intersection Summary

Cycle Length: 42.6

Actuated Cycle Length: 42.6

Natural Cycle: 60

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 0.93

Intersection Signal Delay: 22.6


Intersection LOS: C

Intersection Capacity Utilization 64.8%

ICU Level of Service C


Analysis Period (min) 15

Splits and Phases: 102: 17th Street/Bay Road & Dade Boulevard



## Queues

### 102: 17th Street/Bay Road & Dade Boulevard



Lane Group	EBT	EBR	WBT	NBL	SBR
Lane Group Flow (vph)	213	398	284	438	29
v/c Ratio	0.43	0.58	0.57	0.93	0.05
Control Delay	14.5	5.6	16.7	47.1	0.2
Queue Delay	0.0	0.0	0.0	0.0	0.0
Total Delay	14.5	5.6	16.7	47.1	0.2
Queue Length 50th (ft)	39	0	52	99	0
Queue Length 95th (ft)	79	40	103	#226	0
Internal Link Dist (ft)	491		508		
Turn Bay Length (ft)					
Base Capacity (vph)	495	688	495	470	532
Starvation Cap Reductn	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0
Reduced v/c Ratio	0.43	0.58	0.57	0.93	0.05

#### Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.


# HCM 2010 Signalized Intersection Summary

## 103: West Avenue & Dade Boulevard

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑		↑	↑↑			↓			↓	
Traffic Volume (veh/h)	9	165	0	79	201	127	8	133	94	72	108	27
Future Volume (veh/h)	9	165	0	79	201	127	8	133	94	72	108	27
Number	7	4	14	3	8	18	5	2	12	1	6	16
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A <sub>pbT</sub> )	1.00			1.00	1.00		0.97	0.98		0.93	0.98	0.93
Parking Bus, Adj	1.00	0.90	1.00	1.00	1.00	0.90	1.00	1.00	0.90	1.00	1.00	0.90
Adj Sat Flow, veh/h/ln	1676	1676	1710	1676	1676	1710	1710	1676	1710	1710	1676	1710
Adj Flow Rate, veh/h	10	176	0	84	214	135	9	141	100	77	115	29
Adj No. of Lanes	1	1	0	1	2	0	0	1	0	0	1	0
Peak Hour Factor	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	529	717	0	598	856	511	87	205	140	194	213	45
Arrive On Green	0.48	0.48	0.00	0.48	0.48	0.48	0.26	0.26	0.26	0.26	0.26	0.26
Sat Flow, veh/h	922	1509	0	1079	1801	1074	18	795	542	333	826	175
Grp Volume(v), veh/h	10	176	0	84	188	161	250	0	0	221	0	0
Grp Sat Flow(s),veh/h/ln	922	1509	0	1079	1593	1282	1355	0	0	1333	0	0
Q Serve(g_s), s	0.3	3.1	0.0	2.3	3.2	3.4	0.2	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	3.7	3.1	0.0	5.4	3.2	3.4	7.5	0.0	0.0	6.2	0.0	0.0
Prop In Lane	1.00			1.00		0.84	0.04		0.40	0.35		0.13
Lane Grp Cap(c), veh/h	529	717	0	598	757	610	432	0	0	452	0	0
V/C Ratio(X)	0.02	0.25	0.00	0.14	0.25	0.26	0.58	0.00	0.00	0.49	0.00	0.00
Avail Cap(c_a), veh/h	529	717	0	598	757	610	563	0	0	568	0	0
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.91	0.91	0.00	1.00	1.00	1.00	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	8.2	7.0	0.0	8.6	7.0	7.1	15.2	0.0	0.0	14.6	0.0	0.0
Incr Delay (d2), s/veh	0.1	0.7	0.0	0.5	0.8	1.1	1.2	0.0	0.0	0.8	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.1	1.4	0.0	0.7	1.5	1.3	2.9	0.0	0.0	2.5	0.0	0.0
LnGrp Delay(d),s/veh	8.2	7.7	0.0	9.1	7.8	8.1	16.4	0.0	0.0	15.5	0.0	0.0
LnGrp LOS	A	A		A	A	A	B			B		
Approach Vol, veh/h	186				433			250			221	
Approach Delay, s/veh	7.8				8.2			16.4			15.5	
Approach LOS	A				A			B			B	
Timer	1	2	3	4	5	6	7	8				
Assigned Phs	2			4		6		8				
Phs Duration (G+Y+R <sub>c</sub> ), s	17.6			27.4		17.6		27.4				
Change Period (Y+R <sub>c</sub> ), s	6.0			6.0		6.0		6.0				
Max Green Setting (G <sub>max</sub> ), s	16.0			17.0		16.0		17.0				
Max Q Clear Time (g <sub>c+l1</sub> ), s	9.5			5.7		8.2		7.4				
Green Ext Time (p <sub>c</sub> ), s	0.8			0.7		0.8		1.7				
<b>Intersection Summary</b>												
HCM 2010 Ctrl Delay				11.5								
HCM 2010 LOS				B								

## Timings

### 103: West Avenue & Dade Boulevard



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations	↑	↓	↑	↑↓		↔		↔
Traffic Volume (vph)	9	165	79	201	8	133	72	108
Future Volume (vph)	9	165	79	201	8	133	72	108
Turn Type	Perm	NA	Perm	NA	Perm	NA	Perm	NA
Protected Phases				4		8		2
Permitted Phases						2		6
Detector Phase				4	4	8	8	2
Switch Phase						2	2	6
Minimum Initial (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Split (s)	22.0	22.0	22.0	22.0	22.0	22.0	22.0	22.0
Total Split (s)	23.0	23.0	23.0	23.0	22.0	22.0	22.0	22.0
Total Split (%)	51.1%	51.1%	51.1%	51.1%	48.9%	48.9%	48.9%	48.9%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0		0.0		0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0		6.0		6.0
Lead/Lag								
Lead-Lag Optimize?								
Recall Mode	C-Max	C-Max	C-Max	C-Max	Min	Min	Min	Min
Act Effect Green (s)	20.8	20.8	20.8	20.8		12.2		12.2
Actuated g/C Ratio	0.46	0.46	0.46	0.46		0.27		0.27
v/c Ratio	0.03	0.25	0.19	0.25		0.58		0.66
Control Delay	8.9	10.1	10.3	5.9		14.3		22.2
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0
Total Delay	8.9	10.1	10.3	5.9		14.3		22.2
LOS	A	B	B	A		B		C
Approach Delay		10.0		6.8		14.3		22.2
Approach LOS		B		A		B		C

#### Intersection Summary

Cycle Length: 45

Actuated Cycle Length: 45

Offset: 22 (49%), Referenced to phase 4:EBTL and 8:WBTL, Start of Yellow

Natural Cycle: 45

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.66

Intersection Signal Delay: 12.2


Intersection LOS: B

Intersection Capacity Utilization 66.7%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 103: West Avenue & Dade Boulevard



## Queues

## 103: West Avenue &amp; Dade Boulevard



Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	10	176	84	349	250	221
v/c Ratio	0.03	0.25	0.19	0.25	0.58	0.66
Control Delay	8.9	10.1	10.3	5.9	14.3	22.2
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	8.9	10.1	10.3	5.9	14.3	22.2
Queue Length 50th (ft)	1	26	12	15	35	44
Queue Length 95th (ft)	8	66	38	40	77	89
Internal Link Dist (ft)		508		381	432	477
Turn Bay Length (ft)						
Base Capacity (vph)	375	697	449	1372	540	435
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.03	0.25	0.19	0.25	0.46	0.51

Intersection Summary


# HCM 2010 Signalized Intersection Summary

## 104: West Avenue & 17th Street

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	1	166	180	125	216	36	148	222	147	16	173	1
Future Volume (veh/h)	1	166	180	125	216	36	148	222	147	16	173	1
Number	1	6	16	5	2	12	7	4	14	3	8	18
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	0.97			1.00		0.93	0.96		0.94	1.00		0.91
Parking Bus, Adj	1.00	1.00	0.90	1.00	1.00	0.90	1.00	1.00	0.85	1.00	1.00	0.90
Adj Sat Flow, veh/h/ln	1710	1676	1710	1676	1676	1710	1676	1676	1710	1676	1676	1710
Adj Flow Rate, veh/h	1	173	188	130	225	38	154	231	153	17	180	1
Adj No. of Lanes	0	2	0	1	1	0	1	1	0	1	1	0
Peak Hour Factor	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	28	784	504	111	722	122	295	252	167	89	485	3
Arrive On Green	0.47	0.47	0.47	0.07	0.58	0.58	0.32	0.32	0.32	0.32	0.32	0.32
Sat Flow, veh/h	1	1675	1076	1597	1243	210	1037	778	515	896	1498	8
Grp Volume(v), veh/h	174	0	188	130	0	263	154	0	384	17	0	181
Grp Sat Flow(s),veh/h/ln	1676	0	1076	1597	0	1453	1037	0	1293	896	0	1506
Q Serve(g_s), s	0.0	0.0	14.6	9.0	0.0	12.0	17.4	0.0	37.2	2.4	0.0	12.0
Cycle Q Clear(g_c), s	8.0	0.0	14.6	9.0	0.0	12.0	29.4	0.0	37.2	39.6	0.0	12.0
Prop In Lane	0.01		1.00	1.00		0.14	1.00		0.40	1.00		0.01
Lane Grp Cap(c), veh/h	812	0	504	111	0	844	295	0	418	89	0	487
V/C Ratio(X)	0.21	0.00	0.37	1.18	0.00	0.31	0.52	0.00	0.92	0.19	0.00	0.37
Avail Cap(c_a), veh/h	812	0	504	111	0	844	351	0	487	137	0	568
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00
Uniform Delay (d), s/veh	20.5	0.0	22.3	60.5	0.0	13.9	45.1	0.0	42.3	61.4	0.0	33.8
Incr Delay (d2), s/veh	0.6	0.0	2.1	140.6	0.0	1.0	1.1	0.0	20.1	0.8	0.0	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	3.9	0.0	4.6	8.3	0.0	5.0	5.1	0.0	15.6	0.6	0.0	5.0
LnGrp Delay(d),s/veh	21.1	0.0	24.4	201.1	0.0	14.9	46.2	0.0	62.4	62.1	0.0	34.2
LnGrp LOS	C		C	F		B	D		E	E		C
Approach Vol, veh/h	362			393			538			198		
Approach Delay, s/veh	22.8			76.5			57.8			36.6		
Approach LOS	C			E			E			D		
Timer	1	2	3	4	5	6	7	8				
Assigned Phs		2		4	5	6		8				
Phs Duration (G+Y+R <sub>c</sub> ), s	81.7		48.3	14.7	67.0		48.3					
Change Period (Y+R <sub>c</sub> ), s	* 6.2		* 6.2	* 5.7	* 6.2		* 6.2					
Max Green Setting (Gmax), s	* 69		* 49	* 9	* 54		* 49					
Max Q Clear Time (g_c+l1), s	14.0		39.2	11.0	16.6		41.6					
Green Ext Time (p_c), s	0.6		1.9	0.0	0.9		0.5					
<b>Intersection Summary</b>												
HCM 2010 Ctrl Delay			51.4									
HCM 2010 LOS			D									
Notes												

## Timings

### 104: West Avenue & 17th Street



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations								
Traffic Volume (vph)	1	166	125	216	148	222	16	173
Future Volume (vph)	1	166	125	216	148	222	16	173
Turn Type	Perm	NA	Prot	NA	Perm	NA	Perm	NA
Protected Phases		6	5	2		4		8
Permitted Phases	6				4		8	
Detector Phase	6	6	5	2	4	4	8	8
Switch Phase								
Minimum Initial (s)	7.0	7.0	5.0	7.0	7.0	7.0	7.0	7.0
Minimum Split (s)	37.2	37.2	12.0	37.2	35.2	35.2	32.2	32.2
Total Split (s)	60.2	60.2	14.7	75.2	55.2	55.2	55.2	55.2
Total Split (%)	46.2%	46.2%	11.3%	57.7%	42.3%	42.3%	42.3%	42.3%
Yellow Time (s)	4.0	4.0	3.7	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.2	2.2	2.0	2.2	2.2	2.2	2.2	2.2
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.2	5.7	6.2	6.2	6.2	6.2	6.2	6.2
Lead/Lag	Lag	Lag	Lead					
Lead-Lag Optimize?	Yes	Yes	Yes					
Recall Mode	C-Min	C-Min	None	C-Min	Min	Min	Min	Min
Act Effect Green (s)	48.2	24.2	78.1	39.9	39.9	39.9	39.9	39.9
Actuated g/C Ratio	0.37	0.19	0.60	0.31	0.31	0.31	0.31	0.31
v/c Ratio	0.35	0.51	0.30	0.64	0.87	0.13	0.39	
Control Delay	15.9	56.4	15.1	49.7	59.2	31.2	36.5	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	15.9	56.4	15.1	49.7	59.2	31.2	36.5	
LOS	B	E	B	D	E	C	D	
Approach Delay	15.9		28.8		56.5		36.1	
Approach LOS	B		C		E		D	

#### Intersection Summary

Cycle Length: 130.4

Actuated Cycle Length: 130.4

Offset: 114 (87%), Referenced to phase 2:WBT and 6:EBTL, Start of Yellow

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.87

Intersection Signal Delay: 36.6


Intersection LOS: D

Intersection Capacity Utilization 102.4%

ICU Level of Service G

Analysis Period (min) 15

Splits and Phases: 104: West Avenue & 17th Street



## Queues

## 104: West Avenue &amp; 17th Street



Lane Group	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Group Flow (vph)	362	130	263	154	384	17	181
v/c Ratio	0.35	0.51	0.30	0.64	0.87	0.13	0.39
Control Delay	15.9	56.4	15.1	49.7	59.2	31.2	36.5
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	15.9	56.4	15.1	49.7	59.2	31.2	36.5
Queue Length 50th (ft)	51	102	101	111	285	10	120
Queue Length 95th (ft)	106	170	189	169	371	28	165
Internal Link Dist (ft)	476		364		407		104
Turn Bay Length (ft)		160		170		50	
Base Capacity (vph)	1151	256	876	300	539	161	572
Starvation Cap Reductn	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0
Reduced v/c Ratio	0.31	0.51	0.30	0.51	0.71	0.11	0.32

## Intersection Summary

HCM 2010 AWSC  
105: West Avenue & 18 Street

---

Intersection												
Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↖			↖		↖	↖		↖	↖	
Traffic Vol, veh/h	70	15	98	6	11	12	97	161	17	14	84	80
Future Vol, veh/h	70	15	98	6	11	12	97	161	17	14	84	80
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	75	16	105	6	12	13	104	173	18	15	90	86
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB		WB			NB			SB			
Opposing Approach	WB		EB			SB			NB			
Opposing Lanes	1		1			1			1			
Conflicting Approach Left	SB		NB			EB			WB			
Conflicting Lanes Left	1		1			1			1			
Conflicting Approach Right	NB		SB			WB			EB			
Conflicting Lanes Right	1		1			1			1			
HCM Control Delay	9.7		8.5			10.8			9.2			
HCM LOS	A		A			B			A			
Lane	NBLn1	EBLn1	WBLn1	SBLn1								
Vol Left, %	35%	38%	21%	8%								
Vol Thru, %	59%	8%	38%	47%								
Vol Right, %	6%	54%	41%	45%								
Sign Control	Stop	Stop	Stop	Stop								
Traffic Vol by Lane	275	183	29	178								
LT Vol	97	70	6	14								
Through Vol	161	15	11	84								
RT Vol	17	98	12	80								
Lane Flow Rate	296	197	31	191								
Geometry Grp	1	1	1	1								
Degree of Util (X)	0.39	0.265	0.044	0.244								
Departure Headway (Hd)	4.75	4.854	5.136	4.597								
Convergence, Y/N	Yes	Yes	Yes	Yes								
Cap	754	736	690	775								
Service Time	2.804	2.917	3.22	2.657								
HCM Lane V/C Ratio	0.393	0.268	0.045	0.246								
HCM Control Delay	10.8	9.7	8.5	9.2								
HCM Lane LOS	B	A	A	A								
HCM 95th-tile Q	1.9	1.1	0.1	1								

HCM 2010 AWSC  
106: Bay Road & 18 Street

---

Intersection

Intersection Delay, s/veh 9

Intersection LOS A

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↖ ↗			↖ ↗			↖ ↗			↖ ↗	
Traffic Vol, veh/h	44	81	16	25	98	71	8	20	25	83	24	46
Future Vol, veh/h	44	81	16	25	98	71	8	20	25	83	24	46
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	48	88	17	27	107	77	9	22	27	90	26	50
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	8.9			9.1			8.2			9.2		
HCM LOS	A			A			A			A		

Lane	NBLn1	EBLn1	WBLn1	SBLn1
Vol Left, %	15%	31%	13%	54%
Vol Thru, %	38%	57%	51%	16%
Vol Right, %	47%	11%	37%	30%
Sign Control	Stop	Stop	Stop	Stop
Traffic Vol by Lane	53	141	194	153
LT Vol	8	44	25	83
Through Vol	20	81	98	24
RT Vol	25	16	71	46
Lane Flow Rate	58	153	211	166
Geometry Grp	1	1	1	1
Degree of Util (X)	0.076	0.2	0.261	0.22
Departure Headway (Hd)	4.732	4.708	4.463	4.767
Convergence, Y/N	Yes	Yes	Yes	Yes
Cap	753	760	803	750
Service Time	2.785	2.752	2.503	2.812
HCM Lane V/C Ratio	0.077	0.201	0.263	0.221
HCM Control Delay	8.2	8.9	9.1	9.2
HCM Lane LOS	A	A	A	A
HCM 95th-tile Q	0.2	0.7	1	0.8

HCM 2010 AWSC  
107: Purdy Avenue & 18 Street

---

Intersection

Intersection Delay, s/veh 9.7

Intersection LOS A

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↖ ↗			↖ ↗		↑ ↘	↑ ↗		↑ ↘	↑ ↗	
Traffic Vol, veh/h	12	18	28	93	8	43	14	109	103	23	126	4
Future Vol, veh/h	12	18	28	93	8	43	14	109	103	23	126	4
Peak Hour Factor	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	14	21	32	107	9	49	16	125	118	26	145	5
Number of Lanes	0	1	0	0	1	0	1	1	0	1	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			1			1		
HCM Control Delay	8.6			9.6			10.1			9.6		
HCM LOS	A			A			B			A		

Lane	NBLn1	NBLn2	EBLn1	WBLn1	SBLn1	SBLn2
Vol Left, %	100%	0%	21%	65%	100%	2%
Vol Thru, %	0%	51%	31%	6%	0%	95%
Vol Right, %	0%	49%	48%	30%	0%	3%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	14	212	58	144	21	132
LT Vol	14	0	12	93	21	2
Through Vol	0	109	18	8	0	126
RT Vol	0	103	28	43	0	4
Lane Flow Rate	16	244	67	166	24	152
Geometry Grp	7	7	2	2	7	7
Degree of Util (X)	0.026	0.336	0.092	0.232	0.039	0.226
Departure Headway (Hd)	5.808	4.961	4.993	5.039	5.877	5.36
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes
Cap	613	721	711	708	606	665
Service Time	3.573	2.725	3.072	3.104	3.648	3.13
HCM Lane V/C Ratio	0.026	0.338	0.094	0.234	0.04	0.229
HCM Control Delay	8.7	10.2	8.6	9.6	8.9	9.7
HCM Lane LOS	A	B	A	A	A	A
HCM 95th-tile Q	0.1	1.5	0.3	0.9	0.1	0.9

HCM 2010 AWSC  
108: West Avenue & 20 Street

---

Intersection

Intersection Delay, s/veh 11.1

Intersection LOS B

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	2	246	53	140	209	1	32	1	149	0	1	2
Future Vol, veh/h	2	246	53	140	209	1	32	1	149	0	1	2
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	2	267	58	152	227	1	35	1	162	0	1	2
Number of Lanes	0	1	0	1	1	0	0	1	0	0	1	0
Approach												
Opposing Approach	WB			WB			NB			SB		
Opposing Lanes	2			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			2		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			2			1		
HCM Control Delay	11.9			10.8			10.2			8.7		
HCM LOS	B			B			B			A		

Lane	NBLn1	EBLn1	WBLn1	WBLn2	SBLn1
Vol Left, %	18%	1%	100%	0%	0%
Vol Thru, %	1%	82%	0%	100%	33%
Vol Right, %	82%	18%	0%	0%	67%
Sign Control	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	182	301	140	210	3
LT Vol	32	2	140	0	0
Through Vol	1	246	0	209	1
RT Vol	149	53	0	1	2
Lane Flow Rate	198	327	152	228	3
Geometry Grp	2	5	7	7	2
Degree of Util (X)	0.279	0.444	0.247	0.338	0.005
Departure Headway (Hd)	5.085	4.886	5.844	5.337	5.625
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes
Cap	700	730	609	667	640
Service Time	3.166	2.965	3.63	3.122	3.625
HCM Lane V/C Ratio	0.283	0.448	0.25	0.342	0.005
HCM Control Delay	10.2	11.9	10.6	10.9	8.7
HCM Lane LOS	B	B	B	B	A
HCM 95th-tile Q	1.1	2.3	1	1.5	0

HCM 2010 AWSC  
109: Bay Road & 20 Street

---

**Intersection**

Intersection Delay, s/veh 10.3

Intersection LOS B

Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	101	10	78	211	20	153
Future Vol, veh/h	101	10	78	211	20	153
Peak Hour Factor	0.83	0.83	0.83	0.83	0.83	0.83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	122	12	94	254	24	184
Number of Lanes	1	0	0	1	1	0
Approach	EB	WB	NB			
Opposing Approach	WB	EB				
Opposing Lanes	1	1	0			
Conflicting Approach Left		NB	EB			
Conflicting Lanes Left	0	1	1			
Conflicting Approach Right	NB		WB			
Conflicting Lanes Right	1	0	1			
HCM Control Delay	8.9	11.4	9.2			
HCM LOS	A	B	A			

Lane	NBLn1	EBLn1	WBLn1
Vol Left, %	12%	0%	27%
Vol Thru, %	0%	91%	73%
Vol Right, %	88%	9%	0%
Sign Control	Stop	Stop	Stop
Traffic Vol by Lane	173	111	289
LT Vol	20	0	78
Through Vol	0	101	211
RT Vol	153	10	0
Lane Flow Rate	208	134	348
Geometry Grp	1	1	1
Degree of Util (X)	0.263	0.177	0.448
Departure Headway (Hd)	4.544	4.768	4.629
Convergence, Y/N	Yes	Yes	Yes
Cap	788	749	776
Service Time	2.588	2.822	2.674
HCM Lane V/C Ratio	0.264	0.179	0.448
HCM Control Delay	9.2	8.9	11.4
HCM Lane LOS	A	A	B
HCM 95th-tile Q	1.1	0.6	2.3

# HCM 2010 Signalized Intersection Summary

## 101: Dade Boulevard & Purdy Avenue


---



Movement	EBL	EBT	WBT	WBR	SBL	SBR		
Lane Configurations	↑ ↗	↑ ↘	↑ ↖		↑ ↗	↑ ↘		
Traffic Volume (veh/h)	149	532	626	62	70	173		
Future Volume (veh/h)	149	532	626	62	70	173		
Number	1	6	2	12	3	18		
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0		
Ped-Bike Adj(A_pbT)	1.00			0.97	1.00	1.00		
Parking Bus, Adj	1.00	1.00	1.00	0.90	0.90	0.90		
Adj Sat Flow, veh/h/in	1676	1676	1676	1710	1676	1676		
Adj Flow Rate, veh/h	162	578	680	67	76	188		
Adj No. of Lanes	1	1	1	0	1	1		
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92		
Percent Heavy Veh, %	2	2	2	2	2	2		
Cap, veh/h	364	1247	1002	99	234	209		
Arrive On Green	0.74	0.74	0.74	0.74	0.16	0.16		
Sat Flow, veh/h	639	1676	1348	133	1437	1282		
Grp Volume(v), veh/h	162	578	0	747	76	188		
Grp Sat Flow(s), veh/h/in	639	1676	0	1480	1437	1282		
Q Serve(g_s), s	22.8	17.5	0.0	33.9	6.1	18.7		
Cycle Q Clear(g_c), s	56.8	17.5	0.0	33.9	6.1	18.7		
Prop In Lane	1.00			0.09	1.00	1.00		
Lane Grp Cap(c), veh/h	364	1247	0	1101	234	209		
V/C Ratio(X)	0.45	0.46	0.00	0.68	0.32	0.90		
Avail Cap(c_a), veh/h	364	1247	0	1101	387	345		
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00		
Upstream Filter(I)	1.00	1.00	0.00	0.35	1.00	1.00		
Uniform Delay (d), s/veh	23.3	6.5	0.0	8.6	48.1	53.3		
Incr Delay (d2), s/veh	3.9	1.2	0.0	1.2	0.6	13.8		
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0		
%ile BackOfQ(50%), veh/in	4.4	8.5	0.0	14.1	2.4	7.4		
LnGrp Delay(d), s/veh	27.2	7.8	0.0	9.8	48.7	67.1		
LnGrp LOS	C	A		A	D	E		
Approach Vol, veh/h		740	747		264			
Approach Delay, s/veh		12.0	9.8		61.8			
Approach LOS		B	A		E			
Timer	1	2	3	4	5	6	7	8
Assigned Phs		2			6		8	
Phs Duration (G+Y+R <sub>c</sub> ), s		102.8			102.8		27.2	
Change Period (Y+R <sub>c</sub> ), s		6.1			6.1		6.0	
Max Green Setting (G <sub>max</sub> ), s		83.0			83.0		35.0	
Max Q Clear Time (g <sub>c+l1</sub> ), s		35.9			58.8		20.7	
Green Ext Time (p <sub>c</sub> ), s		2.0			2.1		0.5	
Intersection Summary								
HCM 2010 Ctrl Delay			18.6					
HCM 2010 LOS			B					

## Timings

### 101: Dade Boulevard & Purdy Avenue



Lane Group	EBL	EBT	WBT	SBL	SBR
Lane Configurations	↑ ↗	↑ ↘	↗ ↙	↖ ↗	↖ ↘
Traffic Volume (vph)	149	532	626	70	173
Future Volume (vph)	149	532	626	70	173
Turn Type	Perm	NA	NA	Prot	Perm
Protected Phases		6	2	8	
Permitted Phases		6			8
Detector Phase	6	6	2	8	8
Switch Phase					
Minimum Initial (s)	14.0	14.0	14.0	7.0	7.0
Minimum Split (s)	20.8	20.8	22.1	30.0	30.0
Total Split (s)	89.1	89.1	89.1	41.0	41.0
Total Split (%)	68.5%	68.5%	68.5%	31.5%	31.5%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.1	2.1	2.1	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.1	6.1	6.1	6.0	6.0
Lead/Lag					
Lead-Lag Optimize?					
Recall Mode	C-Min	C-Min	C-Min	None	None
Act Effect Green (s)	106.0	106.0	106.0	12.0	12.0
Actuated g/C Ratio	0.81	0.81	0.81	0.09	0.09
v/c Ratio	0.39	0.47	0.62	0.58	0.69
Control Delay	6.9	5.5	7.7	72.5	20.6
Queue Delay	0.0	0.0	2.0	0.0	0.0
Total Delay	6.9	5.5	9.6	72.5	20.6
LOS	A	A	A	E	C
Approach Delay		5.8	9.6	35.5	
Approach LOS		A	A	D	

#### Intersection Summary

Cycle Length: 130.1

Actuated Cycle Length: 130.1

Offset: 86 (66%), Referenced to phase 2:WBT and 6:EBTL, Start of Yellow

Natural Cycle: 80

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.69

Intersection Signal Delay: 11.9

Intersection LOS: B

Intersection Capacity Utilization 83.7%

ICU Level of Service E


Analysis Period (min) 15

Splits and Phases: 101: Dade Boulevard & Purdy Avenue



## Queues

## 101: Dade Boulevard &amp; Purdy Avenue



Lane Group	EBL	EBT	WBT	SBL	SBR
Lane Group Flow (vph)	162	578	747	76	188
v/c Ratio	0.39	0.47	0.62	0.58	0.69
Control Delay	6.9	5.5	7.7	72.5	20.6
Queue Delay	0.0	0.0	2.0	0.0	0.0
Total Delay	6.9	5.5	9.6	72.5	20.6
Queue Length 50th (ft)	29	117	184	63	0
Queue Length 95th (ft)	78	221	360	111	76
Internal Link Dist (ft)		273	491	484	
Turn Bay Length (ft)	80		100		
Base Capacity (vph)	418	1229	1213	385	438
Starvation Cap Reductn	0	0	305	0	0
Spillback Cap Reductn	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0
Reduced v/c Ratio	0.39	0.47	0.82	0.20	0.43


## Intersection Summary

HCM Signalized Intersection Capacity Analysis  
102: 17th Street/Bay Road & Dade Boulevard

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑	↑		↑	↑	↑	↑				↑
Traffic Volume (vph)	0	259	377	0	302	48	426	0	0	0	0	55
Future Volume (vph)	0	259	377	0	302	48	426	0	0	0	0	55
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.9	6.9		6.9		7.7					6.9
Lane Util. Factor	1.00	1.00	1.00		1.00		1.00					1.00
Frpb, ped/bikes	1.00	1.00		0.99		1.00						1.00
Flpb, ped/bikes	1.00	1.00		1.00		1.00						1.00
Fr <sub>t</sub>	1.00	0.85		0.98		1.00						0.86
Flt Protected	1.00	1.00		1.00		0.95						1.00
Satd. Flow (prot)	1509	1282		1469		1433						1233
Flt Permitted	1.00	1.00		1.00		0.95						1.00
Satd. Flow (perm)	1509	1282		1469		1433						1233
Peak-hour factor, PHF	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
Adj. Flow (vph)	0	298	433	0	347	55	490	0	0	0	0	63
RTOR Reduction (vph)	0	0	291	0	13	0	0	0	0	0	0	42
Lane Group Flow (vph)	0	298	142	0	389	0	490	0	0	0	0	21
Confl. Peds. (#/hr)	17				17			10	10			
Confl. Bikes (#/hr)		1			14			4				
Parking (#/hr)	0	0	0	0	0	0	0	0	0	0	0	10
Turn Type	NA	custom		NA		Prot						Perm
Protected Phases		6				4						
Permitted Phases	6			2								6
Actuated Green, G (s)	14.0	14.0		14.0		14.0						14.0
Effective Green, g (s)	14.0	14.0		14.0		14.0						14.0
Actuated g/C Ratio	0.33	0.33		0.33		0.33						0.33
Clearance Time (s)	6.9	6.9		6.9		7.7						6.9
Vehicle Extension (s)	2.5	2.5		2.5		3.5						2.5
Lane Grp Cap (vph)	495	421		482		470						405
v/s Ratio Prot		0.11				c0.34						
v/s Ratio Perm	0.20			c0.26								0.02
v/c Ratio	0.60	0.34		0.81		1.04						0.05
Uniform Delay, d1	12.0	10.8		13.1		14.3						9.8
Progression Factor	1.00	1.00		1.00		1.00						1.00
Incremental Delay, d2	1.7	0.3		9.3		53.0						0.0
Delay (s)	13.7	11.1		22.3		67.3						9.8
Level of Service	B	B		C		E						A
Approach Delay (s)	12.2			22.3		67.3						9.8
Approach LOS	B			C		E						A
<b>Intersection Summary</b>												
HCM 2000 Control Delay	30.5				HCM 2000 Level of Service			C				
HCM 2000 Volume to Capacity ratio	0.92											
Actuated Cycle Length (s)	42.6				Sum of lost time (s)			14.6				
Intersection Capacity Utilization	73.9%				ICU Level of Service			D				
Analysis Period (min)	15											
c Critical Lane Group												

## Timings

### 102: 17th Street/Bay Road & Dade Boulevard



Lane Group	EBT	EBR	WBT	NBL	SBR
Lane Configurations	↑	↑	↑	↑	↑
Traffic Volume (vph)	259	377	302	426	55
Future Volume (vph)	259	377	302	426	55
Turn Type	NA	custom	NA	Prot	Perm
Protected Phases			6		4
Permitted Phases				2	6
Detector Phase	6	6	2	4	6
Switch Phase					
Minimum Initial (s)	14.0	14.0	14.0	14.0	14.0
Minimum Split (s)	20.9	20.9	20.9	21.7	20.9
Total Split (s)	20.9	20.9	20.9	21.7	20.9
Total Split (%)	49.1%	49.1%	49.1%	50.9%	49.1%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.9	2.9	2.9	3.7	2.9
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.9	6.9	6.9	7.7	6.9
Lead/Lag					
Lead-Lag Optimize?					
Recall Mode	Min	Min	Min	None	Min
Act Effect Green (s)	14.0	14.0	14.0	14.0	14.0
Actuated g/C Ratio	0.33	0.33	0.33	0.33	0.33
v/c Ratio	0.60	0.61	0.81	1.04	0.12
Control Delay	18.3	5.9	29.4	73.9	0.6
Queue Delay	0.0	0.0	0.0	0.0	0.0
Total Delay	18.3	5.9	29.4	73.9	0.6
LOS	B	A	C	E	A
Approach Delay	10.9		29.4		
Approach LOS	B		C		

#### Intersection Summary

Cycle Length: 42.6

Actuated Cycle Length: 42.6

Natural Cycle: 60

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 1.04

Intersection Signal Delay: 33.3


Intersection LOS: C

Intersection Capacity Utilization 73.9%

ICU Level of Service D


Analysis Period (min) 15

Splits and Phases: 102: 17th Street/Bay Road & Dade Boulevard



## Queues

### 102: 17th Street/Bay Road & Dade Boulevard



Lane Group	EBT	EBR	WBT	NBL	SBR
Lane Group Flow (vph)	298	433	402	490	63
v/c Ratio	0.60	0.61	0.81	1.04	0.12
Control Delay	18.3	5.9	29.4	73.9	0.6
Queue Delay	0.0	0.0	0.0	0.0	0.0
Total Delay	18.3	5.9	29.4	73.9	0.6
Queue Length 50th (ft)	58	0	82	~124	0
Queue Length 95th (ft)	113	41	#195	#259	1
Internal Link Dist (ft)	491		508		
Turn Bay Length (ft)					
Base Capacity (vph)	495	712	496	470	507
Starvation Cap Reductn	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0
Reduced v/c Ratio	0.60	0.61	0.81	1.04	0.12

#### Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.  
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.


# HCM 2010 Signalized Intersection Summary

103: West Avenue & Dade Boulevard

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑		↑	↑↑			↑			↑	
Traffic Volume (veh/h)	10	233	0	81	274	131	9	137	96	83	111	29
Future Volume (veh/h)	10	233	0	81	274	131	9	137	96	83	111	29
Number	7	4	14	3	8	18	5	2	12	1	6	16
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A <sub>pbT</sub> )	1.00			1.00	1.00		0.97	0.98		0.93	0.98	0.94
Parking Bus, Adj	1.00	0.90	1.00	1.00	1.00	0.90	1.00	1.00	0.90	1.00	1.00	0.90
Adj Sat Flow, veh/h/ln	1676	1676	1710	1676	1676	1710	1710	1676	1710	1710	1676	1710
Adj Flow Rate, veh/h	11	248	0	86	291	139	10	146	102	88	118	31
Adj No. of Lanes	1	1	0	1	2	0	0	1	0	0	1	0
Peak Hour Factor	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	483	711	0	531	937	433	88	210	141	203	202	44
Arrive On Green	0.47	0.47	0.00	0.47	0.47	0.47	0.26	0.26	0.26	0.26	0.26	0.26
Sat Flow, veh/h	856	1509	0	1011	1988	919	20	800	536	356	772	170
Grp Volume(v), veh/h	11	248	0	86	231	199	258	0	0	237	0	0
Grp Sat Flow(s),veh/h/ln	856	1509	0	1011	1593	1315	1356	0	0	1297	0	0
Q Serve(g_s), s	0.4	4.7	0.0	2.6	4.0	4.2	0.4	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	4.6	4.7	0.0	7.3	4.0	4.2	7.7	0.0	0.0	6.9	0.0	0.0
Prop In Lane	1.00			1.00		0.70	0.04		0.40	0.37		0.13
Lane Grp Cap(c), veh/h	483	711	0	531	750	619	439	0	0	450	0	0
V/C Ratio(X)	0.02	0.35	0.00	0.16	0.31	0.32	0.59	0.00	0.00	0.53	0.00	0.00
Avail Cap(c_a), veh/h	483	711	0	531	750	619	564	0	0	559	0	0
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.77	0.77	0.00	1.00	1.00	1.00	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	8.8	7.5	0.0	9.9	7.4	7.4	15.1	0.0	0.0	14.7	0.0	0.0
Incr Delay (d2), s/veh	0.1	1.0	0.0	0.7	1.1	1.4	1.3	0.0	0.0	1.0	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.1	2.1	0.0	0.8	2.0	1.7	3.0	0.0	0.0	2.8	0.0	0.0
LnGrp Delay(d),s/veh	8.9	8.6	0.0	10.5	8.4	8.8	16.4	0.0	0.0	15.7	0.0	0.0
LnGrp LOS	A	A		B	A	A	B			B		
Approach Vol, veh/h	259				516			258			237	
Approach Delay, s/veh	8.6				8.9			16.4			15.7	
Approach LOS	A				A			B			B	
Timer	1	2	3	4	5	6	7	8				
Assigned Phs	2			4		6		8				
Phs Duration (G+Y+R <sub>c</sub> ), s	17.8			27.2		17.8		27.2				
Change Period (Y+R <sub>c</sub> ), s	6.0			6.0		6.0		6.0				
Max Green Setting (G <sub>max</sub> ), s	16.0			17.0		16.0		17.0				
Max Q Clear Time (g <sub>c+l1</sub> ), s	9.7			6.7		8.9		9.3				
Green Ext Time (p <sub>c</sub> ), s	0.8			1.0		0.8		1.8				
Intersection Summary												
HCM 2010 Ctrl Delay				11.6								
HCM 2010 LOS				B								

## Timings

### 103: West Avenue & Dade Boulevard



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations	↑	→	↓	↑→		↔		↓
Traffic Volume (vph)	10	233	81	274	9	137	83	111
Future Volume (vph)	10	233	81	274	9	137	83	111
Turn Type	Perm	NA	Perm	NA	Perm	NA	Perm	NA
Protected Phases				4		8		2
Permitted Phases					2		6	
Detector Phase	4	4	8	8	2	2	6	6
Switch Phase								
Minimum Initial (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Split (s)	22.0	22.0	22.0	22.0	22.0	22.0	22.0	22.0
Total Split (s)	23.0	23.0	23.0	23.0	22.0	22.0	22.0	22.0
Total Split (%)	51.1%	51.1%	51.1%	51.1%	48.9%	48.9%	48.9%	48.9%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0		0.0		0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0		6.0		6.0
Lead/Lag								
Lead-Lag Optimize?								
Recall Mode	C-Max	C-Max	C-Max	C-Max	Min	Min	Min	Min
Act Effect Green (s)	20.3	20.3	20.3	20.3		12.7		12.7
Actuated g/C Ratio	0.45	0.45	0.45	0.45		0.28		0.28
v/c Ratio	0.03	0.36	0.21	0.32		0.58		0.69
Control Delay	9.1	11.5	10.9	6.8		14.3		23.7
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0
Total Delay	9.1	11.5	10.9	6.8		14.3		23.7
LOS	A	B	B	A		B		C
Approach Delay		11.4			7.5		14.3	23.7
Approach LOS		B		A		B		C

#### Intersection Summary

Cycle Length: 45

Actuated Cycle Length: 45

Offset: 22 (49%), Referenced to phase 4:EBTL and 8:WBTL, Start of Yellow

Natural Cycle: 45

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.69

Intersection Signal Delay: 12.7


Intersection LOS: B

Intersection Capacity Utilization 68.3%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 103: West Avenue & Dade Boulevard



## Queues

## 103: West Avenue &amp; Dade Boulevard



Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	11	248	86	430	258	237
v/c Ratio	0.03	0.36	0.21	0.32	0.58	0.69
Control Delay	9.1	11.5	10.9	6.8	14.3	23.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	9.1	11.5	10.9	6.8	14.3	23.7
Queue Length 50th (ft)	2	40	13	23	36	47
Queue Length 95th (ft)	9	93	39	51	82	98
Internal Link Dist (ft)		508		381	432	477
Turn Bay Length (ft)						
Base Capacity (vph)	340	682	411	1365	538	427
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.03	0.36	0.21	0.32	0.48	0.56

Intersection Summary


# HCM 2010 Signalized Intersection Summary

## 104: West Avenue & 17th Street

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	16	181	198	129	230	38	176	228	193	16	178	1
Future Volume (veh/h)	16	181	198	129	230	38	176	228	193	16	178	1
Number	1	6	16	5	2	12	7	4	14	3	8	18
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A <sub>pbT</sub> )	0.96			1.00		0.92	0.97		0.94	1.00		0.92
Parking Bus, Adj	1.00	1.00	0.90	1.00	1.00	0.90	1.00	1.00	0.85	1.00	1.00	0.90
Adj Sat Flow, veh/h/ln	1710	1676	1710	1676	1676	1710	1676	1676	1710	1676	1676	1710
Adj Flow Rate, veh/h	17	189	206	134	240	40	183	238	201	17	185	1
Adj No. of Lanes	0	2	0	1	1	0	1	1	0	1	1	0
Peak Hour Factor	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	65	650	454	111	670	112	343	254	215	86	550	3
Arrive On Green	0.42	0.42	0.42	0.07	0.54	0.54	0.37	0.37	0.37	0.37	0.37	0.37
Sat Flow, veh/h	83	1530	1069	1597	1245	207	1037	694	586	852	1498	8
Grp Volume(v), veh/h	206	0	206	134	0	280	183	0	439	17	0	186
Grp Sat Flow(s),veh/h/ln	1613	0	1069	1597	0	1452	1037	0	1279	852	0	1507
Q Serve(g_s), s	0.0	0.0	17.9	9.0	0.0	14.3	20.1	0.0	43.0	2.6	0.0	11.6
Cycle Q Clear(g_c), s	10.5	0.0	17.9	9.0	0.0	14.3	31.7	0.0	43.0	45.6	0.0	11.6
Prop In Lane	0.08		1.00	1.00		0.14	1.00		0.46	1.00		0.01
Lane Grp Cap(c), veh/h	715	0	454	111	0	781	343	0	469	86	0	553
V/C Ratio(X)	0.29	0.00	0.45	1.21	0.00	0.36	0.53	0.00	0.94	0.20	0.00	0.34
Avail Cap(c_a), veh/h	715	0	454	111	0	781	354	0	482	95	0	568
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00
Uniform Delay (d), s/veh	24.5	0.0	26.6	60.5	0.0	17.2	41.2	0.0	39.7	61.6	0.0	29.7
Incr Delay (d2), s/veh	1.0	0.0	3.2	153.4	0.0	1.3	1.1	0.0	25.3	0.8	0.0	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.1	0.0	5.7	8.7	0.0	6.0	5.9	0.0	18.4	0.6	0.0	4.8
LnGrp Delay(d),s/veh	25.5	0.0	29.9	213.9	0.0	18.5	42.3	0.0	65.0	62.5	0.0	30.0
LnGrp LOS	C		C	F		B	D		E	E		C
Approach Vol, veh/h	412			414				622			203	
Approach Delay, s/veh	27.7			81.7				58.3			32.7	
Approach LOS	C			F			E			C		
Timer	1	2	3	4	5	6	7	8				
Assigned Phs	2		4	5	6		8					
Phs Duration (G+Y+R <sub>c</sub> ), s	76.1		53.9	14.7	61.4		53.9					
Change Period (Y+R <sub>c</sub> ), s	* 6.2		* 6.2	* 5.7	* 6.2		* 6.2					
Max Green Setting (G <sub>max</sub> ), s	* 69		* 49	* 9	* 54		* 49					
Max Q Clear Time (g <sub>c+l1</sub> ), s	16.3		45.0	11.0	19.9		47.6					
Green Ext Time (p <sub>c</sub> ), s	0.6		1.2	0.0	1.0		0.1					
<b>Intersection Summary</b>												
HCM 2010 Ctrl Delay	53.4											
HCM 2010 LOS	D											
Notes												

## Timings

### 104: West Avenue & 17th Street



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations								
Traffic Volume (vph)	16	181	129	230	176	228	16	178
Future Volume (vph)	16	181	129	230	176	228	16	178
Turn Type	Perm	NA	Prot	NA	Perm	NA	Perm	NA
Protected Phases		6	5	2		4		8
Permitted Phases	6				4		8	
Detector Phase	6	6	5	2	4	4	8	8
Switch Phase								
Minimum Initial (s)	7.0	7.0	5.0	7.0	7.0	7.0	7.0	7.0
Minimum Split (s)	37.2	37.2	12.0	37.2	35.2	35.2	32.2	32.2
Total Split (s)	60.2	60.2	14.7	75.2	55.2	55.2	55.2	55.2
Total Split (%)	46.2%	46.2%	11.3%	57.7%	42.3%	42.3%	42.3%	42.3%
Yellow Time (s)	4.0	4.0	3.7	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.2	2.2	2.0	2.2	2.2	2.2	2.2	2.2
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.2	5.7	6.2	6.2	6.2	6.2	6.2	6.2
Lead/Lag	Lag	Lag	Lead					
Lead-Lag Optimize?	Yes	Yes	Yes					
Recall Mode	C-Min	C-Min	None	C-Min	Min	Min	Min	Min
Act Effect Green (s)	42.0	25.1	72.8	45.2	45.2	45.2	45.2	45.2
Actuated g/C Ratio	0.32	0.19	0.56	0.35	0.35	0.35	0.35	0.35
v/c Ratio	0.44	0.50	0.34	0.66	0.89	0.12	0.36	
Control Delay	19.4	55.6	18.2	46.6	57.0	28.1	32.4	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	19.4	55.6	18.2	46.6	57.0	28.1	32.4	
LOS	B	E	B	D	E	C	C	
Approach Delay	19.4		30.3		54.0		32.0	
Approach LOS	B		C		D		C	

#### Intersection Summary

Cycle Length: 130.4

Actuated Cycle Length: 130.4

Offset: 114 (87%), Referenced to phase 2:WBT and 6:EBTL, Start of Yellow

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.89

Intersection Signal Delay: 36.7


Intersection LOS: D

Intersection Capacity Utilization 106.1%

ICU Level of Service G

Analysis Period (min) 15

Splits and Phases: 104: West Avenue & 17th Street



## Queues

104: West Avenue &amp; 17th Street



Lane Group	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Group Flow (vph)	412	134	280	183	439	17	186
v/c Ratio	0.44	0.50	0.34	0.66	0.89	0.12	0.36
Control Delay	19.4	55.6	18.2	46.6	57.0	28.1	32.4
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	19.4	55.6	18.2	46.6	57.0	28.1	32.4
Queue Length 50th (ft)	68	105	122	128	320	10	115
Queue Length 95th (ft)	129	174	212	199	431	27	164
Internal Link Dist (ft)	476		364		407		104
Turn Bay Length (ft)		160		170		50	
Base Capacity (vph)	1137	266	830	311	546	153	583
Starvation Cap Reductn	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0
Reduced v/c Ratio	0.36	0.50	0.34	0.59	0.80	0.11	0.32

Intersection Summary

HCM 2010 AWSC  
105: West Avenue & 18 Street

---

Intersection

Intersection Delay, s/veh 10.2

Intersection LOS B

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↖			↖			↖			↖	
Traffic Vol, veh/h	72	15	111	6	12	13	100	166	17	14	87	83
Future Vol, veh/h	72	15	111	6	12	13	100	166	17	14	87	83
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	77	16	119	6	13	14	108	178	18	15	94	89
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	10			8.6			11.2			9.3		
HCM LOS	A			A			B			A		

Lane	NBLn1	EBLn1	WBLn1	SBLn1
Vol Left, %	35%	36%	19%	8%
Vol Thru, %	59%	8%	39%	47%
Vol Right, %	6%	56%	42%	45%
Sign Control	Stop	Stop	Stop	Stop
Traffic Vol by Lane	283	198	31	184
LT Vol	100	72	6	14
Through Vol	166	15	12	87
RT Vol	17	111	13	83
Lane Flow Rate	304	213	33	198
Geometry Grp	1	1	1	1
Degree of Util (X)	0.406	0.289	0.048	0.256
Departure Headway (Hd)	4.809	4.88	5.199	4.659
Convergence, Y/N	Yes	Yes	Yes	Yes
Cap	742	730	680	764
Service Time	2.874	2.952	3.297	2.73
HCM Lane V/C Ratio	0.41	0.292	0.049	0.259
HCM Control Delay	11.2	10	8.6	9.3
HCM Lane LOS	B	A	A	A
HCM 95th-tile Q	2	1.2	0.2	1

HCM 2010 AWSC  
106: Bay Road & 18 Street

---

Intersection

Intersection Delay, s/veh 9.1

Intersection LOS A

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↖			↖			↖			↖	
Traffic Vol, veh/h	45	85	16	26	101	73	9	26	35	86	25	47
Future Vol, veh/h	45	85	16	26	101	73	9	26	35	86	25	47
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	49	92	17	28	110	79	10	28	38	93	27	51
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	9.1			9.3			8.4			9.3		
HCM LOS	A			A			A			A		

Lane	NBLn1	EBLn1	WBLn1	SBLn1
Vol Left, %	13%	31%	13%	54%
Vol Thru, %	37%	58%	51%	16%
Vol Right, %	50%	11%	36%	30%
Sign Control	Stop	Stop	Stop	Stop
Traffic Vol by Lane	70	146	200	158
LT Vol	9	45	26	86
Through Vol	26	85	101	25
RT Vol	35	16	73	47
Lane Flow Rate	76	159	217	172
Geometry Grp	1	1	1	1
Degree of Util (X)	0.101	0.211	0.274	0.231
Departure Headway (Hd)	4.759	4.784	4.535	4.832
Convergence, Y/N	Yes	Yes	Yes	Yes
Cap	748	746	789	740
Service Time	2.822	2.839	2.585	2.886
HCM Lane V/C Ratio	0.102	0.213	0.275	0.232
HCM Control Delay	8.4	9.1	9.3	9.3
HCM Lane LOS	A	A	A	A
HCM 95th-tile Q	0.3	0.8	1.1	0.9

HCM 2010 AWSC  
107: Purdy Avenue & 18 Street

---

Intersection

Intersection Delay, s/veh 9.9

Intersection LOS A

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	13	18	29	95	9	44	14	113	107	24	130	4
Future Vol, veh/h	13	18	29	95	9	44	14	113	107	24	130	4
Peak Hour Factor	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	15	21	33	109	10	51	16	130	123	28	149	5
Number of Lanes	0	1	0	0	1	0	1	1	0	1	1	0
Approach												
Opposing Approach	WB		WB			NB			SB			
Opposing Lanes	1		1			2			2			
Conflicting Approach Left	SB		NB			EB			WB			
Conflicting Lanes Left	2		2			1			1			
Conflicting Approach Right	NB		SB			WB			EB			
Conflicting Lanes Right	2		2			1			1			
HCM Control Delay	8.7		9.8			10.4			9.7			
HCM LOS	A		A			B			A			

Lane	NBLn1	NBLn2	EBLn1	WBLn1	SBLn1	SBLn2
Vol Left, %	100%	0%	22%	64%	100%	2%
Vol Thru, %	0%	51%	30%	6%	0%	95%
Vol Right, %	0%	49%	48%	30%	0%	3%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	14	220	60	148	22	136
LT Vol	14	0	13	95	22	2
Through Vol	0	113	18	9	0	130
RT Vol	0	107	29	44	0	4
Lane Flow Rate	16	253	69	170	25	157
Geometry Grp	7	7	2	2	7	7
Degree of Util (X)	0.026	0.351	0.097	0.24	0.041	0.235
Departure Headway (Hd)	5.838	4.99	5.042	5.082	5.911	5.394
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes
Cap	610	716	703	701	602	660
Service Time	3.608	2.76	3.13	3.154	3.688	3.171
HCM Lane V/C Ratio	0.026	0.353	0.098	0.243	0.042	0.238
HCM Control Delay	8.8	10.5	8.7	9.8	8.9	9.8
HCM Lane LOS	A	B	A	A	A	A
HCM 95th-tile Q	0.1	1.6	0.3	0.9	0.1	0.9

HCM 2010 AWSC  
108: West Avenue & 20 Street

---

Intersection

Intersection Delay, s/veh 11.2

Intersection LOS B

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↔		↑	↔			↔			↔	
Traffic Vol, veh/h	2	254	55	145	215	1	33	1	153	0	1	2
Future Vol, veh/h	2	254	55	145	215	1	33	1	153	0	1	2
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	2	276	60	158	234	1	36	1	166	0	1	2
Number of Lanes	0	1	0	1	1	0	0	1	0	0	1	0
Approach	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	2			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			2		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			2			1		
HCM Control Delay	12.2			10.9			10.3			8.7		
HCM LOS	B			B			B			A		

Lane	NBLn1	EBLn1	WBLn1	WBLn2	SBLn1
Vol Left, %	18%	1%	100%	0%	0%
Vol Thru, %	1%	82%	0%	100%	33%
Vol Right, %	82%	18%	0%	0%	67%
Sign Control	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	187	311	145	216	3
LT Vol	33	2	145	0	0
Through Vol	1	254	0	215	1
RT Vol	153	55	0	1	2
Lane Flow Rate	203	338	158	235	3
Geometry Grp	2	5	7	7	2
Degree of Util (X)	0.29	0.462	0.257	0.35	0.005
Departure Headway (Hd)	5.133	4.918	5.876	5.368	5.704
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes
Cap	693	723	605	662	631
Service Time	3.221	3.004	3.669	3.161	3.704
HCM Lane V/C Ratio	0.293	0.467	0.261	0.355	0.005
HCM Control Delay	10.3	12.2	10.7	11.1	8.7
HCM Lane LOS	B	B	B	B	A
HCM 95th-tile Q	1.2	2.5	1	1.6	0

HCM 2010 AWSC  
109: Bay Road & 20 Street

---

Intersection						
Movement	EBT	EBR	WBL	WBT	NBL	NBR
Lane Configurations						
Traffic Vol, veh/h	103	10	80	215	20	156
Future Vol, veh/h	103	10	80	215	20	156
Peak Hour Factor	0.83	0.83	0.83	0.83	0.83	0.83
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	124	12	96	259	24	188
Number of Lanes	1	0	0	1	1	0
Approach	EB	WB	NB			
Opposing Approach	WB	EB				
Opposing Lanes	1	1	0			
Conflicting Approach Left		NB	EB			
Conflicting Lanes Left	0	1	1			
Conflicting Approach Right	NB		WB			
Conflicting Lanes Right	1	0	1			
HCM Control Delay	8.9	11.6	9.3			
HCM LOS	A	B	A			
Lane	NBLn1	EBLn1	WBLn1			
Vol Left, %	11%	0%	27%			
Vol Thru, %	0%	91%	73%			
Vol Right, %	89%	9%	0%			
Sign Control	Stop	Stop	Stop			
Traffic Vol by Lane	176	113	295			
LT Vol	20	0	80			
Through Vol	0	103	215			
RT Vol	156	10	0			
Lane Flow Rate	212	136	355			
Geometry Grp	1	1	1			
Degree of Util (X)	0.269	0.181	0.458			
Departure Headway (Hd)	4.566	4.788	4.643			
Convergence, Y/N	Yes	Yes	Yes			
Cap	785	745	771			
Service Time	2.612	2.845	2.691			
HCM Lane V/C Ratio	0.27	0.183	0.46			
HCM Control Delay	9.3	8.9	11.6			
HCM Lane LOS	A	A	B			
HCM 95th-tile Q	1.1	0.7	2.4			

# HCM 2010 Signalized Intersection Summary

## 101: Dade Boulevard & Purdy Avenue


---



Movement	EBL	EBT	WBT	WBR	SBL	SBR
Lane Configurations	1	6	2	12	3	18
Traffic Volume (veh/h)	170	521	626	109	70	173
Future Volume (veh/h)	170	521	626	109	70	173
Number	1	0	0	0	0	0
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0
Ped-Bike Adj(A_pbT)	1.00			0.97	1.00	1.00
Parking Bus, Adj	1.00	1.00	1.00	0.90	0.90	0.90
Adj Sat Flow, veh/h/ln	1676	1676	1676	1710	1676	1676
Adj Flow Rate, veh/h	185	566	680	118	76	188
Adj No. of Lanes	1	1	1	0	1	1
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92
Percent Heavy Veh, %	2	2	2	2	2	2
Cap, veh/h	321	1247	927	161	234	209
Arrive On Green	0.74	0.74	0.74	0.74	0.16	0.16
Sat Flow, veh/h	609	1676	1246	216	1437	1282
Grp Volume(v), veh/h	185	566	0	798	76	188
Grp Sat Flow(s), veh/h/ln	609	1676	0	1463	1437	1282
Q Serve(g_s), s	32.0	17.0	0.0	40.0	6.1	18.7
Cycle Q Clear(g_c), s	71.9	17.0	0.0	40.0	6.1	18.7
Prop In Lane	1.00			0.15	1.00	1.00
Lane Grp Cap(c), veh/h	321	1247	0	1088	234	209
V/C Ratio(X)	0.58	0.45	0.00	0.73	0.32	0.90
Avail Cap(c_a), veh/h	321	1247	0	1088	387	345
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	1.00	0.00	0.20	1.00	1.00
Uniform Delay (d), s/veh	29.7	6.4	0.0	9.4	48.1	53.3
Incr Delay (d2), s/veh	7.3	1.2	0.0	0.9	0.6	13.8
Initial Q Delay(d3), s/veh	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%), veh/ln	6.0	8.1	0.0	16.2	2.4	7.4
LnGrp Delay(d), s/veh	37.0	7.6	0.0	10.3	48.7	67.1
LnGrp LOS	D	A	B	D	E	
Approach Vol, veh/h	751	798		264		
Approach Delay, s/veh	14.9	10.3		61.8		
Approach LOS	B	B		E		
Timer	1	2	3	4	5	6
Assigned Phs		2			6	8
Phs Duration (G+Y+R <sub>c</sub> ), s	102.8			102.8	27.2	
Change Period (Y+R <sub>c</sub> ), s	6.1			6.1	6.0	
Max Green Setting (G <sub>max</sub> ), s	83.0			83.0	35.0	
Max Q Clear Time (g <sub>c+l1</sub> ), s	42.0			73.9	20.7	
Green Ext Time (p <sub>c</sub> ), s	2.2			1.7	0.5	
Intersection Summary						
HCM 2010 Ctrl Delay		19.7				
HCM 2010 LOS		B				

## Timings

### 101: Dade Boulevard & Purdy Avenue



Lane Group	EBL	EBT	WBT	SBL	SBR
Lane Configurations	↑ ↗	↑ ↘	↗ ↙	↑ ↗	↑ ↘
Traffic Volume (vph)	170	521	626	70	173
Future Volume (vph)	170	521	626	70	173
Turn Type	Perm	NA	NA	Prot	Perm
Protected Phases		6	2	8	
Permitted Phases		6			8
Detector Phase		6	2	8	8
Switch Phase					
Minimum Initial (s)	14.0	14.0	14.0	7.0	7.0
Minimum Split (s)	20.8	20.8	22.1	30.0	30.0
Total Split (s)	89.1	89.1	89.1	41.0	41.0
Total Split (%)	68.5%	68.5%	68.5%	31.5%	31.5%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.1	2.1	2.1	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.1	6.1	6.1	6.0	6.0
Lead/Lag					
Lead-Lag Optimize?					
Recall Mode	C-Min	C-Min	C-Min	None	None
Act Effect Green (s)	106.0	106.0	106.0	12.0	12.0
Actuated g/C Ratio	0.81	0.81	0.81	0.09	0.09
v/c Ratio	0.47	0.46	0.66	0.58	0.69
Control Delay	9.0	5.4	8.7	72.5	20.6
Queue Delay	0.0	0.0	2.5	0.0	0.0
Total Delay	9.0	5.4	11.2	72.5	20.6
LOS	A	A	B	E	C
Approach Delay		6.3	11.2	35.5	
Approach LOS		A	B	D	

#### Intersection Summary

Cycle Length: 130.1

Actuated Cycle Length: 130.1

Offset: 86 (66%), Referenced to phase 2:WBT and 6:EBTL, Start of Yellow

Natural Cycle: 90

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.69

Intersection Signal Delay: 12.7

Intersection LOS: B

Intersection Capacity Utilization 86.9%

ICU Level of Service E


Analysis Period (min) 15

Splits and Phases: 101: Dade Boulevard & Purdy Avenue



## Queues

### 101: Dade Boulevard & Purdy Avenue



Lane Group	EBL	EBT	WBT	SBL	SBR
Lane Group Flow (vph)	185	566	798	76	188
v/c Ratio	0.47	0.46	0.66	0.58	0.69
Control Delay	9.0	5.4	8.7	72.5	20.6
Queue Delay	0.0	0.0	2.5	0.0	0.0
Total Delay	9.0	5.4	11.2	72.5	20.6
Queue Length 50th (ft)	37	113	212	63	0
Queue Length 95th (ft)	105	214	422	111	76
Internal Link Dist (ft)		273	491	484	
Turn Bay Length (ft)	80		100		
Base Capacity (vph)	390	1229	1202	385	438
Starvation Cap Reductn	0	0	273	0	0
Spillback Cap Reductn	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0
Reduced v/c Ratio	0.47	0.46	0.86	0.20	0.43


### Intersection Summary

HCM Signalized Intersection Capacity Analysis  
102: 17th Street/Bay Road & Dade Boulevard

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations		↑	↑		↑	↑	↑	↑				↑
Traffic Volume (vph)	0	259	377	0	292	69	426	0	0	0	0	124
Future Volume (vph)	0	259	377	0	292	69	426	0	0	0	0	124
Ideal Flow (vphpl)	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900	1900
Total Lost time (s)		6.9	6.9		6.9		7.7					6.9
Lane Util. Factor	1.00	1.00	1.00		1.00		1.00					1.00
Frpb, ped/bikes	1.00	1.00		0.99		1.00						1.00
Flpb, ped/bikes	1.00	1.00		1.00		1.00						1.00
Fr <sub>t</sub>	1.00	0.85		0.97		1.00						0.86
Flt Protected	1.00	1.00		1.00		0.95						1.00
Satd. Flow (prot)	1509	1282		1453		1433						1233
Flt Permitted	1.00	1.00		1.00		0.95						1.00
Satd. Flow (perm)	1509	1282		1453		1433						1233
Peak-hour factor, PHF	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
Adj. Flow (vph)	0	298	433	0	336	79	490	0	0	0	0	143
RTOR Reduction (vph)	0	0	291	0	23	0	0	0	0	0	0	94
Lane Group Flow (vph)	0	298	142	0	392	0	490	0	0	0	0	49
Confl. Peds. (#/hr)	17				17			10	10			
Confl. Bikes (#/hr)		1			14			4				
Parking (#/hr)	0	0	0	0	0	0	0	0	0	0	0	10
Turn Type	NA	custom		NA		Prot						Perm
Protected Phases		6				4						
Permitted Phases	6			2								6
Actuated Green, G (s)	12.0	12.0		12.0		10.0						12.0
Effective Green, g (s)	12.0	12.0		12.0		10.0						12.0
Actuated g/C Ratio	0.33	0.33		0.33		0.27						0.33
Clearance Time (s)	6.9	6.9		6.9		7.7						6.9
Vehicle Extension (s)	2.5	2.5		2.5		3.5						2.5
Lane Grp Cap (vph)	494	420		476		391						404
v/s Ratio Prot		0.11				c0.34						
v/s Ratio Perm	0.20			c0.27								0.04
v/c Ratio	0.60	0.34		0.82		1.25						0.12
Uniform Delay, d1	10.3	9.3		11.3		13.3						8.6
Progression Factor	1.00	1.00		1.00		1.00						1.00
Incremental Delay, d2	1.8	0.3		10.8		133.4						0.1
Delay (s)	12.1	9.6		22.2		146.7						8.7
Level of Service	B	A		C		F						A
Approach Delay (s)	10.6			22.2		146.7						8.7
Approach LOS	B			C		F						A
<b>Intersection Summary</b>												
HCM 2000 Control Delay	50.6				HCM 2000 Level of Service			D				
HCM 2000 Volume to Capacity ratio	1.02											
Actuated Cycle Length (s)	36.6				Sum of lost time (s)			14.6				
Intersection Capacity Utilization	73.1%				ICU Level of Service			D				
Analysis Period (min)	15											
c Critical Lane Group												

## Timings

### 102: 17th Street/Bay Road & Dade Boulevard



Lane Group	EBT	EBR	WBT	NBL	SBR
Lane Configurations	↑	↑	↑	↑	↑
Traffic Volume (vph)	259	377	292	426	124
Future Volume (vph)	259	377	292	426	124
Turn Type	NA	custom	NA	Prot	Perm
Protected Phases			6		4
Permitted Phases	6			2	
Detector Phase	6	6	2	4	6
Switch Phase					
Minimum Initial (s)	12.0	12.0	12.0	10.0	12.0
Minimum Split (s)	18.9	18.9	18.9	17.7	18.9
Total Split (s)	18.9	18.9	18.9	17.7	18.9
Total Split (%)	51.6%	51.6%	51.6%	48.4%	51.6%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.9	2.9	2.9	3.7	2.9
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)	6.9	6.9	6.9	7.7	6.9
Lead/Lag					
Lead-Lag Optimize?					
Recall Mode	Min	Min	Min	None	Min
Act Effect Green (s)	12.0	12.0	12.0	10.0	12.0
Actuated g/C Ratio	0.33	0.33	0.33	0.27	0.33
v/c Ratio	0.60	0.61	0.83	1.25	0.29
Control Delay	16.8	5.7	29.7	154.1	4.2
Queue Delay	0.0	0.0	0.0	0.0	0.0
Total Delay	16.8	5.7	29.7	154.1	4.2
LOS	B	A	C	F	A
Approach Delay	10.2		29.7		
Approach LOS	B		C		

#### Intersection Summary

Cycle Length: 36.6

Actuated Cycle Length: 36.6

Natural Cycle: 65

Control Type: Actuated-Uncoordinated

Maximum v/c Ratio: 1.25

Intersection Signal Delay: 53.9


Intersection LOS: D

Intersection Capacity Utilization 73.1%

ICU Level of Service D


Analysis Period (min) 15

Splits and Phases: 102: 17th Street/Bay Road & Dade Boulevard



## Queues

### 102: 17th Street/Bay Road & Dade Boulevard



Lane Group	EBT	EBR	WBT	NBL	SBR
Lane Group Flow (vph)	298	433	415	490	143
v/c Ratio	0.60	0.61	0.83	1.25	0.29
Control Delay	16.8	5.7	29.7	154.1	4.2
Queue Delay	0.0	0.0	0.0	0.0	0.0
Total Delay	16.8	5.7	29.7	154.1	4.2
Queue Length 50th (ft)	48	0	67	~133	1
Queue Length 95th (ft)	95	36	#174	#241	22
Internal Link Dist (ft)	491		508		
Turn Bay Length (ft)					
Base Capacity (vph)	494	711	499	391	498
Starvation Cap Reductn	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0
Reduced v/c Ratio	0.60	0.61	0.83	1.25	0.29

#### Intersection Summary

- ~ Volume exceeds capacity, queue is theoretically infinite.  
Queue shown is maximum after two cycles.
- # 95th percentile volume exceeds capacity, queue may be longer.  
Queue shown is maximum after two cycles.


# HCM 2010 Signalized Intersection Summary

103: West Avenue & Dade Boulevard

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations	↑	↑		↑	↑↑			↓			↓	
Traffic Volume (veh/h)	10	233	0	81	285	131	9	148	96	104	124	29
Future Volume (veh/h)	10	233	0	81	285	131	9	148	96	104	124	29
Number	7	4	14	3	8	18	5	2	12	1	6	16
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A <sub>pbT</sub> )	1.00			1.00	0.99		0.97	0.99		0.95	0.99	0.95
Parking Bus, Adj	1.00	0.90	1.00	1.00	1.00	0.90	1.00	1.00	0.90	1.00	1.00	0.90
Adj Sat Flow, veh/h/ln	1676	1676	1710	1676	1676	1710	1710	1676	1710	1710	1676	1710
Adj Flow Rate, veh/h	11	248	0	86	303	139	10	157	102	111	132	31
Adj No. of Lanes	1	1	0	1	2	0	0	1	0	0	1	0
Peak Hour Factor	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94	0.94
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	299	444	0	316	591	263	90	368	229	297	304	62
Arrive On Green	0.29	0.29	0.00	0.29	0.29	0.29	0.44	0.44	0.44	0.44	0.44	0.44
Sat Flow, veh/h	846	1509	0	1009	2012	895	16	839	522	419	691	142
Grp Volume(v), veh/h	11	248	0	86	238	204	269	0	0	274	0	0
Grp Sat Flow(s),veh/h/ln	846	1509	0	1009	1593	1314	1376	0	0	1252	0	0
Q Serve(g_s), s	0.5	6.2	0.0	3.5	5.6	5.8	0.0	0.0	0.0	0.0	0.0	0.0
Cycle Q Clear(g_c), s	6.3	6.2	0.0	9.8	5.6	5.8	6.1	0.0	0.0	5.8	0.0	0.0
Prop In Lane	1.00			1.00		0.68	0.04		0.38	0.41		0.11
Lane Grp Cap(c), veh/h	299	444	0	316	468	386	687	0	0	663	0	0
V/C Ratio(X)	0.04	0.56	0.00	0.27	0.51	0.53	0.39	0.00	0.00	0.41	0.00	0.00
Avail Cap(c_a), veh/h	351	536	0	379	566	467	687	0	0	663	0	0
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	0.77	0.77	0.00	1.00	1.00	1.00	1.00	0.00	0.00	1.00	0.00	0.00
Uniform Delay (d), s/veh	15.9	13.4	0.0	17.6	13.2	13.3	8.8	0.0	0.0	8.7	0.0	0.0
Incr Delay (d2), s/veh	0.0	0.8	0.0	0.5	0.9	1.1	1.7	0.0	0.0	1.9	0.0	0.0
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	0.1	2.7	0.0	1.0	2.6	2.2	2.6	0.0	0.0	2.6	0.0	0.0
LnGrp Delay(d),s/veh	16.0	14.3	0.0	18.0	14.0	14.4	10.5	0.0	0.0	10.6	0.0	0.0
LnGrp LOS	B	B		B	B	B	B			B		
Approach Vol, veh/h	259				528			269			274	
Approach Delay, s/veh	14.3				14.8			10.5			10.6	
Approach LOS	B				B			B			B	
Timer	1	2	3	4	5	6	7	8				
Assigned Phs	2			4		6		8				
Phs Duration (G+Y+R <sub>c</sub> ), s	25.8			19.2		25.8		19.2				
Change Period (Y+R <sub>c</sub> ), s	6.0			6.0		6.0		6.0				
Max Green Setting (G <sub>max</sub> ), s	17.0			16.0		17.0		16.0				
Max Q Clear Time (g <sub>c+l1</sub> ), s	8.1			8.3		7.8		11.8				
Green Ext Time (p <sub>c</sub> ), s	1.0			0.8		1.1		1.2				
Intersection Summary												
HCM 2010 Ctrl Delay	13.0											
HCM 2010 LOS	B											

## Timings

### 103: West Avenue & Dade Boulevard



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations	↑ ↗	↗ ↘	↖ ↗	↖ ↗ ↘		↖ ↗		↖ ↗
Traffic Volume (vph)	10	233	81	285	9	148	104	124
Future Volume (vph)	10	233	81	285	9	148	104	124
Turn Type	Perm	NA	Perm	NA	Perm	NA	Perm	NA
Protected Phases				4		8		2
Permitted Phases	4				2		6	
Detector Phase	4	4	8	8	2	2	6	6
Switch Phase								
Minimum Initial (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
Minimum Split (s)	22.0	22.0	22.0	22.0	22.0	22.0	22.0	22.0
Total Split (s)	22.0	22.0	22.0	22.0	23.0	23.0	23.0	23.0
Total Split (%)	48.9%	48.9%	48.9%	48.9%	51.1%	51.1%	51.1%	51.1%
Yellow Time (s)	4.0	4.0	4.0	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.0	2.0	2.0	2.0	2.0	2.0	2.0	2.0
Lost Time Adjust (s)	0.0	0.0	0.0	0.0		0.0		0.0
Total Lost Time (s)	6.0	6.0	6.0	6.0		6.0		6.0
Lead/Lag								
Lead-Lag Optimize?								
Recall Mode	None	None	None	None	C-Min	C-Min	C-Min	C-Min
Act Effect Green (s)	12.1	12.1	12.1	12.1		20.9		20.9
Actuated g/C Ratio	0.27	0.27	0.27	0.27		0.46		0.46
v/c Ratio	0.06	0.61	0.35	0.51		0.40		0.52
Control Delay	11.0	20.4	16.2	10.8		8.7		14.7
Queue Delay	0.0	0.0	0.0	0.0		0.0		0.0
Total Delay	11.0	20.4	16.2	10.8		8.7		14.7
LOS	B	C	B	B		A		B
Approach Delay		20.0		11.7		8.7		14.7
Approach LOS		B		B		A		B

#### Intersection Summary

Cycle Length: 45

Actuated Cycle Length: 45

Offset: 0 (0%), Referenced to phase 2:NBTL and 6:SBTL, Start of Yellow

Natural Cycle: 45

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.61

Intersection Signal Delay: 13.3


Intersection LOS: B

Intersection Capacity Utilization 70.9%

ICU Level of Service C

Analysis Period (min) 15

Splits and Phases: 103: West Avenue & Dade Boulevard



## Queues

## 103: West Avenue &amp; Dade Boulevard



Lane Group	EBL	EBT	WBL	WBT	NBT	SBT
Lane Group Flow (vph)	11	248	86	442	269	274
v/c Ratio	0.06	0.61	0.35	0.51	0.40	0.52
Control Delay	11.0	20.4	16.2	10.8	8.7	14.7
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	11.0	20.4	16.2	10.8	8.7	14.7
Queue Length 50th (ft)	2	55	17	32	28	43
Queue Length 95th (ft)	9	97	41	55	82	#140
Internal Link Dist (ft)		508		381	432	477
Turn Bay Length (ft)						
Base Capacity (vph)	264	536	323	1104	681	528
Starvation Cap Reductn	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0
Reduced v/c Ratio	0.04	0.46	0.27	0.40	0.40	0.52

## Intersection Summary

# 95th percentile volume exceeds capacity, queue may be longer.

Queue shown is maximum after two cycles.


# HCM 2010 Signalized Intersection Summary

## 104: West Avenue & 17th Street

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Volume (veh/h)	16	181	198	129	230	40	176	237	193	18	189	1
Future Volume (veh/h)	16	181	198	129	230	40	176	237	193	18	189	1
Number	1	6	16	5	2	12	7	4	14	3	8	18
Initial Q (Q <sub>b</sub> ), veh	0	0	0	0	0	0	0	0	0	0	0	0
Ped-Bike Adj(A <sub>pbT</sub> )	0.96			1.00		0.92	0.97		0.94	1.00		0.92
Parking Bus, Adj	1.00	1.00	0.90	1.00	1.00	0.90	1.00	1.00	0.85	1.00	1.00	0.90
Adj Sat Flow, veh/h/ln	1710	1676	1710	1676	1676	1710	1676	1676	1710	1676	1676	1710
Adj Flow Rate, veh/h	17	189	206	134	240	42	183	247	201	19	197	1
Adj No. of Lanes	0	2	0	1	1	0	1	1	0	1	1	0
Peak Hour Factor	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96	0.96
Percent Heavy Veh, %	2	2	2	2	2	2	2	2	2	2	2	2
Cap, veh/h	61	595	411	157	654	114	343	265	216	89	562	3
Arrive On Green	0.39	0.39	0.39	0.10	0.53	0.53	0.37	0.37	0.37	0.37	0.37	0.37
Sat Flow, veh/h	79	1536	1062	1597	1234	216	1027	707	575	845	1499	8
Grp Volume(v), veh/h	206	0	206	134	0	282	183	0	448	19	0	198
Grp Sat Flow(s),veh/h/ln	1615	0	1062	1597	0	1450	1027	0	1283	845	0	1507
Q Serve(g_s), s	0.0	0.0	19.2	10.7	0.0	14.8	20.3	0.0	43.6	2.9	0.0	12.3
Cycle Q Clear(g_c), s	11.2	0.0	19.2	10.7	0.0	14.8	32.6	0.0	43.6	46.5	0.0	12.3
Prop In Lane	0.08		1.00	1.00		0.15	1.00		0.45	1.00		0.01
Lane Grp Cap(c), veh/h	656	0	411	157	0	768	343	0	481	89	0	565
V/C Ratio(X)	0.31	0.00	0.50	0.85	0.00	0.37	0.53	0.00	0.93	0.21	0.00	0.35
Avail Cap(c_a), veh/h	656	0	411	348	0	768	364	0	506	105	0	595
HCM Platoon Ratio	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00	1.00
Upstream Filter(I)	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00	1.00	0.00	1.00
Uniform Delay (d), s/veh	27.8	0.0	30.3	57.7	0.0	17.8	41.0	0.0	39.0	61.4	0.0	29.2
Incr Delay (d2), s/veh	1.3	0.0	4.3	5.0	0.0	1.4	1.0	0.0	23.4	0.9	0.0	0.3
Initial Q Delay(d3),s/veh	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
%ile BackOfQ(50%),veh/ln	5.4	0.0	6.1	4.9	0.0	6.2	5.8	0.0	18.6	0.7	0.0	5.2
LnGrp Delay(d),s/veh	29.1	0.0	34.6	62.6	0.0	19.2	42.0	0.0	62.4	62.2	0.0	29.5
LnGrp LOS	C		C	E		B	D		E	E		C
Approach Vol, veh/h	412			416				631			217	
Approach Delay, s/veh	31.8			33.2				56.5			32.4	
Approach LOS	C			C				E			C	
Timer	1	2	3	4	5	6	7	8				
Assigned Phs	2		4	5	6		8					
Phs Duration (G+Y+R <sub>c</sub> ), s	75.1		54.9	18.5	56.6		54.9					
Change Period (Y+R <sub>c</sub> ), s	* 6.2		* 6.2	* 5.7	* 6.2		* 6.2					
Max Green Setting (Gmax), s	* 67		* 51	* 28	* 33		* 51					
Max Q Clear Time (g <sub>c+l1</sub> ), s	16.8		45.6	12.7	21.2		48.5					
Green Ext Time (p <sub>c</sub> ), s	0.6		1.7	0.2	0.9		0.2					
<b>Intersection Summary</b>												
HCM 2010 Ctrl Delay	41.5											
HCM 2010 LOS	D											
Notes												

## Timings

### 104: West Avenue & 17th Street



Lane Group	EBL	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Configurations								
Traffic Volume (vph)	16	181	129	230	176	237	18	189
Future Volume (vph)	16	181	129	230	176	237	18	189
Turn Type	Perm	NA	Prot	NA	Perm	NA	Perm	NA
Protected Phases						4		8
Permitted Phases	6					4		8
Detector Phase	6	6	5	2	4	4	8	8
Switch Phase								
Minimum Initial (s)	7.0	7.0	5.0	7.0	7.0	7.0	7.0	7.0
Minimum Split (s)	37.2	37.2	12.0	37.2	35.2	35.2	32.2	32.2
Total Split (s)	38.9	38.9	34.0	72.9	57.5	57.5	57.5	57.5
Total Split (%)	29.8%	29.8%	26.1%	55.9%	44.1%	44.1%	44.1%	44.1%
Yellow Time (s)	4.0	4.0	3.7	4.0	4.0	4.0	4.0	4.0
All-Red Time (s)	2.2	2.2	2.0	2.2	2.2	2.2	2.2	2.2
Lost Time Adjust (s)	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Lost Time (s)			6.2	6.2	6.2	6.2	6.2	6.2
Lead/Lag	Lag	Lag	Lead					
Lead-Lag Optimize?	Yes	Yes	Yes					
Recall Mode	C-Min	C-Min	None	C-Min	Min	Min	Min	Min
Act Effect Green (s)	48.2	17.2	71.1	46.9	46.9	46.9	46.9	46.9
Actuated g/C Ratio	0.37	0.13	0.55	0.36	0.36	0.36	0.36	0.36
v/c Ratio	0.40	0.74	0.36	0.64	0.88	0.13	0.37	
Control Delay	20.3	76.5	19.7	44.1	53.3	26.3	31.1	
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
Total Delay	20.3	76.5	19.7	44.1	53.3	26.3	31.1	
LOS	C	E	B	D	D	C	C	
Approach Delay	20.3		38.0		50.7		30.7	
Approach LOS	C		D		D		C	

#### Intersection Summary

Cycle Length: 130.4

Actuated Cycle Length: 130.4

Offset: 114 (87%), Referenced to phase 2:WBT and 6:EBTL, Start of Yellow

Natural Cycle: 85

Control Type: Actuated-Coordinated

Maximum v/c Ratio: 0.88

Intersection Signal Delay: 37.5


Intersection LOS: D

Intersection Capacity Utilization 106.6%

ICU Level of Service G

Analysis Period (min) 15

Splits and Phases: 104: West Avenue & 17th Street



## Queues

## 104: West Avenue &amp; 17th Street



Lane Group	EBT	WBL	WBT	NBL	NBT	SBL	SBT
Lane Group Flow (vph)	412	134	282	183	448	19	198
v/c Ratio	0.40	0.74	0.36	0.64	0.88	0.13	0.37
Control Delay	20.3	76.5	19.7	44.1	53.3	26.3	31.1
Queue Delay	0.0	0.0	0.0	0.0	0.0	0.0	0.0
Total Delay	20.3	76.5	19.7	44.1	53.3	26.3	31.1
Queue Length 50th (ft)	71	111	126	127	326	11	122
Queue Length 95th (ft)	148	173	234	184	407	26	160
Internal Link Dist (ft)	476		364		407		104
Turn Bay Length (ft)		160		170		50	
Base Capacity (vph)	1034	300	814	323	575	164	614
Starvation Cap Reductn	0	0	0	0	0	0	0
Spillback Cap Reductn	0	0	0	0	0	0	0
Storage Cap Reductn	0	0	0	0	0	0	0
Reduced v/c Ratio	0.40	0.45	0.35	0.57	0.78	0.12	0.32

## Intersection Summary

HCM 2010 AWSC  
105: West Avenue & 18 Street

---

Intersection

Intersection Delay, s/veh 10.8

Intersection LOS B

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	76	15	145	6	12	13	111	166	17	14	87	87
Future Vol, veh/h	76	15	145	6	12	13	111	166	17	14	87	87
Peak Hour Factor	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93	0.93
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	82	16	156	6	13	14	119	178	18	15	94	94
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach												
Opposing Approach	WB			WB			NB			SB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	10.6			8.7			11.8			9.7		
HCM LOS	B			A			B			A		

Lane	NBLn1	EBLn1	WBLn1	SBLn1
Vol Left, %	38%	32%	19%	7%
Vol Thru, %	56%	6%	39%	46%
Vol Right, %	6%	61%	42%	46%
Sign Control	Stop	Stop	Stop	Stop
Traffic Vol by Lane	294	236	31	188
LT Vol	111	76	6	14
Through Vol	166	15	12	87
RT Vol	17	145	13	87
Lane Flow Rate	316	254	33	202
Geometry Grp	1	1	1	1
Degree of Util (X)	0.433	0.345	0.05	0.269
Departure Headway (Hd)	4.929	4.899	5.445	4.782
Convergence, Y/N	Yes	Yes	Yes	Yes
Cap	724	726	662	742
Service Time	3.013	2.984	3.445	2.873
HCM Lane V/C Ratio	0.436	0.35	0.05	0.272
HCM Control Delay	11.8	10.6	8.7	9.7
HCM Lane LOS	B	B	A	A
HCM 95th-tile Q	2.2	1.5	0.2	1.1

HCM 2010 AWSC  
106: Bay Road & 18 Street

---

Intersection

Intersection Delay, s/veh 9.9

Intersection LOS A

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	45	85	87	41	101	73	12	29	73	86	28	47
Future Vol, veh/h	45	85	87	41	101	73	12	29	73	86	28	47
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	49	92	95	45	110	79	13	32	79	93	30	51
Number of Lanes	0	1	0	0	1	0	0	1	0	0	1	0
Approach												
	EB			WB			NB			SB		
Opposing Approach	WB			EB			SB			NB		
Opposing Lanes	1			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			1			1		
HCM Control Delay	10.1			10.1			9.1			10		
HCM LOS	B			B			A			A		

Lane	NBLn1	EBLn1	WBLn1	SBLn1
Vol Left, %	11%	21%	19%	53%
Vol Thru, %	25%	39%	47%	17%
Vol Right, %	64%	40%	34%	29%
Sign Control	Stop	Stop	Stop	Stop
Traffic Vol by Lane	114	217	215	161
LT Vol	12	45	41	86
Through Vol	29	85	101	28
RT Vol	73	87	73	47
Lane Flow Rate	124	236	234	175
Geometry Grp	1	1	1	1
Degree of Util (X)	0.173	0.313	0.312	0.254
Departure Headway (Hd)	5.022	4.871	4.906	5.23
Convergence, Y/N	Yes	Yes	Yes	Yes
Cap	717	743	736	691
Service Time	3.028	2.871	2.906	3.23
HCM Lane V/C Ratio	0.173	0.318	0.318	0.253
HCM Control Delay	9.1	10.1	10.1	10
HCM Lane LOS	A	B	B	A
HCM 95th-tile Q	0.6	1.3	1.3	1

HCM 2010 AWSC  
107: Purdy Avenue & 18 Street

---

Intersection

Intersection Delay, s/veh 10.7

Intersection LOS B

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	13	18	29	95	9	47	14	113	175	27	130	4
Future Vol, veh/h	13	18	29	95	9	47	14	113	175	27	130	4
Peak Hour Factor	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87	0.87
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	15	21	33	109	10	54	16	130	201	31	149	5
Number of Lanes	0	1	0	0	1	0	1	1	0	1	1	0
Approach												
Opposing Approach	WB			WB			NB			SB		
Opposing Lanes	1			1			2			2		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	2			2			1			1		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	2			2			1			1		
HCM Control Delay	9			10.2			11.7			9.9		
HCM LOS	A			B			B			A		

Lane	NBLn1	NBLn2	E BLn1	W BLn1	S BLn1	S BLn2
Vol Left, %	100%	0%	22%	63%	100%	2%
Vol Thru, %	0%	39%	30%	6%	0%	95%
Vol Right, %	0%	61%	48%	31%	0%	3%
Sign Control	Stop	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	14	288	60	151	24	137
LT Vol	14	0	13	95	24	3
Through Vol	0	113	18	9	0	130
RT Vol	0	175	29	47	0	4
Lane Flow Rate	16	331	69	174	28	157
Geometry Grp	7	7	2	2	7	7
Degree of Util (X)	0.026	0.454	0.103	0.253	0.047	0.24
Departure Headway (Hd)	5.87	4.936	5.356	5.255	6.112	5.495
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes	Yes
Cap	605	722	673	675	589	646
Service Time	3.657	2.723	3.356	3.349	3.812	3.295
HCM Lane V/C Ratio	0.026	0.458	0.103	0.258	0.048	0.243
HCM Control Delay	8.8	11.8	9	10.2	9.1	10.1
HCM Lane LOS	A	B	A	B	A	B
HCM 95th-tile Q	0.1	2.4	0.3	1	0.1	0.9

HCM 2010 AWSC  
108: West Avenue & 20 Street

---

Intersection

Intersection Delay, s/veh 11.4

Intersection LOS B

Movement	EBL	EBT	EBR	WBL	WBT	WBR	NBL	NBT	NBR	SBL	SBT	SBR
Lane Configurations												
Traffic Vol, veh/h	2	260	55	149	221	1	33	1	156	0	1	2
Future Vol, veh/h	2	260	55	149	221	1	33	1	156	0	1	2
Peak Hour Factor	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92	0.92
Heavy Vehicles, %	2	2	2	2	2	2	2	2	2	2	2	2
Mvmt Flow	2	283	60	162	240	1	36	1	170	0	1	2
Number of Lanes	0	1	0	1	1	0	0	1	0	0	1	0
Approach												
Opposing Approach	WB			WB			NB			SB		
Opposing Lanes	2			1			1			1		
Conflicting Approach Left	SB			NB			EB			WB		
Conflicting Lanes Left	1			1			1			2		
Conflicting Approach Right	NB			SB			WB			EB		
Conflicting Lanes Right	1			1			2			1		
HCM Control Delay	12.5			11			10.5			8.8		
HCM LOS	B			B			B			A		

Lane	NBLn1	EBLn1	WBLn1	WBLn2	SBLn1
Vol Left, %	17%	1%	100%	0%	0%
Vol Thru, %	1%	82%	0%	100%	33%
Vol Right, %	82%	17%	0%	0%	67%
Sign Control	Stop	Stop	Stop	Stop	Stop
Traffic Vol by Lane	190	317	149	222	3
LT Vol	33	2	149	0	0
Through Vol	1	260	0	221	1
RT Vol	156	55	0	1	2
Lane Flow Rate	207	345	162	241	3
Geometry Grp	2	5	7	7	2
Degree of Util (X)	0.296	0.473	0.265	0.361	0.005
Departure Headway (Hd)	5.166	4.942	5.895	5.387	5.759
Convergence, Y/N	Yes	Yes	Yes	Yes	Yes
Cap	688	720	604	661	625
Service Time	3.258	3.032	3.691	3.183	3.759
HCM Lane V/C Ratio	0.301	0.479	0.268	0.365	0.005
HCM Control Delay	10.5	12.5	10.8	11.2	8.8
HCM Lane LOS	B	B	B	B	A
HCM 95th-tile Q	1.2	2.6	1.1	1.6	0

HCM 2010 AWSC  
109: Bay Road & 20 Street

---

Intersection

Intersection Delay, s/veh 10.5

Intersection LOS B

Movement	EBT	EBR	WBL	WBT	NBL	NBR
----------	-----	-----	-----	-----	-----	-----

Lane Configurations



Traffic Vol, veh/h 106 10 83 218 20 159

Future Vol, veh/h 106 10 83 218 20 159

Peak Hour Factor 0.83 0.83 0.83 0.83 0.83 0.83

Heavy Vehicles, % 2 2 2 2 2 2

Mvmt Flow 128 12 100 263 24 192

Number of Lanes 1 0 0 1 1 0

Approach	EB	WB	NB
----------	----	----	----

Opposing Approach WB EB

Opposing Lanes 1 1 0

Conflicting Approach Left NB EB

Conflicting Lanes Left 0 1 1

Conflicting Approach Right NB WB

Conflicting Lanes Right 1 0 1

HCM Control Delay 9 11.8 9.4

HCM LOS A B A

Lane	NBLn1	EBLn1	WBLn1
------	-------	-------	-------

Vol Left, % 11% 0% 28%

Vol Thru, % 0% 91% 72%

Vol Right, % 89% 9% 0%

Sign Control Stop Stop Stop

Traffic Vol by Lane 179 116 301

LT Vol 20 0 83

Through Vol 0 106 218

RT Vol 159 10 0

Lane Flow Rate 216 140 363

Geometry Grp 1 1 1

Degree of Util (X) 0.275 0.187 0.469

Departure Headway (Hd) 4.593 4.81 4.659

Convergence, Y/N Yes Yes Yes

Cap 779 741 769

Service Time 2.64 2.87 2.71

HCM Lane V/C Ratio 0.277 0.189 0.472

HCM Control Delay 9.4 9 11.8

HCM Lane LOS A A B

HCM 95th-tile Q 1.1 0.7 2.5

HCM 2010 TWSC  
201: Bay Road & Driveway

---

Intersection						
Int Delay, s/veh	3.8					
Movement	EBL	EBR	NBL	NBT	SBT	SBR
Lane Configurations						
Traffic Vol, veh/h	35	77	23	48	67	86
Future Vol, veh/h	35	77	23	48	67	86
Conflicting Peds, #/hr	0	0	0	0	0	0
Sign Control	Stop	Stop	Free	Free	Free	Free
RT Channelized	-	None	-	None	-	None
Storage Length	0	-	-	-	-	-
Veh in Median Storage, #	0	-	-	0	0	-
Grade, %	0	-	-	0	0	-
Peak Hour Factor	92	92	92	92	92	92
Heavy Vehicles, %	2	2	2	2	2	2
Mvmt Flow	38	84	25	52	73	93
Major/Minor						
Major/Minor	Minor2	Major1		Major2		
Conflicting Flow All	222	120	166	0	-	0
Stage 1	120	-	-	-	-	-
Stage 2	102	-	-	-	-	-
Critical Hdwy	6.42	6.22	4.12	-	-	-
Critical Hdwy Stg 1	5.42	-	-	-	-	-
Critical Hdwy Stg 2	5.42	-	-	-	-	-
Follow-up Hdwy	3.518	3.318	2.218	-	-	-
Pot Cap-1 Maneuver	766	931	1412	-	-	-
Stage 1	905	-	-	-	-	-
Stage 2	922	-	-	-	-	-
Platoon blocked, %	-	-	-	-	-	-
Mov Cap-1 Maneuver	752	931	1412	-	-	-
Mov Cap-2 Maneuver	752	-	-	-	-	-
Stage 1	889	-	-	-	-	-
Stage 2	922	-	-	-	-	-
Approach						
Approach	EB	NB		SB		
HCM Control Delay, s	9.8	2.5		0		
HCM LOS	A					
Minor Lane/Major Mvmt		NBL	NBT	EBLn1	SBT	SBR
Capacity (veh/h)	1412	-	867	-	-	-
HCM Lane V/C Ratio	0.018	-	0.14	-	-	-
HCM Control Delay (s)	7.6	0	9.8	-	-	-
HCM Lane LOS	A	A	A	-	-	-
HCM 95th %tile Q(veh)	0.1	-	0.5	-	-	-

## Queuing Analysis based on ITE Procedures

$q = 47 \text{ veh/hr}$  (demand rate)\*

$Q = 17 \text{ veh/hr}$  (service rate)

$$p = \frac{q}{NQ} = 0.4607 \quad (N = 6 \text{ valet runners})$$

$$Q_M = 0.4607$$

Using Acceptable Probability of 5% (95% Confidence Level)

$$M = \left( \frac{\ln(x > M) - \ln(Q_M)}{\ln(p)} \right) - 1$$

$$M = \left( \frac{\ln(0.05) - \ln(0.4607)}{\ln(0.4607)} \right) - 1$$

$$M = \left( \frac{-2.995 - (-0.7750)}{-0.7750} \right) - 1$$

$$M = 2.86 - 1 = 1.86, \text{ say } 2 \text{ vehicles}$$

Note: when taking  $\ln$  of a number, it is recommended to have the same number of digits in the original number. Calculations involving " $\ln$ " were not rounded.

- Assumed 80% of retail customers will use valet parking

## Valet Trips Calculation

- Assumed 80% of retail customers will use valet parking

Valet Trips =  $0.80 \times (\text{Inbound trips} - \text{Internalization} - \text{Multimodal reduction})$

Where:

Inbound trips = 77 (from trip generation table)

Internalization =  $77 \times 0.05 = 4$

Multimodal reduction =  $0.20 \times (77-4) = 15$  (multimodal reduction was applied after internalization)

Valet Trips =  $0.80 \times (77 - 4 - 15) = 46.4$ , say **47**

**Please note that valet trips already include pass-by trips since were calculated based on In-bound trips**

### **Service Rate Calculation**

An average service rate was determined based on the service rate for standard parking spaces. The total service rate for standard parking spaces is the sum of the following times:

- Walking time: time for valet attendant to pick up vehicle within the garage at walking speed of 4 feet per second.
- Driving time: time to drive around on local roads at a speed of 25 miles per hour.

#### **Valet Time (Standard Parking Spaces):**



- Walking Time:  $300 \text{ ft} * (1 \text{ sec}/4\text{ft}) * (1 \text{ min}/60\text{sec}) = 1.25 \text{ min}$
- Driving Time + Control Delay:  $845 \text{ ft} * (1\text{mile}/5,280) * (1\text{hr}/25 \text{ miles}) * (60 \text{ min}/1\text{hr}) + 19 \text{ sec} * (1 \text{ min}/60 \text{ sec}) = 0.38 \text{ min} + 0.31 \text{ min} = 0.69 \text{ min} = \text{Assumed} = 1.0 \text{ min}$
- Total Time:  $1.25 + 1.0 \text{ min}$

#### **Average Valet Time:**

**2.25 min, say 3.5 min**

The zoning is  
F-1, Land Use  
and is an  
existing lot.  
This map is  
not in Part  
of the FPL  
Permit.

MAP	UP DATE SURVEY (7/7/11) SJ	ADMS. BLDG. NUMBER: 1752	PER TAX FLU:	Remarks Description
No	15	15	15	



**LOCATION SKETCH**  
NOT TO SCALE

**LEGAL DESCRIPTION:**

The West 1/2 of Lot 3, Lot 4, Lot 5, Lot 6 and lot 7, Block 16, ISLAND VIEW SUB-DIVISION, Miami-Dade County, Florida, as recorded in Plat Book 6 of Page 115 of the Public Records of Miami-Dade County, Florida.

**SURVEYOR'S NOTES:**

- This site sits in Section 33, Township 53 South, Range 42 East, City of Miami Beach, Miami-Dade County, Florida
- All documents are recorded in the Public Records of Miami-Dade County, Florida, unless otherwise noted.
- Londs shown herein were NOT obstructed for restrictions, easements and/or rights-of-way.
- Bearings herein are referred to an assumed value of S 93°00'00" W for the South line of Lot 3, and evidence by (2) found 1/2" pipe & cap.
- Elevations shown herein are relative to the Not-rod Geodetic Vertical Datum of 1929, based on Mean Sea Level, which was established by Mean Sea Level Survey, conducted at the North corner of the bridge at 10th Street (25' south of centerline of Eastbound lane) and West Avenue (Bridge over Collins Canal).
- Londs shown herein are located within an area having 2.16 "square miles" of AE (D-1) by the Federal Emergency Management Agency (FEMA), in Flood Insurance Rate Map (FIRMA) community 10-12-06C-317L, dated September 11, 2009, and index map revised September 11, 2009, and is related to the Not-rod Geodetic Vertical Datum of 1929.
- Distances indicated herein are field measured by electronic measurement, unless otherwise noted.
- Londs shown herein containing 33.75 square feet, or 1.775 acres, more or less.
- All horizontal control measurements are within a precision of 1:10,000.
- This map is intended to be displayed of the graphic scale shown herein or smaller.
- Roads, overhead not located unless otherwise shown.
- Underground improvements and/or underground encroachments not shown unless otherwise indicated.
- The approximate location of all utilities shown herein were determined from As-Built plans and/or site location and should be verified before construction.
- Legal description is not guaranteed based on information furnished by client and no claims as to ownership are made or implied.
- Tax Folio Numbers per Miami-Dade County Property Appraiser's website.

**SURVEYOR'S CERTIFICATION:**

I hereby certify that the boundary & topographic Survey was made under my responsible charge in May 2011, and updated in July 3, 2011 and meets the applicable codes set forth in the Florida Administrative Code, pursuant to Section 472-27, Florida Statutes.

"Not valid without signature and the original record seal of a Florida Licensed Surveyor and Mapper"

FORTIN, LEAVY, SKILES, INC., LB3653

**Daniel C Fortin**  
Daniel C. Fortin, FLS, The Firm  
Surveyor, Mapper, Land Surveyor  
State of Florida



**LEGEND**

■ = CATCH BASIN	■ = 8" CURB
○ = MANHOLE	■ = 2" CURB & GUTTER
△ = LIGHT PILE	■ = CHAIN LINK FENCE
□ = WATER METER	■ = IDENTIFICATION
△ = WATER VALVE	■ = ELEVATION
■ = CATCH BASIN INLET	■ = INV.
□ = UTILITY POLE	■ = SURVEY
■ = FIRE HYDRANT	■ = P.R.M.
■ = HAWTHORPE	■ = CONCRETE
□ = SIGN	■ = ASPHALT PAVEMENT

<b>BOUNDARY &amp; TOPOGRAPHIC SURVEY</b>
<b>SUNSET PARK</b>
<b>CITY OF MIAMI BEACH, MIAMI-DADE COUNTY, FLORIDA</b>

Original Date	SS-17
Scale	1"-30'
Drawn By	MAP
CAD No	151403
Plotted	5/3/18 9:03a
Ref. Draw.	2009-065
Field Book	SJD
Job No.	63659 & FL.D.SHTS.
Job No.	171148
Dwg. No.	2015-444
Sheet	1 of 1

## SUNSET PARK

### RESTAURANT 1

#### OPERATIONAL PLAN

The restaurant (hereinafter “Restaurant 1”) consists of ±3,556 square feet, and a total of 108 seats (14 bar seats, 86 indoor seats, and 8 outdoor seats), as shown on the enclosed ground floor plan, sheet Z101. The operational criteria for Restaurant 1 is provided below:

1. Except as may be required for fire or building code/life safety code purposes, no loudspeakers shall be affixed to or otherwise located on the exterior premises of the retail spaces or in any outdoor dining terrace or sidewalk café should one be established.
2. No outdoor live music associated with any commercial uses in the retail space shall be permitted at any time, unless provided for under a special event permit.
3. Interior loud speakers shall not be located near doors which lead to the outside and interior music levels shall not interfere with the normal conversation of diners.
4. The maximum number of outdoor seats for a restaurant shall be 40 seats.
5. The maximum interior floor area of a restaurant on the Property shall be 3,600 square feet.
6. Any restaurant’s primary function shall be food service and at no time shall a restaurant become a dance hall, disco or nightclub.
7. The hours of operation for any restaurant shall be limited to 8:00 AM to 11:30 PM, Sunday through Wednesday and 8:00 AM to 12:30 AM, Thursday through Saturday.
8. The following commercial uses shall be prohibited on the Property: entertainment establishment (excepting television, radio and/or recorded background music per Sections 114-1 and 142-305 of the City of Miami Beach Code), package store, tattoo studio, stand-alone bar (however, a restaurant is allowed to have a bar as a component or ancillary use thereof), check cashing store and pawnshop.
9. The main trash room on the ground floor will be enclosed. All on-site trash disposal will be physically blocked from view and noise limited by a wall and roofed enclosures within the Property.
10. Restaurant 1 trash bins shall be wheeled out to main dumpster(s) located in the loading dock area. Trash removal from main dumpster(s) shall take place in the hours between 6 AM and 10 AM.
11. Deliveries and loading shall occur along Purdy Avenue and Bay Road at those certain on-street parking spaces designated for loading and off-street loading areas identified on Sheet A-2.11, and during the hours between 7 AM and 4:30 PM.
12. The maximum number of employees allowed on the premises at one time at Restaurant 1 shall be 30.

SUNSET PARK  
RESTAURANT 2  
OPERATIONAL PLAN

The restaurant (hereinafter “Restaurant 2”) consists of ±3,514 square feet, and a total of 124 seats (8 bar seats, 106 indoor seats, and 8 outdoor seats), as shown on the enclosed ground floor plan, sheet Z101. The operational criteria for Restaurant 2 is provided below:

1. Except as may be required for fire or building code/life safety code purposes, no loudspeakers shall be affixed to or otherwise located on the exterior premises of the retail spaces or in any outdoor dining terrace or sidewalk café should one be established.
2. No outdoor live music associated with any commercial uses in the retail space shall be permitted at any time, unless provided for under a special event permit.
3. Interior loud speakers shall not be located near doors which lead to the outside and interior music levels shall not interfere with the normal conversation of diners.
4. The maximum number of outdoor seats for a restaurant shall be 40 seats.
5. The maximum interior floor area of a restaurant on the Property shall be 3,600 square feet.
6. Any restaurant’s primary function shall be food service and at no time shall a restaurant become a dance hall, disco or nightclub.
7. The hours of operation for any restaurant shall be limited to 8:00 AM to 11:30 PM, Sunday through Wednesday and 8:00 AM to 12:30 AM, Thursday through Saturday.
8. The following commercial uses shall be prohibited on the Property: entertainment establishment (excepting television, radio and/or recorded background music per Sections 114-1 and 142-305 of the City of Miami Beach Code), package store, tattoo studio, stand-alone bar (however, a restaurant is allowed to have a bar as a component or ancillary use thereof), check cashing store and pawnshop.
9. The main trash room on the ground floor will be enclosed. All on-site trash disposal will be physically blocked from view and noise limited by a wall and roofed enclosures within the Property.
10. Restaurant 2 trash bins shall be wheeled out to main dumpster(s) located in the loading dock area. Trash removal from main dumpster(s) shall take place in the hours between 6 AM and 10 AM.
11. Deliveries and loading shall occur along Purdy Avenue and Bay Road at those certain on-street parking spaces designated for loading and off-street loading areas identified on Sheet A-2.11, and during the hours between 7 AM and 4:30 PM.
12. The maximum number of employees allowed on the premises at one time at Restaurant 2 shall be 30.