

SCALE: 3/32" = 1'-0"



Symbols do not show the actual canopy of the trees, for clarity, always cross check with Existing Tree Disposition List for sizes and disposition status. Contact landscape architect / ISA certified arborist for clarification on any discrepancies.

PROPOSED	CANOPYLOSS									
403	Proposed Canopy Loss (see Existing Tree Disposition List)									
282	- 70% of canopy mitigation must be met with new trees									
121	- 30% of canopy mitigation may	be met with paln	ns							
REQUIRED (4									
		MIN. SIZE AT	CANOPY	CANOPY MITIGATE						
QUANTITY	REPLACEMENT CANOPY TYPE	PLANTING	CREDIT (Sq.Ft)	(Sq.Ft)						
2	Category 1 Trees	12' OAH * 2" Cal.	300	6						
2	Category 2 Trees	10' OAH * 2" Cal.	150	3						
2	Category 3 Trees	8' OAH * 2" Cal.	100	2						
3	Category 4 Palms	6' Clear trunk	50	1						
PROVIDED (1,2									



Existing Tree Protection Detail SCALE: N.T.S.

- Before beginning work, the Contractor is required to meet with the Landscape Architect at the site to review all work procedures, access routes, storage areas, and tree protection measures.
- 2. The General Contractor is required to coordinate with the Landscape Architect to determine the amount of tree canopy or root zone that the General Contractor will be responsible for pruning. THE TRIMMING SHALL BE AS PER ANSI A300 STANDARDS. 3. Fences shall be erected to protect trees to be preserved. Fences define a specific Tree Protection Zone (TPZ) for each tree or group of trees. Fences are to remain until all site work has been completed. Fences may not be relocated or removed without the written permission of the Landscape Architect. Refer to TREE PROTECTION ZONE (TPZ) DETAIL.

4. Construction trailers, traffic and storage areas must remain outside fenced areas at all times.

- 5. All underground utilities and drain or irrigation lines shall be routed outside the tree protection zone. If lines must traverse the protection area, they shall be tunneled or bored under the tree. 6. No materials, equipment, spoil, or waste or washout water may be deposited, stored, or parked within the tree protection zone (fenced area).
- Additional tree pruning required for clearance during construction must be performed by a ISA qualified arborist AS PER ANSI A300 STANDARDS, and not by construction personnel.
- 8. Any herbicides placed under paving materials must be safe for use around trees and labeled for that use. Any pesticides used on site must be tree-safe and not easily transported by water. 9. If injury should occur to any tree during construction, it should be evaluated as soon as possible by the Landscape Contractor and the Landscape Architect should be notified immediately.
- 10. Any grading, construction, demolition, or other work that is expected to encounter tree roots must be monitored by the Landscape Contractor. 11. All trees shall be irrigated three times a week. Each irrigation procedure shall wet the soil within the tree protection zone, 2-3 GALLONS OF WATER PER INCH OF TRUNK CALIPER.
- 12. All trees to remain on-site shall be fertilized three times per year using a granular 8-12-12 "Palm Special" product at standard rates. Fertilizer shall be broadcast on the ground beneath the canopy of each tree and watered in
- 13. Erosion control devices such as silt fencing, debris basins, and water diversion structures shall be installed to prevent site erosion and siltation situations and/or erosion within the tree protection zones.
- 14. Before grading, pad preparation, or excavation for foundations, footings, walls, or trenching near trees the trees shall be root pruned 12 inches outside the tree protection zone by cutting all roots cleanly to a depth of 36 inches. Roots shall be cut manually by digging a trench and cutting exposed roots with a saw, vibrating knife, rock saw, narrow trencher with sharp blades, or other approved root-pruning equipment.
- 15. Any roots damaged during grading or construction shall be exposed to sound tissue and cut cleanly with a saw.
- 16. If temporary haul or access roads must pass over the root area of trees to be retained, a road bed of 6 inches of mulch or gravel shall be created to protect the soil. The road bed material shall be replenished as necessary to maintain a 6-inch depth.
- 17. Spoil from trenches, basements, or other excavations shall not be placed within the tree protection zone, either temporarily or permanently. 18. No burn piles or debris pits shall be placed within the tree protection zone. No ashes, debris, or garbage may be dumped or buried within the tree protection zone.
- 19. Maintain fire-safe areas around fenced areas. Also, no heat sources, flames, ignition sources, or smoking is allowed near mulch or trees.

3 Existing Tree Protection Notes SCALE: N.T.S.

UMBER	BOTANICAL NAME	COMMON NAME	HEIGHT(FT)	SPREAD (FT)	DIAMETER DBH (IN)	CANOPY (SQ.FT)	CONDITION	ACTION	COMMENTS
1	Peltophorum pterocarpum	Yellow Poinciana	30	30	36	0	Good	Remain	Protect during construction
2	Dypsis lutescens	Areca Palm	20	15	7 Trunks @ 4	177	Poor	Remove	
3	Dypsis lutescens	Areca Palm	18	12	4 Trunks @ 4	113	Poor	Remove	
4	Cocos nucifera 'Green Malayan'	Coconut Palm	15	10	18	0	Fair	Remain	Protect during construction
5	Cocos nucifera 'Green Malayan'	Coconut Palm	18	12	18	0	Good	Remain	Protect during construction
6	Cocos nucifera 'Green Malayan'	Coconut Palm	15	10	18	0	Good	Remain	Protect during construction
7	Cocos nucifera 'Green Malayan'	Coconut Palm	15	10	18	0	Good	Remain	Protect during construction
8	Cocos nucifera 'Green Malayan'	Coconut Palm	15	10	12	0	Good	Remain	Protect during construction
9	Cocos nucifera 'Green Malayan'	Coconut Palm	15	10	18	0	Good	Remain	Protect during construction
10	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
11	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
12	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
13	Cocos nucifera 'Green Malayan'	Coconut Palm	15	10	18	0	Good	Remain	Protect during construction
14	Mangifera indica	Mango	22	15	12	0	Fair	Remain	Protect during construction
15	Mangifera indica	Mango	22	15	3 Trunks @ 6	0	Fair	Remain	Protect during construction
16	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
17	Strelitzia nicolai	White Bird of Paradise	20	10	4 Trunks @ 6	0	Fair	Remain	Protect during construction
18	Bismarckia nobilis 'Silver'	Silver Bismarck Palm	18	18	20	0	Good	Remain	Protect during construction
19	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
20	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
21	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
22	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
23	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
24	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
25	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
26	Ravenala madagascariensis	Traveler's Palm	22	15	24	0	Fair	Remain	Protect during construction
27	Wodyetia bifurcata	Foxtail Palm	20	12	8	113	Fair	Remove	
28	Ficus benjamina	Weeping Fig	30	35	36	0	Good	Remain	Protect during construction
OTAL P	ROPOSED CANOPY LOSS (in	square feet)				403			

Existing Tree Disposition List SCALE: N.T.S.


ALL LANDS

Existing Tree Disposition Plan

L100

Landscape Plan

L200



3/8" Pea Rock

FMG (52) 3 gal

BAR (2) 45 gal

.

(41) 15 gal

(28) 3 gal

SHERIDAN AVENUE

Landscape Plan

SCALE: 3/32" = 1'-0"

LXN (2) 65 gal

1. All mechanical equipment including, but not limited to Back Flow Preventor, Pumps, Electric, Phone or Cable Boxes, Lift Stations, Etc. shall be screened on 3 sides from view using an approved hedge, fence or wall.

3. The Landscape Architect must be notified when the plant material has been set in place to approve final locations, prior to installation.

GENERAL NOTES

1. Landscape Contractor is responsible for verifying locations of all underground and overhead utilities and easements prior to commencing work. All Utility companies and/or the General Contractor shall be notified to verify utility locations prior to digging. Utility trenching is to be coordinated with the Landscape plans prior to beginning of project. The Owner or Landscape Architect shall not be responsible for damage to utility or irrigation lines.

3. Landscape Contractor is responsible for verifying all plant quantities prior to bidding and within (7) seven calendar days of receipt of these plans shall notify

supply is the responsibility of the Landscape Contractor, and he/she shall take steps to insure availability at time of planting. 5. All plant material shall meet or exceed the size on the plant list. In all cases meeting the height and the spread specifications shall take precedence over

6. All planted areas to be outfitted with automatic irrigation system providing 100% coverage and 50% overlap. A rain sensor must be part of the irrigation Landscape Contractor shall be responsible for providing temporary hand watering to all proposed & landscape areas, during construction.

Landscape Contractor is to remove and discard from site existing unwanted trees, palms, shrubs, groundcover's, sod and weeds within landscape areas. All limestone shall be removed from planting beds prior to installation of plant material

10. All permitting and fees to be the responsibility of the Contractor.

General Planting Notes

LANDSCAPE REQUIREMENTS (Single Family Home) City of Miami Beach, Florida Code of Ordinances & Miami-Dade County Ordinance TREES Required Provided **Street Trees:** One canopy tree or grouping of three palms shall be provided for every 25 linear feet of frontage. 2 Existing Trees Length of Sheridan Avenue: 105 feet / 25 feet = 4 and 2 Proposed Minimun Height at time of planting: 12' / Minimun Caliper at time of planting: 2" / Minimun CT at time of planting: 4' Palms which meet all of the following requirements shall count as a required street tree on the basis of Minimun canopy of 15' at maturity / Minimun OA at time of planting: 14' / Minimun Caliper at time of planting: 4" An average maximum spacing of twenty-five (25) feet on center. Lot Trees (In addition to Street Trees): 3 trees per lot. Minimun Height at time of planting: 10' / Minimun Caliper at time of planting: 2" No less than 30 % of the required trees shall be native species. Minimun Height at time of planting: 8' / Minimun Caliper at time of planting: 1 1/2" 3 Palms = 1Palms which meet all of the following requirements shall count as a required tree on the basis of two (2) palms-per tree, except as provided herein for palms used as of street trees. Minimun Overall Height at time of planting: 10' / Minimun Caliper at time of planting: 3" Total of Required Trees No less than 30 % of the required trees shall be native species. No less than 50% of the required trees shall be low maintenance and drought tolerant species. No more than 30 % of the minimum tree requirements shall be palms. 80% of the trees shall be listed in the Miami Dade Landscape Manual, The Miami Dade Street Tree Master Plan and/or The University of Florida's Low-Maintenance Landscape Plants for South Florida List. **SHRUBS 30** 198 10 Units (Shrubs) per required lot tree. No less than 30 % of the required shrubs shall be native species. No less than 50% of the required shrubs shall be low maintenance and drought tolerant species. 24 80% of the shrubs shall be listed in the Miami Dade Landscape Manual, The Miami Dade Street 124

including the reasons why pruning is necessary, prior to the pruning actvities taking place.

18. Any sod areas damaged by construction are to be replaced with St. Augustine 'Floratam' sod.

17. Stake all trees and palms for approval by Landscape Architect prior to installation.


19. St. Augustine 'Floratam' - Contractor's responsibility to verify quantity.


21. Root barrier shall be Vespro Inc. or approved equal.

Landscape Contractor shall fertilize plant material as needed to support optimum healthy plant growth. All fertilization shall be performed in compliance with the latest ANSI A300 (Part 2) Standards.

20. Install rootbarrier as per manufacturer's recommendation on all large trees that are 6' or closer to any pavement or building, as shown on details page.

EXISTING TREE LEGEND -*Tree/Palm Number* Existing TREE/PALM TO REMAIN





3 Shrubs Planting Detail SCALE: N.T.S.

 Spacing diagram refers to all planting unless noted otherwise L= Spacing as called for in planting plan and plant list

SOD

- Lawn edging plactic composition / 5.5" H.

Plant location (typ.)

Set plants;

6" back for groundcover, 12" back for shrubs

Plant so that top of rootball is 2 " above

finished grade.

Shrubs Planting Detail
SCALE: N.T.S.



Palm Planting Detail
SCALE: N.T.S.



Landscape Details & Plant Images

L300