19



2012

2016

Development Approvals

A previous owner, 411 Aqua, LLC, requested a COA for the following work:

- Demolition of the secondary historic structure.
- Partial demolition*, renovation and restoration of the primary historic structure.
- Construction of a new 3-story building and a new 4-story building, as part of a new office complex.

*Note: It was not possible to determine the scope of demolition planned for the primary historic structure based on the approved design dcuments.

Construction of a 27,000 square foot boutique hotel at the corner of Michigan Avenue and 5th Street commenced in early 2017.

The lot at 411 Michigan Avenue was part of the project and was to be used for parking.

Only the foundation and underground parking was completed before the project stalled, and it went into foreclosure in 2018.

This property, along with 411 Michigan Avenue, are included in the current proposed project.

Final Submittal **14 March 2022**

CUBE 3

icense No. L18000278579

Jonathan W. Cardello, AIA


FL License No. AR93391



Final Submittal 14 March 2022

A5.23

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED



LEED Criteria Sample

(Not reflective of all LEED criteria met in the project)

Sensitive Land Protection: Site is previously developed and meets criteria (p. A3.2 Existing Foundation)

High Priority Site: Project located in a DDA

Surrounding Density and Diverse Uses: Project qualifies for surrounding density (p. A1.3)
Diverse Uses - Walgreens, WeWork Office,
Citibank, Southpointe Elementary, Chabad of South Beach, Minibar, Under the Mango Tree

Access to Quality Transit: 103 - Weekday: 31/Weekend: 29; 113 - Weekday: 20/Weekend: 17; 120 - Weekday: 82 / Weekend: 52; MB-SBL - Weekday: 64 /Weekend: 64;

Green Vehicles: Provided charging spaces for 5% of total parking spaces for the project ('EV' label p. A3.2, A3.3)

Site Development, Outdoor Water Use
Reduction: Protect or Restore HabitatLandscaped area with 100% native and adaptive plant palette (L1.6)

Heat Island Reductions: Project will use paving materials with a three-year aged solar reflectance (SR) value of at least 0.33 for paving; ENERGY-STAR Roofing Membrane is also required at exposed roofs (Bulkhead, Parking Structure)

Storage & Collection of Recyclables: Dumpster Areas labeled as Recycling Area/Trash (p. A3.3) On every floor, by Restroom/Water Fountain area, recycling bins will be provided.. E-waste collector and mercury lamp disposal in Trash/Recycling Room

Enhanced Indoor Air Quality Strategies: Project will have Entryway System, janitorial closet details And MERV 13 or Higher Filters in Permit Set

Project Statement
Signature Projects

License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

Design Collaborator

Introduction

A6.1

A6.2

A6.3


411 Michigan Avenue Miami Beach, Florida

CUBE 3

CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

> Final Submittal 14 March 2022


A6.0



Alberto Campo Baeza

Alberto Campo Baeza is one of the great master architects of our time.

He has built a select number of pristine buildings and has received countless architecture awards. Campo Baeza's body of work is best defined as poetic minimalism due to its simplicity, beauty and exquisite detailing. Based in Madrid, he recently received the Premio Nacional de Arquitectura, Spain's most prestigious architecture award.





A6.1



"We have designed a very simple building, ordered, very transparent and bright, which we believe reflects the spirit of the City of Miami Beach"

ALBERTO CAMPO BAEZA

01 Courtyard

The Courtyard is one of the most distinctive elements of Miami Beach and Mediterranean Style architecture. As such, we deliberately incorporated it into our building. It serves both as circulation and as a dedicated interior outdoor space that all tenants and visitors will enjoy. Here, the patio is the heart of the building, and therefore the exterior materials and plantings will be selected to offer an authentic "Miami Beach Experience."

02 Balconies

The balconies, servings as "open-air corridors", are typical to several architectural styles present in Miami Beach. These are logical solutions for tropical climates since they offer shade on the façade, create an outdoor living space, allow cross-ventilation, and favor the use of natural light while also providing shade and reducing solar heat gain. Our building appropriates this very typical Miami Beach element and offers wide and deep balconies on all four facades.

03 Covered Outdoor Spaces

Covered outdoor spaces are characteristically found in hot climates like Miami Beach. Spaces such as porches, winter gardens, Florida Rooms, and sunrooms allow users to enjoy the outdoors in a controlled manner all year round while protecting themselves from the rain. The proposed design incorporates a spacious 2,800 square foot podium on the ground floor, a protected place intimately close to the street and neighborhood.

Local architects have utilized accessible rooftops throughout Miami's history. Under direct exposure to the sky and sun, the rooftops areas provide views from where tenants can admire the city skyline and historic district beyond. Our roof terrace will be shrouded with vegetation and furnished to provide a relaxing garden sanctuary for the building's tenants. Careful attention will be paid to the location of the mechanical equipment to hide it from view and reduce its visual impact on neighboring streets.

04 Cross Ventilation

Cross ventilation is the traditional way to cool homes and buildings in warm climates such as Miami Beach. It is a highly sustainable and proven architectural technique utilized throughout Architectural History. Our design combines this traditional form of passive conditioning with an active systems air conditioning system. These are compatible methods to guarantee thermal comfort while respecting the environment and making use of natural ventilation as the weather permits.

05 Planters

Planters are typical characteristic elements of traditional Miami Beach architecture They allow vegetation to be incorporated into buildings in a controlled manner, smooth the transition between vertical walls and horizontal ground, protect views to the interior and, if well-implemented, improve the overall appearance of the building. Our building incorporates planters both on the ground floor, the roof, and the parking structure. In all cases, leafy plant species capable of reducing the impact of the sun will be employed in this project.

06 Landscaping

One of the main project objectives is to provide conscientious, abundant, and attractive landscaping, both for the users of the building and the neighborhood. For this, different species of character and scale according to their function. Medium-sized species will be used as well as climbing plants that provide shade and restore the environment. On the street level, larger species will be planted that will relate to the existing vegetation in the adjoining streets. Perennial Peanut will serve as a groundcover along the sidewalk. Our courtyard will feature a beautiful water chestnut tree to bring nature indoors. Our goal is to create a high-quality natural landscape consistent with Miami Beach's history.

07 Natural Light

Miami Beach enjoys plentiful sunshine yearlong. This is undoubtedly a privilege that every architect must take advantage of and control. Over time, the different architectural styles that exist in Miami Beach have successfully embraced this opportunity. Our building, like those that precede us, is firmly committed to taking advantage of natural light and will achieve this with a twofold strategy. First, we will provide indirect lighting to office spaces and its users. For this, wide overhangs are designed to avoid direct sunlight on the facades and, in turn, allow controlled light to enter the interior of the building. Secondly, direct light is captured in the generous and welcoming space of the lobby. This is achieved through four skylights that allow the sun's rays to be drawn into the heart of the building. This is one way in which our design integrates one of Miami Beach's most valuable natural resources: sunshine.

08 Color

The Ocean Beach district is characterized by white structures. White is an excellent color for tropical climates and marine environments such as Miami Beach. Our project will be built in white to complement the nearby neighborhood buildings. Stone and white stucco will be combined on the ground floor and white painted concrete on the upper floors. A white pergola is also projected on the roof to shade the building as are white-painted railings on all the balconies. Thereby, our white-colored building will respect the history of Miami Beach.

09 Historic House

The existing Historic House located on the property is part of Miami Beach's rich and abundant Architectural History. The main objective of our project, and indeed our firm's practice, is to be respectful of the project's context and its local history. 411 Michigan holds special importance to this part of Miami's heritage and our project. Furthermore, our intention is not only to preserve the home but to update its function to be fully incorporated into the current life of Miami Beach. To achieve this, we re-positioned it closer to the sidewalk on Michigan Avenue in such a way that it naturally relates to the new office building and enjoys a greater urban presence.

In its new location, the house will be unobstructed from view for the neighborhood to enjoy. The house's relocation will also allow the Historic home and adjacent historic buildings to form a new historic frontage for the neighborhood. The new development represents a fantastic opportunity to reinforce the historical character of this unique and important site, serving as a threshold for the Ocean Beach Historical District. Our goal is to integrate the contributing structure into our master plan, and through adaptive reuse, ensure that it is integral to the everyday use and function of the project, while also weaving into the fabric of the neighborhood.

These modifications will allow this piece of heritage to be visible from the surrounding public spaces and reinforce the historical character of the street. These actions place the Historic House at the forefront, where it can be viewed as an introduction to the historical Neighborhood as you come off 5th Street and travel down Michigan Avenue.

We will preserve the stucco white finish, scalloped parapet with barrel tiles, clay tile attic vents, and roof features as well as the exterior stairs with stucco walls. Tropical vegetation will be planted around the Historic House and the building will be raised above grade, becoming resistant against flooding to follow the resiliency guidelines set forth by the City of Miami Beach.

10 Parking Structure

The integration of the garage structure is also a key element for us to create a cohesive design, embracing old and new. This structure incorporates and reinterprets local building materials, such as breeze block, and serves as a transitional piece of architecture connecting the historic structure to the modern building. The three elements of the site represent a transition in scale, architecture, and history creating a linear relationship that speaks to the history of South Beach, while also protecting, amplifying, and highlighting how historic and modern architecture can contribute equally to a city's tapestry and co-exist. The parking structure will be set back from the Historic House to allow the house to serve as a foreground building giving it the prominence it deserves.

Our project aims to contribute a new and valuable piece of architecture for Miami Beach, while also integrating environmental sustainability, adaptive reuse of a historic house, and reflecting an appreciation of the surrounding history and context through a master plan that celebrates the neighborhood's past and future.



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

20' 40' 80'

1 Michigan Avenue Miami Beach, Florida

Project Statement



Final Submittal **14 March 2022**


A6.2

COPYRIGHT (C) 2020 CUBE 3 LLC, ALL RIGHTS RESERVED

FL License No. AR93391

Signature Projects by Alberto Campo Baeza

Cádiz, Spain HOUSE OF THE INFINITE



Granada, Spain

CAJA DE GRANADA



Garrison, NY, USA

OLNICK SPANU HOUSE



Zamora, Spain

OFFICES FOR JUNTA DE CASTILLA Y LEÓN





Final Submittal 14 March 2022

A6.3 COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

A.7.0 Project Imagery

| | - 9 J |
|-------|---------------------------------------|
| A7.1 | Rendering Across 5th Street |
| A7.2 | Rendering 5th Street & Michigan Ave |
| A7.3 | Rendering 4th Street & Michigan Ave |
| A7.4 | Rendering Eastbound on 5th Street |
| A7.5 | Details Slab Edge |
| A7.6 | Details Parking Structure |
| A7.7 | Details Railing |
| A7.8 | Details Skylight |
| A7.9 | Details Podium |
| A7.10 | Details Canopy |
| A7.11 | Materials Board |
| | |



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Final Submittal 14 March 2022

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED



Final Submittal

14 March 2022

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED



Angle 5 Virtual Photo




Final Submittal 14 March 2022

A7.2



Angle 6 Virtual Photo








Jonathan W. Cardello, AIA

FL License No. AR93391

NOTE: RENDER TO BE UPDATED TO SHOW GROUND LEVEL STEPS AND PLANTERS. SEE SHEETS A2.5, A3.3, & A5.16 FOR REFERENCE

Angle 1 Virtual Photo



Final Submittal **14 March 2022**

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED




A7.4



NOTE: RENDER TO BE UPDATED TO SHOW GROUND LEVEL STEPS AND PLANTERS. SEE SHEETS A2.5, A3.3, & A5.16 FOR REFERENCE


Angle 4 Virtual Photo



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579 Jonathan W. Cardello, AIA FL License No. AR93391

CUBE 3

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED





MULTISPORT PAVILION FRANCISCO DE VITORIA UNIVERSITY - MADRID (SPAIN) ALBERTO CAMPO BAEZA 2017

6'-5" (STRUCTURE)

7'-4" (AXES)

7'-4" (AXES)

6'-5" (STRUCTURE)

7'-4" (AXES)

8) (GLASS/AXES)

3'-8" (GLASS/AXI

3'-8" (GLASS/AXES)

1'-10"

1'-10" SKYLIGHT DETAIL. PLAN/SECTION

3'└8" (GLASS/AXES)

1'-10"


1'-10"

7 9 6 4 | 3



ALBERTO CAMPO BAEZA 2003







- 1. DOUBLE THERMAL LAMINATED LOW IRON GLASS
- 2.- ALUMINIUM FRAME (COLOR -WHITE)
- 3.- STRUCTURAL SEALANT

3RD FLOOR

+33' (+46' N.G.V.D.)

- 4.- STEEL FOLDED SHEET (COLOR -WHITE) (ONE SINGLE PIECE) 5.- THERMAL INSULATION
- 6.- WATERPROOFING MEMBRANE
- 7.- 2' x 2' THASSOS MARBLE STONE OR SYNTHETIC EQUIVALENT 8.- CONCRETE PEDESTAL SET WITH MORTER
- 9.- MORTER PROTECTIVE LAYER 10.- GEOTEXTILE SHEET
- 11.- REINFORCED CONCRETE WALL TO FINISH WATERPROOFING MEMBRANE AND SUPPORT SKYLIGHT FRAME.
- 12.- GYP BOARD PAINTED WHITE
- 13.- SLOPE: LIGHT CONCRETE LAYER
- 14.- CONCRETE SLAB
- 15.- GAP BETWEEN GLASS/STONE TILES (≈1/3")

FLOOR: MARBLE PAVING or SYNTHETIC EQUIVALENT (COORDINATED TO SKYLIGHTS GLASS SIZE)

HORIZONTAL SKYLIGHT: GLASS FLUSH WITH PAVING DOUBLE LAMINATED SAFETY GLASS (LOW IRON)

CONCRETE STRUCTURE



Slab Edgel Details
Scale: NTS

Final Submittal 14 March 2022

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

CUBE 3


CUBE 3, LLC


111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579


Jonathan W. Cardello, AIA


FL License No. AR93391


Michigan Avenue Miami Beach, Florida
















SECTION - NO SCALE









COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

FL License No. AR93391

CUBE 3

CUBE 3, LLC

111 SW 3rd Street, Floor 4


Miami, Florida 33133

License No. L18000278579

Jonathan W. Cardello, AIA

20' 40'

411 Michigan Avenue Miami Beach, Florida





MULTISPORT PAVILION FRANCISCO DE VITORIA UNIVERSITY - MADRID (SPAIN) ALBERTO CAMPO BAEZA 2017

6'-5" (STRUCTURE)

7'-4" (AXES)

7'-4" (AXES)

6'-5" (STRUCTURE)

7'-4" (AXES)

-8) (GLASS/AXES)

3'-8" (GLASS/AX

3'-8" (GLASS/AXES)

1'-10"

1'-10" SKYLIGHT DETAIL. PLAN / SECTION

3'-8" (GLASS/AXES)

1'-10"

1'-10"

7 9 6 4 |8 | 10 | 5 |



SM GROUP HEADQUARTERS - MADRID (SPAIN) ALBERTO CAMPO BAEZA 2003



3RD FLOOR

+33' (+46' N.G.V.D.)

1. DOUBLE THERMAL LAMINATED LOW IRON GLASS

2.- ALUMINIUM FRAME (COLOR -WHITE)

PRELIMINARY ALUMINIUM FRAME DETAIL

3.- STRUCTURAL SEALANT

4.- STEEL FOLDED SHEET (COLOR -WHITE) (ONE SINGLE PIECE) 5.- THERMAL INSULATION

6.- WATERPROOFING MEMBRANE

7.- 2' x 2' THASSOS MARBLE STONE OR SYNTHETIC EQUIVALENT

8.- CONCRETE PEDESTAL SET WITH MORTER

9.- MORTER PROTECTIVE LAYER

10.- GEOTEXTILE SHEET

11.- REINFORCED CONCRETE WALL TO FINISH WATERPROOFING MEMBRANE

AND SUPPORT SKYLIGHT FRAME.

12.- GYP BOARD PAINTED WHITE

13.- SLOPE: LIGHT CONCRETE LAYER

14.- CONCRETE SLAB

15.- GAP BETWEEN GLASS/STONE TILES (≈1/3")

FLOOR: MARBLE PAVING or SYNTHETIC EQUIVALENT (COORDINATED TO SKYLIGHTS GLASS SIZE)

HORIZONTAL SKYLIGHT: GLASS FLUSH WITH PAVING DOUBLE LAMINATED SAFETY GLASS (LOW IRON)

CONCRETE STRUCTURE



Final Submittal 14 March 2022

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

CUBE 3

CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

Michigan Avenue Miami Beach, Florida


Details :NTS **Skylight**Scale: N


411 Michigan Avenue Miami Beach, Florida


Podium Details
Scale: NTS





Final Submittal 14 March 2022















STONE



ORIGIN OF LAYOUT

ORIGIN OF LAYOUT

_____ORIGIN OF LAYOUT

FLOOR PLAN - NO SCALE TYPICAL STONE: FLOOR (3' x 3' x 2") & WALL (3' x 2.5' x 2") CORNER STONE - BIG DIMENSION (EMPTYING)

ORIGIN OF LAYOUT

ORIGIN OF LAYOUT SINGULAR DIMENSION STONE.

DETAIL 1

3'-3 1/4" | 2'+5 1/2"

WEST ELEVATION



Jonathan W. Cardello, AIA

FL License No. AR93391

0' 20' 40' 80'

411 Michigan Avenue Miami Beach, Florida

Trellis Details
Scale: NTS



Final Submittal 14 March 2022

A7.10

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED







Stucco Color: White



Glass Color - Common Areas Color: Clear



Aluminum Color Color: White



Thassos Stone Wall Color: White | Pattern to be refined

Final Submittal 14 March 2022

A7.11 COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

C1.0 Civil Information

| • | iidtioii |
|---|-----------------------------------|
| 1.1 | Employee Ingress Circulation |
| 1.2 | Employee Ingress / Visitor Egress |
| 1.3 | Employee Egress Circulation |
| 1.4 | Basement Parking Ingress |
| 1.5 | Basement Parking Egress |
| | |



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391


Final Submittal 14 March 2022

C1.0

COPYRIGHT (C) 2020 CUBE 3,
LLC, ALL RIGHTS RESERVED

EMPLOYEE INGRESS





PASSENGER VEHICLE

Width : 7.00
Track : 6.00
Lock to Lock Time : 6.0
Steering Angle : 31.6

CUBE 3



Final Submittal 14 March 2022

C1.1

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED


EMPLOYEE INRESS / VISITOR EGRESS






Jonathan W. Cardello, AIA

FL License No. AR93391





PASSENGER VEHICLE

Width : 7.00
Track : 6.00
Lock to Lock Time : 6.0
Steering Angle : 31.6

411 Michigan Avenue Miami Beach, Florida

Employee Ingress / Visitor Egress Circulation





C1.2

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

EMPLOYEE EGRESS







PASSENGER VEHICLE

| | feet |
|-------------------|--------|
| Width | : 7.00 |
| Track | : 6.00 |
| Lock to Lock Time | : 6.0 |
| Steering Angle | : 31.6 |

CUBE 3

CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579


Jonathan W. Cardello, AIA


FL License No. AR93391




COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

BASEMENT INGRESS








PASSENGER VEHICLE


| | feet |
|-------------------|--------|
| Width | : 7.00 |
| Track | : 6.00 |
| Lock to Lock Time | : 6.0 |
| Steering Angle | : 31.6 |




C1.4

BASEMENT EGRESS







PASSENGER VEHICLE


Width : 7.00
Track : 6.00
Lock to Lock Time : 6.0
Steering Angle : 31.6



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391



411 Michigan Avenue Miami Beach, Florida

Basement Parking Circulation Scale: NTS



Final Submittal **14 March 2022**

C1.5

COPYRIGHT (C) 2020 CUBE 3,
LLC, ALL RIGHTS RESERVED

L1.0 Landscape Plans

L1.11

| L1.1 | Notes |
|-------|---|
| L1.2 | Arborist Report A |
| L1.3 | Arborist Report B |
| L1.4 | Tree Disposition Plan |
| L1.5 | Tree Disposition Schedule |
| L1.6 | Site Planting Plan |
| L1.6A | Site Planting Plan Future Alternative |
| L1.7 | Site Planting Schedule |
| L1.8 | Mezzanine & Parking Structure Roof Pla |
| L1.9 | Atrium Planting Plan |
| L1.10 | Roof Planting Plan |
| | |

Planting Details



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Final Submittal 14 March 2022

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

GENERAL LANDSCAPE NOTES

REFER TO ARCHITECTURE FOR SITE, BUILDING, AND ZONING INFORMATION.

- 1. The Contractor shall be responsible for verifying all underground utilities prior to digging in any area. The Contractor shall notify all necessary utility companies 48 hours minimum prior to digging for verification of all underground utilities, irrigation and all other obstructions and coordinate with Owner's Representative prior to initiating operations. Drawings are prepared according to the best information available at the time of preparing
- 2. The Contractor is responsible to ensure proper watering and maintenance of new and relocated materials during the warranty period.
- 3. Contractor is to report any discrepancies between the construction drawings and field conditions to the Owner immediately
- 4. All planting materials shall meet or exceed Florida Grade # 1 as specified in Grades and Standards for Nursery Plants and Part II, Palms and Trees, current edition
- 5. Contractor shall familiarize himself/herself with existing site conditions prior to initiating planting. All existing site furnishings, paving, landscape and other elements to remain shall be protected from any damage throughout all construction phases unless otherwise noted.
- 6. Landscape Contractor shall coordinate all work with related contractors and with the general construction of the project in order not to impede the progress of the work of others or the Contractor's own work. Landscape contractor shall provide schedule of his/her works two weeks in advance, beginning two weeks prior to commencing landscape trade construction.
- 7. Contractor shall be responsible to remove existing ground cover for all planting beds as specified prior to planting relocated material. Contractor 33. The contractor shall take every precaution to prevent damage to all utilities (both above and below ground) within the project area. Damage to shall be responsible to replace all portions of existing landscape and hardscape areas damaged while completing planting installation with same grass or materials species to the satisfaction of the Owner
- 8. The Contractor shall bear all costs of testing of soils, amendments, etc. associated with the work and included in the specifications. Prior to commencement of the landscape planting work the Contractor shall provide complete soil tests with recommendations for the installation area.
- 9. All plant material that may need to be replaced shall be in full and strict accordance to Florida No. 1 grade, according to the "Grades and Standards for Nursery Plants", published by the Florida Department of Agriculture and Consumer Services, the project manual and/or specifications. Plant material in some cases may exceed Florida No. 1 grade in order to meet the minimum requirements for the project.
- 10. Landscape Contractor shall field stake the location of all plant material prior to initiating installation for the review and approval of the Owner and/ or Landscape Architect.
- 11. Landscape Contractor shall field adjust location of plant material as necessary to avoid damage to all existing underground utilities and/or existing above ground elements. All changes required shall be completed at the Contractor's expense and shall be coordinated with the Owner and the Landscape Architect.
- 12. Any substitutions in size and/or plant material must be approved by the Landscape Architect or Owner prior to modification of the contract, purchasing and delivery of plants. All plants will be subject to approval by Landscape Architect and/or Owner before planting can begin. All plant materials will not include any plants considered to be invasive to South Florida's native plant communities.
- 13. Contractor shall refer to the landscape planting details, general notes and the project manual and/or specifications for further and complete landscape planting instructions
- 14. Landscape Contractor shall coordinate all planting work with permanent or temporary irrigation work. Landscape Contractor shall be responsible for all hand watering as required by Owner to supplement irrigation watering and rainfall.
- 15. Landscape Contractor shall be responsible for hand watering in all planting areas, regardless of the status of existing or proposed irrigation.
- 16. Landscape Contractor shall clean the work areas at the end of each working day. Rubbish and debris shall be collected and deposited off-site

All materials, products and equipment shall be stored in an organized fashion as directed by the Owner.

- 17. Landscape Contractor shall regrade all areas disturbed by plant removal, relocation and/or installation work, Landscape Contractor shall replace (by equal size and quality) any and all existing plant material disturbed or damaged by plant removal, relocation, and/or installation work.
- 18. Guying I staking practices shall not permit nails, screws, wires etc., to penetrate outer surface of tree or palm. Trees or palms rejected due to this practice shall be replaced at the Contractor's expense
- 19. Burlap material, wire cages, plastic straps, etc., must be cut and removed from top one third
- 20. Trees grown in grow bags or grow bag type material are not allowed.
- 21. Plant size specifications take precedence over container size.
- 22. Contractor to verify quantities and report any discrepancies to Owner and/or Landscape Architect.
- 23. Remove and replace sidewalk. Reconstruct swale. Mill and resurface 2in. avg. using type S-III asphalt mix design on the driving lane. Any work and/or improvements to the right of way including landscaping and irrigation require a separate CMB Public Works Department ROW Construction
- 24. The locations of hardscape and landscape, as shown in these plans, are approximate. The final locations may be adjusted to accommodate unforeseen field conditions, to comply with safety setback criteria, to avoid creating unsafe sight conditions, or as otherwise directed by or approved by the landscape architect.
- 25. Existing grades and existing site information shown on this plan is compiled from base information supplied by the surveyor and architect. The contractor is responsible for confirmation of actual site conditions. Urban robot accepts no responsibility for existing topographic and existing site information.

26. The general contractor shall require landscape installation sub-contractor to provide a detailed report and strategy for the transplanting, staging and reuse of any existing trees or palms within the proposed landscape plans. This shall be verified and approved by the landscape architect.

L1

Landscape Plans

Landscape Notes

Arborist Report A

Arborist Report B

Site Planting Plan

Planting Plan

Removed Alternative

Atrium Planting Plan

Roof Planting Plan

Planting Details

Site Planting Schedule

Mezzanine & Parking Roof

Tree Disposition Plan

Tree Disposition Schedule

L1.1

L1.2

L1.3

114

L1.5

L1.6

L1.6a

117

L1.8

119

L1.10

L1.11

- 27. All dimensions and layout information is referenced to coordinates points provided on the survey.
- 28. The contractor shall verify all existing conditions prior to the commencement of work. Any discrepancies shall be reported to the owner's representative immediately
- 29. The contractor shall perform all work in accordance with all local, state and federal regulations and shall obtain all necessary permits for this
- 30. All site work shall be performed in accordance with landscape (I) and, if applicable, civil (c) drawing sets.
- 31. All notes and dimensions are typical unless otherwise noted.
- 32. All dimensions are square (parallel or perpendicular) unless otherwise noted. The contractor shall notify the owner/owner's representative immediately in the event of any discrepancies found in the documents and/or field, or of conditions uncovered in the work which are not reflected in
- any utilities as a result of actions by the contractor shall be restored by the contractor, at his expense, to conditions equal to or better than before the
- 34. Any areas disturbed by equipment, material storage, demolition and/or installation procedures are to be restored to original (or better) condition by contractor before completion of project and are subject to approval by owner's representative. All existing grassed areas not adequately protected and therefore damaged during construction, shall be replaced by the contractor at no additional cost to the owner.
- 35. The contractor is responsible for keeping the site clean of miscellaneous debris throughout the construction period. All waste material is to be disposed of immediately to an off-site location, unless otherwise indicated on the plans.
- 36. Contractor is responsible for general clean-out of all drainage basins (new and existing), manholes and/or other drainage features which have accumulated sediment as a result of construction activities.
- 37. The contractor shall provide all equipment, labor, materials and related work necessary for the prevention and control of dust resulting from operations in the performance of work of this contract. All cost in connection there with shall be considered to be included in the various unit and/or lump sum prices bid for the various item as listed in the bid.
- 38. Contractor shall submit shop drawings and/or samples of all materials to landscape architect as required within the detail drawings and notes.
- 39. All installation shall comply with City of Miami Beach ordinances. All discrepancies shall be notified to Landscape Architect immediately.

111 SW 3rd Street, Floor 4 Miami Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

Site Planting Plan Bus Stop

Michigan Avenue Miami Beach, Florida

Landscape Notes



HPB FINAL SUBMITTAL 09 MARCH 2022

ALVEY TREE Consulting

ALVEY TREE CONSULTING LLC ALEXIS ALVEY ISA BOARD CERTIFIED MASTER ARBORIST®
#NY-5539B

Arborist Report 411 Michigan Avenue Miami Beach

10/18/2021



Tree #5

Common Name

Green Buttonwood

Scientific Name -

Conocarpus erectu

Arborist Report 10/18/2021

On October 13th, 2021 I visited the property located at 411 Michigan Avenue at the request of Urban Robot Associates. I evaluated the trees on the site in anticipation of new construction. For each tree, I confirmed species, location, and size (Height, Spread, DBH); evaluated condition (Poor, Fair, Good); provided relevant comments about health and condition; and took photographs. Street trees are included.

For tree disposition and Tree Protection Zones, please see the landscape plans. For trees and palms that are to remain, protective barriers shall be placed at the dripline or 10ft radius from the trunk, whichever is greater. Barriers shall be installed prior to the start of construction, and shall remain in place until development is completed and until the department authorizes their removal. Barriers shall be a minimum of 4ft high, and shall be constructed of continuous chain link fence with metal posts at 8ft spacing, or of 2x4 posts with three equally spaced 2x4 rails. Posts may be shifted to avoid roots. No materials shall be placed or disposed of within the TPZ. Natural grade shall be maintained within the TPZ.

My findings are summarized in the following pages. This report shall in no shape or form be construed as a tree risk assessment which is beyond the scope of work written in the contractual agreement. Please feel free to contact me should any questions arise. Thank-you for the oppor-tunity to assist in this manner.



ISA Board Certified Master Arborist® #NY-5539B

Alvey Tree Consulting LLC 516-728-1366 alveytree@gmail.com

Property Location -411 Michigan Avenue

Miami Beach, FL 33139

Tree #6

Common Name

Brazilian Pepper

Scientific Name

Client -Urban Robot Associates

Justine Velez, RLA, Principal 420 Lincoln Road, Suite 600, Miami Beach, FL 33139 786.246.4857 / justine@urbanrobot.net

DBH (in) - 16

Height (ft) - 35

DBH (in) - 9.5

Canopy Spread (ft) - 25

DBH (in) - 16.5

Height (ft) - 40

DBH (in) - 14

Height (ft) - 35

Canopy Spread (ft) - 16

Canopy Spread (ft) - 18

Tree #1

Tree #2 Common Name Royal Palm

Scientific Name

Roystonea regia

Common Name

Scientific Name

Tree #1 is a Royal Palm street tree located along Fifth Street. It is growing in a sidewalk cut-out. The tree is in fair condition with a sharply pencilling trunk and

ree #2 is a Royal Palm street tree located along Fifth street. It is growing in a sidewalk cut-out. The tree is n fair condition with a sharply pencilling trunk and hlorotic foliage.

Condition



Tree #3

Common Name -

Scientific Name -

ee #3 is a Royal Palm street tree located along Fifth reet. It is growing in a sidewalk cut-out. The tree is fair condition with a sharply pencilling trunk and

Condition -

Native? -



Tree #4 **DBH (in)** - 16 Common Name -

Royal Palm Scientific Name Roystonea regia

Tree #10

Common Name

Scientific Name

Height (ft) - 33 Canopy Spread (ft) - 18

DBH (in) - 17

Height (ft) - 35

Canopy Spread (ft) - 16



ee #4 is a Royal Palm street tree located along Fifth reet. It is growing in a sidewalk cut-out. The tree is in od condition with a healthy green canopy.

ALVEY TREE CONSULTING

Tree #8

Mahogany

Tree #9

Mahogany

Common Name

Scientific Name -

Common Name

Scientific Name

DBH (in) - 10.5 Height (ft) - 18 Canopy Spread (ft) - 8

ree #8 is a Mahogany located on the south side of the property. It is in poor condition with a small canopy. The



DBH (in) - 13

Height (ft) - 30

Canopy Spread (ft) - 12

Tree #10 is a Sabal Palm located on the south side of the

Native?

Native? -

Tree #11

Common Name -Foxtail Palm

Scientific Name -

Height (ft) - 20 Canopy Spread (ft) - 15

DBH (in) - 8.5



e #11 is a Foxtail Palm located on the south side of the perty. It is in poor condition with a pencilling trunk d chlorotic foliage.





DBH (in) - 48

Height (ft) - 28

Canopy Spread (ft) - 40

street tree located along Fifth Street. t is growing in a planting swale that mately 13ft wide at its idest. the tree is multi-trunked and was haracked previously, and now a dead trunk is present (circled in red, below left). Many of the trunks have included bark and there is decay in the tree crotch (circled in red, below right). The canopy hangs low over the stream the canop knags low over the stream of with only approximately left of overhead clearance. This is hazardus for taller pedestrains. A number of other limbs in the canopy have been hartacked. There are large surface roots throughout the entire planting swale are. If this tree is proposed to remain, a tree risk assessment is recommended. as hatracked previously, and now a Tree #7 Common Name -Mahogany

Tree #5 is a large Green Buttonwood

Height (ft) - 35 Scientific Name -Canopy Spread (ft) - 12 Swietenia mahaaoi

recently a Mainingain located on the south side of the oroperty. It is in fair condition with a narrow columnar tabit. It is growing through the canopy of Brazilian depper #6 and is competing with it. There is an injury to

e property. The tree is in good condition. It has a dense snopy and has grown quite tall for a Pepper.

Native?

fore need to be removed



Tree #9 is a Mahogany located on the south side of the property. It is in poor condition. There is little that remains of the canopy. Many limbs have been removed and the tree has poor form. There is an injury on the

Condition



DBH (in) - 14.5

Height (ft) - 40

Canopy Spread (ft) - 15

Tree #12 Notes - TPZ Calculations & Tree and Palm Relocation **DBH (in) -** 10.5 Native?

Condition -

Tree #12 is a Mahogany located in the southwest corner of the property. The tree is in poor condition and has been hatracked. Little canopy remains.

Common Name -

Scientific Name -

Height (ft) - 16

Canopy Spread (ft) - 10

Tree Protection Zone (TPZ) -For trees and palms that are to remain, protective barriers shall be placed at the dripline or 10ft radius

From the trunk, whichever is greater.

For trees and palms that are to relamin, protective barriers shall be placed at the dripline or 1 - 2ft outside the rootball, whichever is greater.

Tree and Palm Relocation Notes -

1. All phases of transplanting trees and palms to be performed or supervised by Certified Arborist.

2. Trees to be relocated shall be root pruned six to eight weeks prior to transplanting. Landscape Contractor shall

maintain transplanted material during construction period by watering, moving, spraying, fertilizing, and pruning.

3. Landscape Contractor is responsible for verifying locations of all underground and overhead utilities and easements

3. Earloscape Contractor is responsible to wreniying locations or an intelligential on the intelligence and easternity prior to commencing work. All utility companies and/or the General Contractor shall be notified to verify locations prior to digging. Utility trenching is to be coordinated with the Landscape Contractor prior to beginning of project. The Owner and Certified Arborist shall not be responsible for damage to utility or irrigation lines.

4. The Landscape Contractor shall comply with all local and state codes and shall be responsible for obtaining all appli-

5. The Landscape Contractor shall regularly inspect the relocated material to ensure compliance with standard horticultural practices.

6. The Landscape Contractor is responsible for guaranteeing the transplanted trees and palms for a period of one year. At the time of the final inspection all transplanted trees and palms that are not in viable condition shall be replaced by the Landscape Contractor.

7. The Landscape Contractor shall take all precautions to minimize shock of root pruning and transplanting in accor-

dance with standard arboriculture practices. 8. The diameter of the root ball to be transplanted shall follow the guidelines set forth in the latest edition of the Florida

Grades and Standards for Nursery Plants

Oracles alto Scandards for Norsery Praints.

9. Roots shall be cleanly cut with a sharp spade, hand saw, chainsaw, or other approved root-pruning equipment.

10. Trees shall not be pruned at transplanting to compensate for root loss. Any pruning required shall be as per the ANSI A300 Standards.

11. For all palms except Sabal palmetto, only dead fronds shall be removed. Sabal palmetto shall have all fronds cut

without damaging the bud. Fronds shall be securely tied around the bud prior to relocation and shall be untied after placement in the new planting hole. The bud shall be protected from damage or injury during relocation.

12. After root pruning trees, backfill roots to original existing grade with existing soil free of any deleterious material to

The rectified purpose of 3" much over backfill area to prevent weed growth, conserve moisture and prevent evaporation. Keep mulch 6" away from the trunk.

14. Provide tree protection as per Landscape Architect's Tree Protection Detail to ensure that the tree or root system is

not damaged during the root-pruning period.

15. After root pruning and prior to relocation, tree(s) shall be watered a minimum of twice weekly.

16. Transplanting shall occur within 24 hours after being dug for relocation. The root ball shall be kept moist.

17. Digging and preparation of the new hole for the transplant shall be done prior to removing the tree from the existing

18. The depth of the new hole shall be equal to the depth of the root ball and the width shall be equal to two to three

19. Trees and palms shall be lifted from the ground with heavy equipment designed specifically for tree relocation so 15. Itees and paints shall be linted from the ground with nearly equipment, designed specifically for tree relocation so that the trunk and crown is not impacted and damaged by the equipment.

20. The slings used to lift the trees and large palms shall be non-binding nylon slings that are wrapped under the root ball to support the weight of tree or palm. Slings shall not be solely wrapped around the trunk of the tree. Padding the

sling may be necessary so that the trunk is not damaged.

Notes - Tree and Palm Relocation (Contd.)

21. Trees and palms shall be planted so that the top of the rootball is flush with the existing grade. Ensure that deep planting does not occur. The tree and palm shall be centrally positioned in the planting hole and set straight, plumb or normal to the growth pattern prior to transplanting.

22. Transplanted trees and palms shall be backfield with a uniform mix of 25% fully decomposed compost and 75%

existing site soil cleaned free of weeds and rocks.

23. Trees and palms shall be watered to eliminate air pockets in the backfill mix prior to mulching

24. A 4" soil berm shall be created around the edge of the planting hole to hold water, or as per the Landscape Archi-

24. A 4" soil berm shall be created around the edge of the planting hole to hold water, or as per the Landscape Architect's Planting Details.

25. Install tree and palm bracing as per the Landscape Architect's Planting Details, to ensure stability of trees and palms.

26. After transplanting trees and palms, the Landscape Contractor shall be responsible for watering to maintain soil moisture during the guarantee period. The following schedule is suggested: First month- Daily; Second month- 3 times per week; Third and Fourth month- 2 times per week; Last Eight months - 1 time per week. For trees over 4" in caliper at the time of planting, the suggested schedule is. First 6 weeks- Daily; from 1.5 months to 6 months - 3 times per week,

Notes - Tree and Palm Protection

1. Fences shall be erected to protect trees and palms to be preserved. Fences define a specific protection zone for each tree or group of trees. Fences shall be installed prior to the beginning of construction and are to remain until all site work has been completed. Fences may not be relocated or removed without the written permission of the Arborist. Refer to the Landscape Architect's Tree Protection Detail.

2. Construction trailers, traffic, and storage areas must remain outside fenced areas at all times.

3. All underground utilities and drain or irrigation lines shall be routed outside the tree protection zone. If lines must traverse the protection area, disturbance shall be minimized by using techniques such as tunneling or boring. 4. No materials, equipment, spoil, or waste or washout water may be deposited, stored, or parked within the tree pro-

5. Additional tree pruning required for clearance during construction must be approved by the Certified Arborist and

shall be performed by trained arborists, not by construction personnel.

6. If injury should occur to any tree during construction, it should be evaluated as soon as possible by the Landscape Contractor and the Certified Arborist should be notified immediately.

7. Any grading, construction, demolition, or other work that is expected to encounter tree roots must be monitored by the Landscape Contractor.

8. All trees shall be irrigated at least two times a week. Each irrigation session shall wet the soil within the tree protections.

tion zone to a depth of 30 inches.

9. Before grading, pad preparation, or excavation for foundations, footings, walls, or trenching near trees the trees shall be root pruned at the edge of the tree protection zone by cutting all roots cleanly to a depth of 36 inches. Roots shall be

to tool planet a tire begin in its deep protection zone by outning an inost cleanly to a deep not so uniness, soots sharing cut manually by digging a trench and cutting exposed roots with a saw, wibsting kinfe, rook saw, narrow trencher with sharp blades, or other approved root-pruning equipment.

10. Any roots damaged during grading or construction shall be exposed to sound tissue and cut cleanly with a saw.

11. Spoil from trenches, basements, or other excavations shall not be placed within the tree protection zone, either

mporarily or permanently. 12. No burn piles or debris pits shall be placed within the tree protection zone. No ashes, debris, or garbage may be

13. Maintain fire-safe areas around the fences. Also, no heat sources, flames, ignition sources, or smoking is allowed

13. Maillatil increase areas around the letters. Ass., in the case assets, memory, assets, assets, as the letter of trees.

14. Protective barriers shall be placed around each tree, cluster of trees, or the edge of the preservation area at the specified distance. Protective barriers shall be a minimum of four feet above ground level and shall be constructed of wood, plastic, or metal, and shall remain in place until development is completed. Protective barriers shall be in place prior to the start of any construction.

Understory plants within protective barriers shall be protected.

13. One excess oil, fill, equipment, building materials or building debris shall be placed within the areas surrounded by protective barriers, nor shall there be disposal of any waste material such as paints, oils, solvents, asphalt, concrete, mortar or any other material harmful to trees or understory plants within the areas surrounded by protective barriers.

17. Trees shall not be braced in such a fashion as to scar, penetrate, perforate or otherwise inflict damage to the tree. 18. Natural grade shall be maintained within protective barriers. In the event that the natural grade of the site is changed as a result of site development such that the safety of the tree may be endangered, tree wells or retaining

walls are required.

19. Fences and walls shall be constructed to avoid disturbance to any protected tree. Post holes and trenches located close to trees hall be dug by hand and adjusted as necessary, using techniques such as discontinuous footings, to avoid damage to major roots.


ALVEY TREE CONSULTING ALVEY TREE CONSULTING ALVEY TREE CONSULTING



LEGEND 000 EXISTING TREE TO REMOVE

REFER TO DISPOSITION FULL SCHEDULE ON SHEET L1.5

| DISPOSITION SCHEDULE | | | | | | | | | |
|----------------------|--------|--------------------------|----------------------------|-------|--------|--------|--|--|--|
| ID | Symbol | Botanical Name | Botanical Name Common Name | | Height | Spread | | | |
| 01 | | Roystonea regia | Royal Palm | 16.5" | 40' | 18' | | | |
| 02 | | Roystonea regia | Royal Palm | 14" | 35' | 16' | | | |
| 03 | | Roystonea regia | Royal Palm | 17" | 35' | 16' | | | |
| 04 | | Roystonea regia | Royal Palm | 16" | 33' | 18' | | | |
| 05 | 0 | Conocarpus erectus | Green Buttonwood | 48" | 28' | 40' | | | |
| 06 | • | Schinus terebinthifolius | Brazilian Pepper | 16" | 35' | 25' | | | |
| 07 | • | Swietenia mahagoni | Mahogany | 9.5" | 35' | 12' | | | |
| 08 | • | Swietenia mahagoni | Mahogany | 10.5" | 18' | 8' | | | |
| 09 | • | Swietenia mahagoni | Mahogany | 14.5" | 40' | 15' | | | |
| 10 | | Sabal palmetto | Sabal Palm | 13" | 30' | 12' | | | |
| 11 | | Wodyetia bifurcata | Foxtail Palm | 8.5" | 20' | 15' | | | |



CUBE 3

CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Tree Disposition Plan Scale: 1" = 20'-0"



HPB FINAL SUBMITTAL 09 MARCH 2022

- Protective barriers shall be placed at the drip line of each tree, cluster of trees, or preservation area, and in no case less than ten feet from the
- trunk of any protected tree, tree cluster or preservation area.

 2. In situations where trees have been transplanted to the project site, the protective fencing shall be placed no closer to the tree than a point one to two feet outside the root ball, or at the drip line, whichever is greater.
- 3. Fenced tree protection zones shall be extended where necessary to protect tree canopies roots.
- 4. If trees are to be preserved in place and root pruning is required to accommodate new construction, the root pruning locations shall be identified and approved by the environment and sustainability department, and fencing shall be installed one to two feet beyond the edge of the root ball. The installation of the fencing shall be coordinated with any phased root pruning.
- 5. All protective barriers shall be installed prior to the start of any construction or site development, including tree removal, demolition or landclearing activities, and shall remain in place throughout all phases of construction. Protective barriers shall be maintained in place until development is completed and shall not be removed until the environment and sustainability department inspects the site and authorizes their removal. 6. Understory plants within areas surrounded by protective barriers shall be protected.
- 7. No disposal of any waste material such as paints, oils, solvents, asphalt, concrete, mortar, or any other material shall occur within the areas - CONTINUOUS CHAINLINK FENCE

 Surrounded by protective barriers.

 8. Natural grade shall be maintained on areas surrounded by protective barriers. In the event that the natural grade of the site is changed as a result of site development such that the safety of the tree may be endangered, tree wells or retaining walls are required.
 - 9. Only hand digging and grading activities will be permitted within the tree protection zone. All surrounding areas must be graded to a point that
 - meets the outside of the tree protection zone. 10. Underground utility lines, including, but not limited to, irrigation, plumbing, electrical, or telecommunication lines, shall be placed outside the
 - areas enclosed by protective barriers. If such placement is not possible, disturbance and root damage shall be minimized by using techniques such as tunneling, hand digging, excavation with an air spade, or the use of overhead utility lines.
 - 11. No vehicles or equipment shall be permitted within areas surrounded by protective barriers. 12. The cutting of roots with a diameter of two inches or larger is prohibited, unless there is no feasible alternative, as determined by the
 - 13. Trees shall be evaluated by the environment and sustainability director to determine whether the root cutting will destabilize the tree or cause unacceptable damage to the tree.
 - 14. Root cuts shall be made, at minimum, a distance from the trunk equivalent to three times the tree's trunk diameter at four and one-half feet above ground unless unavoidable because of sidewalks, pavement, or other infrastructure. Root cuts must be made at a distance from the trunk equivalent to five times the tree's DBH or greater in all other circumstances.

| ١ | Tree Protection Detail |
|---|------------------------|
| Г | |

NOT TO SCALE

| DIS | DISPOSITION SCHEDULE | | | | | | | | | | | |
|-----|----------------------|--------------------------|------------------|-------|--------|--------|--------|----------------|---------|--------|----------|-----------------------|
| ID | Symbol | Botanical Name | Common Name | DBH | Height | Spread | Native | Condition | Protect | Remove | Relocate | Reason for Removal |
| 01 | | Roystonea regia | Royal Palm | 16.5" | 40' | 18' | Υ | FAIR; FDOT ROW | | Х | | |
| 02 | * | Roystonea regia | Royal Palm | 14" | 35' | 16' | Y | FAIR; FDOT ROW | | Х | | |
| 03 | * | Roystonea regia | Royal Palm | 17" | 35' | 16' | Υ | FAIR; FDOT ROW | | Х | | |
| 04 | X | Roystonea regia | Royal Palm | 16" | 33' | 18' | Y | FAIR; FDOT ROW | | Х | | |
| 05 | • | Conocarpus erectus | Green Buttonwood | 48" | 28' | 40' | Υ | POOR; FDOT ROW | | Х | | |
| 06 | • | Schinus terebinthifolius | Brazilian Pepper | 16" | 35' | 25' | N | GOOD | | Х | | INVASIVE |
| 07 | · | Swietenia mahagoni | Mahogany | 9.5" | 35' | 12' | Y | FAIR | | х | | |
| 08 | • | Swietenia mahagoni | Mahogany | 10.5" | 18' | 8' | Υ | POOR | | Х | | |
| 09 | • | Swietenia mahagoni | Mahogany | 14.5" | 40' | 15' | Υ | POOR | | Х | | |
| 10 | * | Sabal palmetto | Sabal Palm | 13" | 30' | 12' | Y | GOOD | | х | | |
| 11 | | Wodyetia bifurcata | Foxtail Palm | 8.5" | 20' | 15' | N | POOR | | х | | |

TOTAL TREES AND PALMS TO BE REMOVED

TREES 109" DBH

PALMS

SEC. 46-61. - TREE REPLACEMENT

SMALL TREES: minimum of 2" DBH x 6' spread in canopy x 12' in height LARGE TREES: minimum of 4" DBH x 8' spread in canopy x 16' in height PALMS: minimum 12 feet overall height with a two-inch DBH

PROPOSED TREES — SEE PLANTING PLANS

STREET TREES

SMALL TREES: 8 8 Silver Buttonwoods*

LARGE TREES: 7 7 Green Buttonwoods*

GROUND FLOOR

SMALL TREES: 8

5 Simpson's stoppers*, 2 Silver Buttonwoods*, 1 White Tabebuia* LARGE TREES: 4

2 Gumbo Limbo*, 2 Satin Leaf*

UPPER STRUCTURE

SMALL TREES: 2

2 Simpson's Stoppers*, LARGE TREES: 1

1 Water Chestnut

TOTAL PROPOSED

18 SMALL TREES + 12 LARGE TREES

*Native trees

REQUIRED MITIGATION

MITIGATION FOR REMOVED TREES:

40 SMALL TREES OR 20 LARGE TREES

TOTAL PROPOSED:

18 SMALL TREES + 12 LARGE TREES

SHORTFALL:

NONE

Disposition Schedule Tree



HPB FINAL SUBMITTAL 09 MARCH 2022

Miami, Florida 33133

License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

Michigan Avenue Miami Beach, Florida

411

environment and sustainability director.


NOTE

REFER TO PLANTING FULL SCHEDULE AND LANDSCAPE LEGEND ON SHEET L1.7

| ĺ | TREE SCHEDULE | | | | | | | |
|-----------|---------------|-----|----------------|----------------------------------|-------------------|--|--|--|
| Symbol ID | | Qty | Botanical Name | Common Name | | | | |
| | BS | BS | 2 | Bursera Simaruba | Gumbo Limbo | | | |
| | | CE | 7 | Conocarpus erectus | Green Buttonwood | | | |
| | COES | CES | 2 | Conocarpus erectus 'Sericeus' | Silver Buttonwood | | | |
| | Ga CES | CES | 8 | Conocarpus erectus 'Sericeus' | Silver Buttonwood | | | |
| | 0 | со | 2 | Chrysophyllum oliviforme | Satin Leaf | | | |
| | 0 | MF | 5 | Myrcianthes fragrans | Simpson's Stopper | | | |
| | K | PE | 11 | Ptychosperma elegans | Solitaire Palm | | | |
| | | ТВ | 1 | Tabebuia bahamensis | White Tabebuia | | | |

| SHRUB SCHEDULE | | | | | | | | |
|--|-----|-----|--|-----------------------|--|--|--|--|
| Symbol | ID | Qty | Botanical Name | Common Name | | | | |
| £ | Ae | 10 | Ardisia escallonioides | Marlberry | | | | |
| | Сс | 2 | Capparis cynophallophora | Jamaica caper | | | | |
| THE STATE OF THE S | Cf | 11 | Cordyline fruticosa | Ti Plant | | | | |
| | lv | 30 | llex vomitoria 'nana' | Dwarf Yaupon Holly | | | | |
| 1111 | Lm | 100 | Liriope muscari | Lily Turf | | | | |
| 7 | Pnp | 283 | Psychodria nervosa "Little Psycho" | Dwarf Wild Coffee | | | | |
| | wa | 3 | Wrightia antidysenterica | Asian Snow | | | | |

| GROUNDCOVER & VINE SCHEDULE | | | | | | | | | |
|-----------------------------|----|------|-----------------------------|-----------------------------|--|--|--|--|--|
| Symbol | ID | QTY | Botanical Name | Common Name | | | | | |
| (BA) | ВА | 3 | Bougainvillea arborea | Vine Bougainvillea | | | | | |
| 1,1,1 | Lm | 170 | Liriope muscari | Lily Turf | | | | | |
| | ag | 5361 | Arachis glabrata | Golden Ornamental Peanut | | | | | |
| \$1.55.57 1.55.57 | sf | 60 | Stephanotis floribunda | Bridal Bouquet | | | | | |
| | tj | 60 | Trachelospermum jasminoides | Confederate Jasmine | | | | | |



CUBE 3

CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Site Planting Plan Scale: 1" = 20'-0"



HPB FINAL SUBMITTAL 09 MARCH 2022


L1.6

REFER TO PLANTING FULL SCHEDULE AND LANDSCAPE LEGEND ON SHEET L1.7

| TREE SCHEDULE | | | | | | | | |
|---|-----|-----|----------------------------------|-------------------|--|--|--|--|
| Symbol | ID | Qty | Botanical Name | Common Name | | | | |
| S S S S S S S S S S S S S S S S S S S | BS | 2 | Bursera Simaruba | Gumbo Limbo | | | | |
| (E. B.) | CE | 8 | Conocarpus erectus | Green Buttonwood | | | | |
| C. S. S. | CES | 2 | Conocarpus erectus 'Sericeus' | Silver Buttonwood | | | | |
| () () () () () () () () () () | CES | 8 | Conocarpus erectus 'Sericeus' | Silver Buttonwood | | | | |
| 0 | СО | 2 | Chrysophyllum oliviforme | Satin Leaf | | | | |
| () | MF | 5 | Myrcianthes fragrans | Simpson's Stopper | | | | |
| X | PE | 11 | Ptychosperma elegans | Solitaire Palm | | | | |
| 7 | ТВ | 1 | Tabebuia bahamensis | White Tabebuia | | | | |

| SHRUB SCHEDU | JLE | | | |
|--|-----|-----|--|-----------------------|
| Symbol | ID | Qty | Botanical Name | Common Name |
| £ | Ae | 10 | Ardisia escallonioides | Marlberry |
| | Сс | 2 | Capparis cynophallophora | Jamaica caper |
| W. W | Cf | 11 | Cordyline fruticosa | Ti Plant |
| | lv | 30 | llex vomitoria 'nana' | Dwarf Yaupon Holly |
| 17.7 | Lm | 1 | Liriope muscari | Lily Turf |
| \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ | Pnp | 8 | Psychodria nervosa "Little Psycho" | Dwarf Wild Coffee |
| | wa | 3 | Wrightia antidysenterica | Asian Snow |

| GROUNDCOVER | R & VINE S | CHEDUL | E | | |
|-------------------------------|------------------------------|-----------------------|-----------------------------|-----------------------------|--|
| Symbol | ID | QTY | Botanical Name | Common Name | |
| (BA) | BA 3 Bougainvillea arborea | | Vine Bougainvillea | | |
| 1,1,1 | Lm | 7,443 | Liriope muscari | Lily Turf | |
| | ag | 5361 Arachis glabrata | | Golden Ornamental Peanut | |
| (-7.6.) (-7.6.) (-7.6.) | sf 60 Stephanotis floribunda | | | Bridal Bouquet | |
| | tj | 60 | Trachelospermum jasminoides | Confederate Jasmine | |



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Site Planting Plan Scale: 1" = 20'-0"

HPB FINAL SUBMITTAL 09 MARCH 2022

L1.6a

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

| LA | NDSCAPE LEGEND | | |
|----|--|-----------|----------|
| | CITY OF MIAMI BEACH | | |
| | LANDSCAPE LEGEND | | |
| | INFORMATION REQUIRED TO BE PERMANENTLY AFFIXED TO PLANS Zoning District C-PS2 Lot Area 21,000 Acre | es0.48 | _ |
| | | REQUIRED/ | |
| | OPEN SPACE | ALLOWED | PROVIDED |
| A. | Square feet of required Open Space as indicated on site plan: Lot Area = $\underline{21,000}$ s.f.x $\underline{}$ s.f. | | |
| В. | Square feet of parking lot open space required as indicated on site plan: | | |
| _ | Number of parking spaces x 10 s.f. parking space = Total square feet of landscaped open space required: A+B= | | |
| C. | Total square feet of landscaped open space required. A+b= | | |
| | LAWN AREA CALCULATION | | |
| | Square feet of landscaped open space required | | |
| В. | Maximum lawn area (sod) permitted= 20 % x $21,000$ s.f. | 4,200 | 0 |
| | <u>TREES</u> | | |
| A. | Number of trees required per lot or net lot acre, less existing number of | | |
| | trees meeting minimum requirements= | 10 | 40 |
| D | 0.48 trees x22 net lot acres - number of existing trees= % Natives required: Number of trees provided x 30% = | 10 4 | 12 |
| | % Natives required: Number of trees provided x 30% = % Low maintenance / drought and salt tolerant required: | 4 | |
| С. | Number of trees provided x 50%= | 6 | 12 |
| D. | Street Trees (maximum average spacing of 20' o.c.) | | |
| | linear feet along street divided by 20'= | 15 | 15 |
| E. | Street tree species allowed directly beneath power lines: | | |
| | (maximum average spacing of 20' o.c.): | | |
| | N/A linear feet along street divided by 20'= | N/A | N/A |
| | <u>SHRUBS</u> | | |
| A. | Number of shrubs required: Sum of lot and street trees required x 12= | 300 | 282 |
| В. | % Native shrubs required: Number of shrubs provided x 50%= | 113 | 55 |
| | | | |
| ^ | LARGE SHRUBS OR SMALL TREES | | |
| A. | Number of large shrubs or small trees required: Number of required shrubs x 10%= | 30 | 25 |
| В. | % Native large shrubs or small trees required: Number of large shrubs or | | |
| | small trees provided x 50%= | 15 | 22 |

NOTE

4 Additional trees on structure (1 Pachira aquatica, 2 Simpson's Stoppers)

1737 Additional shrubs on Roof (1737 Clusia Nana)

58 Additional large shrubs on Roof (58 Bougainvillea)

| | | | | Ground Lo | evel Tree Sc | hedule | | | |
|--------|-----|-----|----------------------------------|-------------------|--------------|-------------------------|--------|--------|---|
| Symbol | ID | Qty | Botanical Name | Common Name | Cal | Height | Spread | Native | Remarks |
| BS | BS | 2 | Bursera Simaruba | Gumbo Limbo | 4" min | 16' min | 10' | Υ | Florida Fancy; Field Grown, 5'CT, Red Peeling Trunk. Lot Tree |
| | CE | 7 | Conocarpus erectus | Green Buttonwood | 6"-8" min | 24' OA | 12' | Y | 8' CT, FL#1, Single Leader. Field Grown or Collected. Matching heights. Street Trees |
| CES | CES | 2 | Conocarpus erectus 'Sericeus' | Silver Buttonwood | 9" min | 14' min | 8' | Υ | 4' CT, Florida Fancy, Multi- stemmed; Lot Tree |
| C CES | CES | 8 | Conocarpus erectus 'Sericeus' | Silver Buttonwood | 12" min | 16' OA | 10' | Y | 4' CT, Florida Fancy, Multi- stemmed 3-4" per stem. Field Grown or Collected. Matching heights. Street Trees |
| | СО | 2 | Chrysophyllum oliviforme | Satin Leaf | 4" Min | 16' min | 20' | Υ | 5' CT, Florida Fancy, Single Leader, Field Grown. Lot Tree |
| | MF | 5 | Myrcianthes fragrans | Simpson's Stopper | N/A | 12' min | 8' | Υ | 5' CT, Florida Fancy, Multi- stemmed; Lot Trees |
| | PE | 11 | Ptychosperma elegans | Solitaire Palm | | Staggered: 8', 12', 16' | | | |
| E | ТВ | 1 | Tabebuia bahamensis | White Tabebuia | 2" Min | 10' min | 10' | Υ | 4' CT; Florida Fancy; Multi- stemmed; Lot Trees |

| | | | | Ground Level S | Shrub Sc | hedule | | | | |
|---|-----|-----|--|-----------------------|----------|--------|--------|-------------|--------|---------------|
| Symbol | ID | Qty | Botanical Name | Common Name | Size | Height | Spread | Spacing | Native | Remarks |
| () | Ae | 10 | Ardisia escallonioides | Marlberry | 3 gal | 2' | 2' | See Plan | Υ | Shrub |
| | Сс | 7 | Capparis cynophallophora | Jamaica caper | 15 gal | 4' | 4' | See Plan | Υ | Large Shrub |
| W. S. | Cf | 11 | Cordyline fruticosa | Ti Plant | 5g | 3' | 2' | | | |
| | lv | 30 | llex vomitoria 'nana' | Dwarf Yaupon Holly | 7 gal | 2' | 2' | 30" OC | Υ | Shrub |
| 1,1,1 | Lm | 1 | Liriope muscari | Lily Turf | 1 gal | 12" | 12" | 18" | 2 | Shrub |
| < 7 | Pnp | 8 | Psychodria nervosa "Little Psycho" | Dwarf Wild Coffee | 3 gal | 24" | 24" | 24" | Υ | Shrub |
| | wa | 227 | Wrightia antidysenterica | Asian Snow | 3 gal | | | 10" | N | Lower Terrace |

| | | | | Ground Level Groun | dcover & | Vine Scho | edule | | | | |
|---------|----|------|-----------------------------|-----------------------------|----------|-----------|--------|---------|--------|--------------|---------------------------------------|
| Symbol | ID | QTY | Botanical Name | Common Name | Size | Height | Spread | Spacing | Native | Area (sf) | Remarks |
| ВА | BA | 3 | Bougainvillea arborea | Vine Bougainvillea | | 8'-10' | | | N | 0 | Purple, Trained to Wood Trellis |
|),',',' | Lm | 170 | Liriope muscari | Lily Turf | 1 gal | 12" | 12" | 18" | 2 | 553 | Shrub |
| | ag | 5361 | Arachis glabrata | Golden Ornamental Peanut | 1 gal | | | 10" | N | 1,874 | Sidewalk improvements |
| | sf | 60 | Stephanotis floribunda | Bridal Bouquet | 3 gal | | | 5' | Υ | 129 | Twining Vine |
| | tj | 60 | Trachelospermum iasminoides | Confederate Jasmine | 3 gal | | | 5' | Υ | 182 | Twining Vine |



CUBE 3, LLC 111 SW 3rd Street, Floor 4 Miami, Florida 33133 License No. L18000278579

Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Site Planting Schedule



HPB FINAL SUBMITTAL 09 MARCH 2022

L1.7

Jonathan W. Cardello, AIA

FL License No. AR93391


411 Michigan Avenue Miami Beach, Florida

Mezzanine & Parking Roof Planting Plan Scale: 1" = 20'-0"




HPB FINAL SUBMITTAL 09 MARCH 2022

L1.8



| | Mezzanine Shrub Schedule | | | | | | | | | |
|--------|--------------------------|-----|--------------------------|--------------------|-------|--------|--------|---------|--------|------------------------------------|
| Symbol | ID | Qty | Botanical Name | Common Name | Size | Height | Spread | Spacing | Native | Remarks |
| Bay | Ва | 17 | Bougainvillea arborea | Vine Bougainvillea | 25gal | 8'-10' | 3' | | IN | Purple, Trained to Wood Trellis |

| | Mezzanine Groundcover & Vine Schedule | | | | | | | | | | | |
|-----|---------------------------------------|----|-----|--|----------------------------------|------|--------|--------|---------|--------|--------------|--------------------------------------|
| Syn | mbol | ID | QTY | Botanical Name | Common Name | Size | Height | Spread | Spacing | Native | Area (sf) | Remarks |
| (| 3 | pm | 30 | Podocarpus macrophyllus 'Pringles' | Dwarf Podocarpus - 'Pringles' | 3gal | | | 24" | N | 0 | Hedge in Freestanding Planters |




5th STREET

MEZZANINE PLANTING PLAN SCALE: 1" = 20'

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

| | Atrium Tree Schedule | | | | | | | | |
|--------|----------------------|-----|------------------|----------------|-----|--------|--------|--------|--------------------|
| Symbol | ID | Qty | Botanical Name | Common Name | Cal | Height | Spread | Native | Remarks |
| - | PA | 1 | Pachira aquatica | Water Chestnut | 6" | 18' | 10' | N | Collected specimen |



Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Atrium Planting Plan Scale: 1" = 20'-0"



HPB FINAL SUBMITTAL 09 MARCH 2022

L1.9

COPYRIGHT (C) 2020 CUBE 3,
LLC, ALL RIGHTS RESERVED

| CUBE 3 | |
|-------------|--|
| CUBE 3, LLC | |

Jonathan W. Cardello, AIA

FL License No. AR93391

411 Michigan Avenue Miami Beach, Florida

Roof Planting Plan Scale: 1" = 20'-0"



HPB FINAL SUBMITTAL 09 MARCH 2022

L1.10

COPYRIGHT (C) 2020 CUBE 3, LLC, ALL RIGHTS RESERVED

Roof Tree Schedule

Symbol ID Qty Botanical Name Common Name Cal Height Spread Native Remarks

BA 16 Bougainvillea arborea Tree Bougainvillea 12'-14' N FL#1, Purple


| | Roof Shrub Schedule | | | | | | | | | | | |
|--------|---------------------|--------|----|------------------|-------------------|-----|---------------|----|----------------|---|---------|--|
| Symbol | | ID Qty | | Botanical Name | Common Name Size | | Height Spread | | Spacing Native | | Remarks | |
| | | Cg | 42 | Clusia guttifera | Small Leaf Clusia | 15g | 5' | 5' | 3' | N | FL #1 | |


| Roof Groundcover Schedule | | | | | | | | | | | |
|---------------------------|----|-------|---------------------|-------------------|------|--------|--------|---------|--------|--------------|---------|
| Symbol | ID | QTY | Botanical Name | Common Name | Size | Height | Spread | Spacing | Native | Area (sf) | Remarks |
| 10.55 10.555 | Cr | 1,597 | Clusia rosea 'nana' | Dwarf Pitch Apple | 3g | 18" | 12" | 18" | N | 3,113 | FL #1 |


00 00 00 (3) (3) Ø 0 0 **₩** ₩ 0 0 0 0 0 CAFE / JUICE BAR

ICHIGAN AVENITE


09 MARCH 2022









Tree Protection Detail NOT TO SCALE




SHRUB DETAIL 5 NOT TO SCALE




GROUNDR SPACING DETAIL NOT TO SCALE



LARGE TREE STAKE DETAIL NOT TO SCALE



TREE TRANSPLANTING DETAIL 2 NOT TO SCALE



ROOT PRUNING DETAIL NOT TO SCALE

4. All trees must be guyed or staked as shown in the details.

3. All plant material shall be protected during transport and delivery to final location with shade cloth or other acceptable means of windburn prevention.

PLANTING SPECIFICATIONS

5. Installation- All plant material shall be installed in a sound, workman- like manner and according to accepted good planting and tree relocation procedures with the quality of plant materials as hereinafter described. All elements of landscaping shall be installed so as to meet all applicable ordinances and code requirements.

1. The Contractor is responsible for maintaining, all planting areas (including watering, spraying, mulching, mowing, fertilizing, etc.) until the job is accepted, in full, by the Owner and/or Landscape

6. There shall be no chains or cables used on trees or palms. Handle with two inch (2") minimum width nylon straps or equal

2. All root balls shall conform to the size standards set forth in "American Standards for Nursery Stock".

- 7. Contractor shall assure drainage and percolation of all planting pits prior to installation of plant material. Contractor shall fill all tree pits with water before planting to assure that proper drainage and percolation is available. Correct if required to assure percolation. Contractor is responsible for replacement of all plants lost due to inadequate drain- age conditions.
- 8. Contractor to request final acceptance of project in writing. If all work is satisfactory and complete in accordance with conditions of contract documents, then the Owner and the Landscape Architect shall declare the project substantially complete.
- 9. Contractor to replace rejected plant material within one (1) week of written notice.
- 10. Contractor shall mulch all plant material throughout and completely to a three inch (3") depth of loose, weed free, sterilized Melaleuca mulch.
- 11. Plant Material which is not installed at the direction of the landscape architect or owner will become the property of the contractor unless it becomes relocated on site. The Contractor shall provide the owner a credit for any plant material not installed on the site.

SOIL PREPARATION AND SOIL MIX

- 1. All shrub beds shall be provided with a minimum 30" depth of approved planting soil if existing soil is not acceptable to the Landscape Architect. Shrub beds shall be excavated to 30" depth and soil replaced as specified. Acceptable soil composition shall be 70% sand, 30% organic content with an overall pH range between 6.5 and 7.5.
- 2. Apply Roundup (manufactured by Monsanto Corp. or equal.) according to manufacturer's rate and specification within limits of all areas to be planted. Protect existing plants to remain from overspray or spray within root zone. Contractor to ensure total weed eradication from all areas to be planted.
- 3. Before replacing topsoil, rake subsoil surface clear of stones (1" diameter and larger), debris, rubbish, and remaining roots from removed plant material.
- 4. Scarify subsoil to a depth of six inches (6").
- 5. Contractor to apply "Surflan" or equal, or approved pre-emergent herbicide in accordance with manufacturer's rate and specifications.
- 6. Planting Soil Mixtures:

All plant material on grade with the exception of palms and beach material, shall be planted with the following soil mix:

Planting Soil Mixture A:

a.) Weed free soil and consist of

70% clean silica sand.

- 30% everglades muck, and
- b.) There must be a slight acidic reaction to the soil with no excess calcium or carbonate.
- c.) Soil shall be delivered in a loose friable condition

All palms + beach material on grade shall be planted with the following: Planting Soil Mixture B:

- a.) 80% clean sillca sand
- b.) 20% everglades mack
- All elevated planting areas on structure shall be planted with the following unless otherwise approved by L.A Planting Soil Mixture C:

Mix specifically designed to meet project requirements based on climatic region and plant requirements

- a.) Coarse Stalite, 3/8" Expanded Slate 50%
- b.) Fine Stalite Expanded Slate 10%
- c.) USGA Root Zone Sand 25%
- d.) Approved Compost 15%
- 7. Topsoil shall be natural, fertile, agricultural soil capable of sustaining vigorous plant growth. It shall be of uniform composition throughout, with admixture of subsoil. It shall be free of stones, lumps, live plants an their roots, sticks, and other extraneous matter. Spread topsoil mixture to minimum depth of three inches (3") throughout all lawn areas .
- 8. Remove all rocks and other objects over one inches (1") in diameter.
- 9. Smooth all soil mixture to five inches (5") below top of surrounding pavement edges. This allows room for 3" of mulch and 2" clear space below top of pavement.
- 10. Smooth topsoil mixture to two inches (2") below finish grade in areas to be sodded.
- 11. Topsoil shall not be extremely acid or alkaline, nor contain toxic substances which may be harmful to plant growth. The topsoil pH shall be in the range of pH 6.5 to 7.5. If necessary, the Contractor shall apply the appropriate soil amendments adjusting soil pH to assure a pH range of 6.5 to 7.5.
- 12. Finish grade all topsoil areas to a smooth, even surface, assuring positive drainage away from the structures and eliminate any low areas which may collect water.
- 13. Contractor shall assure percolation and drainage of all planting pits prior to planting. Contractor will be responsible for all plants lost due to the lack of percolation.
- 14. Contractor to remove debris and excess material daily from job site. Contractor shall remove all staking of trees and palms after twelve (12) months of substantial completion.

- 1. Mulch shall be shredded Florimulch (100% Melaleuca mulch). Planting areas not covered by lawn grass/sod shall be mulched to a minimum depth of 3", in order to present a finished appearance.
- 2. Any other mulch must be must be submitted to and approved.

