


## LEGEND



COVERED AREA

### **EXISTING LOT COVERAGE CALCULATION**

TOTAL LOT COVERAGE EXIST. PERCENTAGE	2,345 Sq. Ft. 21.6%
1ST FLOOR	1,985 Sq. Ft.
GARAGE	360 Sq. Ft.
LOT AREA	10,849 Sq. Ft.
MAX COVERAGE (30%)	3,254 Sq. Ft.

LEGENE



### **EXISTING UNIT SIZE CALCULATION**

OTAL UNIT SIZE XIST. PERCENTAGE	2,345 Sq. Ft. 21.6%
1ST FLOOR A/C	1,985 Sq. Ft.
GARAGE (AFTER EXCLUDING 500 S.F.)	360 Sq. Ft.
LOT AREA	10,849 Sq. Ft.
MAX. UNIT SIZE (50%)	5,424 Sq. Ft.



JOSE L. SANCHEZ, AIA, L 278 NW 37TH ST MIAMI, FLORIDA 331 TEL: (305) 576-806 FAX: (305) 576-577 FL Lic: AR 0016966 FL Lic: AA 26000837

Client: MR. & MRS. OWADE

EXISTING LOT COVE./ UNIT SIZE

Revision	Date

EX-1

PROPERTY LINE - TYP. 150.0'



#### DEMOLITION NOTES

- 1. SCOPE OF DEMOLITION ENTAILS ENTIRE HOUSE.
- 2. REMOVE WALKWAYS, CONCRETE PATIO, DRIVES AND FENCES AS INDICATED ON PLANS.
- 3. MAINTAIN AND PROTECT ALL EXISTING TREES.

#### TREE PROTECTION NOTE


PROVIDE 8'X8' PROTECTION BARRIER FOR TREES LESS THAN 18"
IN DIAMETER AND 12'X12' PROTECTION BARRIER FOR TREES 18"
IN DIAMETER AND GREATER.

#### GENERAL DEMOLITION NOTES

OINT

AYNE

- CONTRACTOR SHALL NOTIFY ALL UTILITIES FOR PROPER DISCONNECTION PRIOR TO DEMOLITION ACTIVITIES.
- 2. CONTRACTOR SHALL PERFORM AND OBTAIN ALL PERMITS WITH CITY OF MIAMI BEACH & COMPLY WITH ALL NECESSARY REQUIREMENTS. CONTRACTOR SHALL PROVIDE NOTIFICATIONS AS REQUIRED AND COMPLY WITH LOCAL ORDINANCES.
- 3. CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY ACCIDENTAL DAMAGE TO ADJACENT PROPERTIES AND EXISTING ITEMS TO REMAIN. RESPONSIBILITY MEANS REPLACEMENT OF OR RESTORATION TO ORIGINAL CONDITION OF ANY DAMAGED ITEMS.
- 4. CONTRACTOR SHALL REMOVE ANY DECORATIVE ACCESSORIES AND LIGHT FIXTURES FROM WALLS, CEILINGS AND ELSEWHERE DIRECTED BY OWNER AND PROTECT SAME FROM POSSIBLE DAMAGE UNTIL INSPECTION FOR DISPOSITION IS MADE BY OWNER.
- 5. CONTRACTOR SHALL PERFORM INSECT/RODENT EXTERMINATION AS REQUIRED BY AUTHORITIES HAVING JURISDICTION.
- 6. CONDUCT OPERATIONS SO AS NOT INTERFERE WITH ADJACENT ROADS, STREETS DRIVES, WALKS, SERVICE LINES AND THE LIKE.
- 7. MAINTAIN BUILDING GROUNDS FREE FROM ACCUMULATION OF WASTE MATERIALS AND RUBBISH. DISPOSE ALL MATERIALS IMMEDIATELY AFTER DEMOLITION.
- 8. CONTRACTOR SHALL TAKE APPROPRIATE STEPS TO PREVENT AIRBORNE DUST TO SPREAD TO ADJACENT PROPERTIES. WATER SHALL BE APPLIED WHEREVER PRACTICAL TO SETTLE AND HOLD DUST TO A MINIMUM, PARTICULARLY DURING THE DEMOLITION & MOVING OF MATERIALS. PROVIDE DUMP CONTAINERS ON SITE FOR COLLECTION OF WASTE MATERIALS, RUBBISH AND DEBRIS FOR ALL TRADES.
- 9. UPON COMPLETION OF DEMOLITION WORK, LEAVE THE PROPERTY AND ADJACENT AREAS CLEAN AND SATISFACTORY TO LOCAL AUTHORITIES AND THE ARCHITECT. BESIDES THE REMOVAL OF WASTE MATERIALS. THE ENTIRE SPACE SHALL BE LEFT IN A "BROOM CLEAN" CONDITION, WITH THE COMPLETE REMOVAL OF ALL ACCUMULATIONS OF DUST FROM ANY REMAINING SURFACES, STRUCTURAL ELEMENTS OR OTHERWISE.
- 10. CONTRACTOR SHALL PERFORM ALL NECESSARY TESTING FOR ASBESTOS CONTAINING MATERIAL AND RETAIN A CERTIFIED ASBESTOS ABATEMENT COMPANY FOR REMOVAL OF ANY ASBESTOS CONTAINING MATERIAL PER STATE OF FLORIDA REGULATIONS.



COPYRIGHT © 2017 ALL RIGHTS RESERVED.

ESE DRAWINGS AND DOCUMENTS ARE INSTRUMENTS SERVICE AND SHALL REMAIN THE PROPERTY OF AXIS ARCHITECTURE + DESIGN, WHETHER THE OUJECT FOR WHICH THEY WERE PREPARED IS SECUTED OR NOT. THEY ARE NOT TO BE USED IN Y MANNER ON OTHER PROJECTS OR EXTENSIONS THIS PROJECT EXCEPT BY AGREEMENT IN WRITING D WITH THE APPROPRIATE COMPENSATION TO AWINGS & SPECIFICATIONS WITHOUT THE WRITTEN NISENT OF PRAXIS ARCHITECTURE + DESIGN. REPRODUCTIONS O AWINGS & SPECIFICATIONS WITHOUT THE WRITTEN NISENT OF PRAXIS ARCHITECTURE + DESIGN IS OHIBITED. CONTRACTORS RESPONSIBLE FOR REYNING ALL SITE CONDITIONS PRIOR TO OCCEDING WITH WORK.

() + <u>т</u> Ом Ом

SAYNE POINT

AMI BEACH, FLOF

Drawing Title

# DEMOLITION PLAN

Revisio	on	Date
Scale: As Shown Date 01-20-17		

Dwg: